# **QGIS Training Manual**

Release 2.18

**QGIS Project** 

| 1 | Johdatus kurssiin  1.1 Foreword  | 1 1 3          |
|---|--|----------------|
| 2 |  |                |
| 3 | Module: Creating a Basic Map  3.1 Lesson: Working with Vector Data  3.2 Lesson: Symbology  |                |
| 4 | Module: Classifying Vector Data 4.1 Lesson: Attribute Data   | 52             |
| 5 | Module: Creating Maps5.15.1 Lesson: Using Map Composer5.25.2 Assignment 110  |                |
| 6 | Module: Creating Vector Data166.1 Lesson: Creating a New Vector Dataset166.2 Lesson: Feature Topology16.3 Lesson: Forms126.4 Lesson: Actions12                       | 11<br>22       |
| 7 | Module: Vector Analysis147.1 Lesson: Reprojecting and Transforming Data127.2 Lesson: Vector Analysis137.3 Lesson: Network Analysis147.4 Lesson: Spatial Statistics15 | 47<br>56<br>73 |
| 8 | Module: Rasters268.1 Lesson: Working with Raster Data208.2 Lesson: Changing Raster Symbology208.3 Lesson: Terrain Analysis2  | 09             |
| 9 | Module: Completing the Analysis229.1 Lesson: Raster to Vector Conversion229.2 Lesson: Combining the Analyses239.3 Assignment25                                       | 32             |

|    | 9.4   | Lesson: Supplementary Exercise  | 233   |
|----|---|---|---|
| 10 | Mod   | ule: Plugins  | 247   |
|    |   | Lesson: Installing and Managing Plugins   |   |
|    |   | Lesson: Useful QGIS Plugins   |   |
|    |   |   |   |
| 11 |   |   | 261   |
|    | 11.1  | Lesson: Web Mapping Services  | 261   |
|    | 11.2  | Lesson: Web Feature Services  | 270   |
|    |   |   |   |
| 12 |   |   | 279   |
|    |   | Lesson: Install QGIS Server   |   |
|    | 12.2  | Lesson: Serving WMS   | 283   |
| 12 | N T . J.  | J., CDACC   | ٠   |
| 13 |   | ule: GRASS Lesson: GRASS Setup  | 295   |
|    |   | 1   |   |
|    | 13.2  | Lesson: GRASS Tools   | 500   |
| 14 | Mod   | ule: Assessment   | 315   |
| 14 |   | Create a base map   |   |
|    |   | Analyze the data  |   |
|    |   | Final Map   |   |
|    | 17.5  | Timat Map   | 111   |
| 15 | Mod   | ule: Metsänhoidon sovellus  | 319   |
|    |   | Lesson: Metsänhoitomodulin esittely   | 319   |
|    |   | Lesson: Kartan georeferointi  |   |
|    |   | Lesson: Metsäkuvioiden digitointi   |   |
|    |   | Lesson: Metsäkuvioiden päivittäminen  |   |
|    |   | Lesson: Järjestelmällinen näytteenottosuunnitelma   |   |
|    |   | Lesson: Yksityiskohtaisten karttojen luominen Atlas työkalua käyttäen   |   |
|    |   | Lesson: Metsän parametrien laskenta   |   |
|    |   | Lesson: DEM from LiDAR Data   |   |
|    |   | Lesson: Karttaesitys  |   |
|    |   |   |   |
| 16 |   | ule: Database Concepts with PostgreSQL  |   |
|    |   |   | 395   |
|    |   | Lesson: Introduction to Databases   | 395   |
|    | 16.2  | Lesson: Implementing the Data Model   | 395<br>400  |
|    | 16.2<br>16.3  | Lesson: Implementing the Data Model   | 395<br>100<br>105   |
|    | 16.2<br>16.3<br>16.4  | Lesson: Implementing the Data Model   | 395<br>400<br>405<br>407  |
|    | 16.2<br>16.3<br>16.4<br>16.5  | Lesson: Implementing the Data Model  Lesson: Adding Data to the Model  Lesson: Queries  Lesson: Views   | 395<br>400<br>405<br>407<br>411   |
|    | 16.2<br>16.3<br>16.4<br>16.5  | Lesson: Implementing the Data Model   | 395<br>400<br>405<br>407<br>411   |
| 15 | 16.2<br>16.3<br>16.4<br>16.5<br>16.6  | Lesson: Implementing the Data Model Lesson: Adding Data to the Model Lesson: Queries Lesson: Views Lesson: Rules  | 395<br>400<br>405<br>407<br>411<br>412  |
| 17 | 16.2<br>16.3<br>16.4<br>16.5<br>16.6<br><b>Mod</b>  | Lesson: Implementing the Data Model  Lesson: Adding Data to the Model  Lesson: Queries  Lesson: Views  Lesson: Rules  Alle: Spatial Database Concepts with PostGIS  | 395<br>400<br>405<br>407<br>411<br>412  |
| 17 | 16.2<br>16.3<br>16.4<br>16.5<br>16.6<br><b>Mode</b><br>17.1   | Lesson: Implementing the Data Model  Lesson: Adding Data to the Model  Lesson: Queries  Lesson: Views  Lesson: Rules  Alle: Spatial Database Concepts with PostGIS  Lesson: PostGIS Setup   | 395<br>400<br>405<br>407<br>411<br>412<br><b>415</b>  |
| 17 | 16.2<br>16.3<br>16.4<br>16.5<br>16.6<br><b>Mod</b><br>17.1<br>17.2  | Lesson: Implementing the Data Model  Lesson: Adding Data to the Model  Lesson: Queries  Lesson: Views  Lesson: Rules  Ale: Spatial Database Concepts with PostGIS  Lesson: PostGIS Setup  Lesson: Simple Feature Model  | 395<br>400<br>405<br>407<br>411<br>412<br><b>415</b><br>418   |
| 17 | 16.2<br>16.3<br>16.4<br>16.5<br>16.6<br><b>Mode</b><br>17.1<br>17.2<br>17.3   | Lesson: Implementing the Data Model  Lesson: Adding Data to the Model  Lesson: Queries  Lesson: Views  Lesson: Rules  Alle: Spatial Database Concepts with PostGIS  Lesson: PostGIS Setup  Lesson: Simple Feature Model  Lesson: Import and Export  | 395<br>400<br>405<br>407<br>411<br>412<br><b>415</b><br>418<br>423  |
| 17 | 16.2<br>16.3<br>16.4<br>16.5<br>16.6<br><b>Mod</b><br>17.1<br>17.2<br>17.3<br>17.4  | Lesson: Implementing the Data Model  Lesson: Adding Data to the Model  Lesson: Queries  Lesson: Views  Lesson: Rules  Alle: Spatial Database Concepts with PostGIS  Lesson: PostGIS Setup  Lesson: Simple Feature Model  Lesson: Import and Export  Lesson: Spatial Queries   | 395<br>400<br>405<br>407<br>411<br>412<br>415<br>418<br>423<br>424  |
| 17 | 16.2<br>16.3<br>16.4<br>16.5<br>16.6<br><b>Mod</b><br>17.1<br>17.2<br>17.3<br>17.4  | Lesson: Implementing the Data Model  Lesson: Adding Data to the Model  Lesson: Queries  Lesson: Views  Lesson: Rules  Alle: Spatial Database Concepts with PostGIS  Lesson: PostGIS Setup  Lesson: Simple Feature Model  Lesson: Import and Export  | 395<br>400<br>405<br>407<br>411<br>412<br>415<br>418<br>423<br>424  |
|    | 16.2<br>16.3<br>16.4<br>16.5<br>16.6<br><b>Mode</b><br>17.1<br>17.2<br>17.3<br>17.4<br>17.5   | Lesson: Implementing the Data Model Lesson: Adding Data to the Model Lesson: Queries Lesson: Views Lesson: Rules  Alle: Spatial Database Concepts with PostGIS Lesson: PostGIS Setup Lesson: Simple Feature Model Lesson: Import and Export Lesson: Spatial Queries Lesson: Geometry Construction   | 395<br>400<br>405<br>407<br>411<br>412<br>415<br>415<br>418<br>423<br>424<br>432  |
|    | 16.2<br>16.3<br>16.4<br>16.5<br>16.6<br><b>Mode</b><br>17.1<br>17.2<br>17.3<br>17.4<br>17.5   | Lesson: Implementing the Data Model Lesson: Adding Data to the Model Lesson: Queries Lesson: Views Lesson: Rules  Lesson: Rules  Lesson: PostGIS Setup Lesson: Simple Feature Model Lesson: Import and Export Lesson: Spatial Queries Lesson: Geometry Construction  QGIS processing guide  | 395<br>400<br>405<br>407<br>411<br>412<br><b>415</b><br>418<br>423<br>424<br>432  |
|    | 16.2<br>16.3<br>16.4<br>16.5<br>16.6<br><b>Mode</b><br>17.1<br>17.2<br>17.3<br>17.4<br>17.5<br><b>The</b> (   | Lesson: Implementing the Data Model Lesson: Adding Data to the Model Lesson: Queries Lesson: Views Lesson: Rules  Lesson: Rules  Lesson: PostGIS Setup Lesson: Simple Feature Model Lesson: Import and Export Lesson: Spatial Queries Lesson: Geometry Construction  QGIS processing guide Introduction   | 395<br>400<br>405<br>407<br>411<br>412<br><b>415</b><br>418<br>423<br>432<br><b>439</b>   |
|    | 16.2<br>16.3<br>16.4<br>16.5<br>16.6<br><b>Mode</b><br>17.1<br>17.2<br>17.3<br>17.4<br>17.5<br><b>The</b> 0<br>18.1<br>18.2   | Lesson: Implementing the Data Model Lesson: Adding Data to the Model Lesson: Queries Lesson: Views Lesson: Rules  Alle: Spatial Database Concepts with PostGIS Lesson: PostGIS Setup Lesson: Simple Feature Model Lesson: Import and Export Lesson: Spatial Queries Lesson: Geometry Construction  QGIS processing guide Introduction An important warning before starting  | 395<br>400<br>405<br>407<br>411<br>412<br><b>415</b><br>413<br>424<br>432<br><b>439</b><br>439                                    |
|    | 16.2<br>16.3<br>16.4<br>16.5<br>16.6<br><b>Mode</b><br>17.1<br>17.2<br>17.3<br>17.4<br>17.5<br><b>The</b> (18.1<br>18.2<br>18.3                                     | Lesson: Implementing the Data Model Lesson: Adding Data to the Model Lesson: Queries Lesson: Views Lesson: Rules  Alle: Spatial Database Concepts with PostGIS Lesson: PostGIS Setup Lesson: Simple Feature Model Lesson: Import and Export Lesson: Spatial Queries Lesson: Geometry Construction  An important warning before starting Setting-up the processing framework  An important warning before starting Setting-up the processing framework   | 395<br>400<br>405<br>407<br>411<br>412<br><b>415</b><br>418<br>424<br>432<br><b>439</b><br>439                                    |
|    | 16.2<br>16.3<br>16.4<br>16.5<br>16.6<br><b>Mode</b><br>17.1<br>17.2<br>17.3<br>17.4<br>17.5<br><b>The</b> (18.1<br>18.2<br>18.3<br>18.4                             | Lesson: Implementing the Data Model Lesson: Adding Data to the Model Lesson: Queries Lesson: Views Lesson: Rules  Lesson: Rules  Lesson: Rules  Lesson: PostGIS Setup Lesson: Simple Feature Model Lesson: Import and Export Lesson: Spatial Queries Lesson: Geometry Construction  QGIS processing guide Introduction An important warning before starting Setting-up the processing framework Running our first algorithm. The toolbox  | 395<br>400<br>405<br>407<br>411<br>412<br><b>415</b><br>418<br>424<br>432<br><b>439</b><br>439<br>441                             |
|    | 16.2<br>16.3<br>16.4<br>16.5<br>16.6<br><b>Mode</b><br>17.1<br>17.2<br>17.3<br>17.4<br>17.5<br><b>The</b> 0<br>18.1<br>18.2<br>18.3<br>18.4<br>18.5                 | Lesson: Implementing the Data Model Lesson: Adding Data to the Model Lesson: Queries Lesson: Views Lesson: Rules  Lesson: Rules  Lesson: Rules  Lesson: PostGIS Setup Lesson: Simple Feature Model Lesson: Import and Export Lesson: Spatial Queries Lesson: Geometry Construction  QGIS processing guide Introduction An important warning before starting Setting-up the processing framework Running our first algorithm. The toolbox More algorithms and data types   | 395<br>400<br>405<br>407<br>411<br>412<br><b>415</b><br>418<br>424<br>432<br><b>439</b><br>439<br>441<br>442<br>445               |
|    | 16.2<br>16.3<br>16.4<br>16.5<br>16.6<br><b>Mode</b><br>17.1<br>17.2<br>17.3<br>17.4<br>17.5<br><b>The</b> 0<br>18.1<br>18.2<br>18.3<br>18.4<br>18.5<br>18.6         | Lesson: Implementing the Data Model Lesson: Adding Data to the Model Lesson: Queries Lesson: Views Lesson: Rules  Alle: Spatial Database Concepts with PostGIS Lesson: PostGIS Setup Lesson: Simple Feature Model Lesson: Import and Export Lesson: Spatial Queries Lesson: Spatial Queries Lesson: Geometry Construction  QGIS processing guide Introduction An important warning before starting Setting-up the processing framework Running our first algorithm. The toolbox More algorithms and data types CRSs. Reprojecting                 | 395<br>400<br>405<br>407<br>411<br>412<br><b>415</b><br>415<br>413<br>424<br>432<br>439<br>439<br>441<br>442<br>445<br>445        |
|    | 16.2<br>16.3<br>16.4<br>16.5<br>16.6<br><b>Mode</b><br>17.1<br>17.2<br>17.3<br>17.4<br>17.5<br><b>The</b> 0<br>18.1<br>18.2<br>18.3<br>18.4<br>18.5<br>18.6<br>18.7 | Lesson: Implementing the Data Model Lesson: Adding Data to the Model Lesson: Queries Lesson: Views Lesson: Rules  de: Spatial Database Concepts with PostGIS Lesson: PostGIS Setup Lesson: Simple Feature Model Lesson: Import and Export Lesson: Spatial Queries Lesson: Geometry Construction  QGIS processing guide Introduction An important warning before starting Setting-up the processing framework Running our first algorithm. The toolbox More algorithms and data types CRSs. Reprojecting Selection                                 | 395<br>400<br>405<br>407<br>411<br>412<br><b>415</b><br>415<br>413<br>424<br>439<br>439<br>439<br>441<br>445<br>452               |
|    | 16.2<br>16.3<br>16.4<br>16.5<br>16.6<br>Mode<br>17.1<br>17.2<br>17.3<br>17.4<br>17.5<br>The 0<br>18.1<br>18.2<br>18.3<br>18.4<br>18.5<br>18.6<br>18.7               | Lesson: Implementing the Data Model Lesson: Adding Data to the Model Lesson: Queries Lesson: Views Lesson: Rules  Alle: Spatial Database Concepts with PostGIS Lesson: PostGIS Setup Lesson: Simple Feature Model Lesson: Import and Export Lesson: Spatial Queries Lesson: Geometry Construction  QGIS processing guide Introduction An important warning before starting Setting-up the processing framework Running our first algorithm. The toolbox More algorithms and data types CRSs. Reprojecting Selection Running an external algorithm | 395<br>400<br>405<br>407<br>411<br>412<br><b>415</b><br>415<br>413<br>424<br>432<br>439<br>439<br>441<br>445<br>455<br>457        |
|    | 16.2<br>16.3<br>16.4<br>16.5<br>16.6<br>Mode<br>17.1<br>17.2<br>17.3<br>17.4<br>17.5<br>The C<br>18.1<br>18.2<br>18.3<br>18.4<br>18.5<br>18.6<br>18.7<br>18.8       | Lesson: Implementing the Data Model Lesson: Adding Data to the Model Lesson: Queries Lesson: Views Lesson: Rules  de: Spatial Database Concepts with PostGIS Lesson: PostGIS Setup Lesson: Simple Feature Model Lesson: Import and Export Lesson: Spatial Queries Lesson: Geometry Construction  QGIS processing guide Introduction An important warning before starting Setting-up the processing framework Running our first algorithm. The toolbox More algorithms and data types CRSs. Reprojecting Selection                                 | 395<br>400<br>405<br>407<br>411<br>412<br><b>415</b><br>418<br>424<br>432<br><b>439</b><br>439<br>441<br>445<br>455<br>457<br>462 |

|    |   | Vector calculator   |  |
|----|---|---|--|
|    | 18.12   | Defining extents  | 472  |
|    | 18.13   | HTML outputs  | 476  |
|    | 18.14   | First analysis example  | 478  |
|    | 18.15   | Clipping and merging raster layers  | 487  |
|    |   | Hydrological analysis   |  |
|    |   | Starting with the graphical modeler   |  |
|    |   | More complex models   |  |
|    |   | Numeric calculations in the modeler   |  |
|    |   |   |  |
|    |   | A model within a model  |  |
|    |   | Using modeler-only tools for creating a model   |  |
|    |   | Interpolation   |  |
|    |   | More interpolation  |  |
|    | 18.24   | Iterative execution of algorithms   | 547  |
|    | 18.25   | More iterative execution of algorithms  | 552  |
|    |   | The batch processing interface  |  |
|    |   | Models in the batch processing interface  |  |
|    |   | Pre- and post-execution script hooks  |  |
|    |   |   |  |
|    |   | Other programs  |  |
|    |   | Interpolation and contouring  |  |
|    |   | Vector simplification and smoothing   |  |
|    |   | Planning a solar farm   |  |
|    | 18.33   | Use R scripts in Processing   | 562  |
|    | 18.34   | R Syntax in Processing scripts  | 571  |
|    |   | R Syntax Summary table for Processing   |  |
|    |   | Predicting landslides   |  |
|    | 10.50   | Treatening landshace  | 0,0  |
| 19 | Modu  | ile: Using Spatial Databases in QGIS  | 577  |
|    |   | Lesson: Working with Databases in the QGIS Browser  |  |
|    |   |   |  |
|    |   | Leccon: Heing DR Manager to work with Spatial Databases in OGIS   |  |
|    |   | Lesson: Using DB Manager to work with Spatial Databases in QGIS   |  |
|    |   | Lesson: Using DB Manager to work with Spatial Databases in QGIS   |  |
| 20 | 19.3  | Lesson: Working with spatialite databases in QGIS   | 593  |
| 20 | 19.3<br><b>Appe</b> r   | Lesson: Working with spatialite databases in QGIS   | 593<br><b>597</b>  |
| 20 | 19.3<br><b>Apper</b> 20.1   | Lesson: Working with spatialite databases in QGIS   | 593<br><b>597</b><br>597   |
| 20 | 19.3<br>Apper<br>20.1<br>20.2   | Lesson: Working with spatialite databases in QGIS   | 593<br><b>597</b><br>597<br>597  |
| 20 | 19.3<br>Apper<br>20.1<br>20.2<br>20.3   | Lesson: Working with spatialite databases in QGIS   | 593<br><b>597</b><br>597<br>597<br>597   |
| 20 | 19.3<br>Apper<br>20.1<br>20.2<br>20.3<br>20.4   | Lesson: Working with spatialite databases in QGIS  ndix: Contributing To This Manual  Downloading Resources  Manual Format  Adding a Module  Adding a Lesson  | 593<br><b>597</b><br>597<br>597<br>597   |
| 20 | 19.3<br>Apper<br>20.1<br>20.2<br>20.3<br>20.4   | Lesson: Working with spatialite databases in QGIS   | 593<br><b>597</b><br>597<br>597<br>597   |
| 20 | 19.3<br>Apper<br>20.1<br>20.2<br>20.3<br>20.4<br>20.5   | Lesson: Working with spatialite databases in QGIS  ndix: Contributing To This Manual  Downloading Resources  Manual Format  Adding a Module  Adding a Lesson  | 593<br><b>597</b><br>597<br>597<br>597<br>598  |
| 20 | Apper<br>20.1<br>20.2<br>20.3<br>20.4<br>20.5<br>20.6   | Lesson: Working with spatialite databases in QGIS  ndix: Contributing To This Manual  Downloading Resources  Manual Format  Adding a Module  Adding a Lesson  Adding a Section  Add a Conclusion  | 593<br><b>597</b><br>597<br>597<br>598<br>599<br>600   |
| 20 | Apper<br>20.1<br>20.2<br>20.3<br>20.4<br>20.5<br>20.6<br>20.7   | Lesson: Working with spatialite databases in QGIS  ndix: Contributing To This Manual  Downloading Resources  Manual Format  Adding a Module  Adding a Lesson  Adding a Section  Add a Conclusion  Add a Further Reading Section   | 593<br>597<br>597<br>597<br>598<br>599<br>600  |
| 20 | 19.3<br><b>Apper</b> 20.1<br>20.2<br>20.3<br>20.4<br>20.5<br>20.6<br>20.7<br>20.8   | Lesson: Working with spatialite databases in QGIS  ndix: Contributing To This Manual  Downloading Resources  Manual Format  Adding a Module  Adding a Lesson  Adding a Section  Add a Conclusion  Add a Further Reading Section  Add a What's Next Section  | 593<br>597<br>597<br>597<br>598<br>599<br>600<br>600   |
| 20 | 19.3<br><b>Apper</b> 20.1 20.2 20.3 20.4 20.5 20.6 20.7 20.8 20.9   | Lesson: Working with spatialite databases in QGIS  ndix: Contributing To This Manual  Downloading Resources  Manual Format  Adding a Module  Adding a Lesson  Adding a Section  Add a Conclusion  Add a Further Reading Section  Add a What's Next Section  Using Markup  | 593<br>597<br>597<br>597<br>598<br>599<br>600<br>600<br>600  |
| 20 | 19.3<br><b>Apper</b> 20.1 20.2 20.3 20.4 20.5 20.6 20.7 20.8 20.9   | Lesson: Working with spatialite databases in QGIS  ndix: Contributing To This Manual  Downloading Resources  Manual Format  Adding a Module  Adding a Lesson  Adding a Section  Add a Conclusion  Add a Further Reading Section  Add a What's Next Section  | 593<br>597<br>597<br>597<br>598<br>599<br>600<br>600<br>600  |
|    | 19.3 <b>Apper</b> 20.1 20.2 20.3 20.4 20.5 20.6 20.7 20.8 20.9 20.10  | Lesson: Working with spatialite databases in QGIS  ndix: Contributing To This Manual  Downloading Resources  Manual Format  Adding a Module  Adding a Lesson  Adding a Section  Add a Conclusion  Add a Further Reading Section  Add a What's Next Section  Using Markup  Thank You!  | 593<br>597<br>597<br>597<br>597<br>598<br>600<br>600<br>600<br>600   |
|    | 19.3  Apper 20.1 20.2 20.3 20.4 20.5 20.6 20.7 20.8 20.9 20.10  Answ  | Lesson: Working with spatialite databases in QGIS  ndix: Contributing To This Manual  Downloading Resources  Manual Format  Adding a Module  Adding a Lesson  Adding a Section  Add a Conclusion  Add a Further Reading Section  Add a What's Next Section  Using Markup  Thank You!  | 593<br>597<br>597<br>597<br>597<br>598<br>600<br>600<br>600<br>602   |
|    | 19.3 <b>Appe</b> 20.1 20.2 20.3 20.4 20.5 20.6 20.7 20.8 20.9 20.10 <b>Answ</b> 21.1  | Lesson: Working with spatialite databases in QGIS  ndix: Contributing To This Manual  Downloading Resources  Manual Format  Adding a Module  Adding a Lesson  Adding a Section  Add a Conclusion  Add a Further Reading Section  Add a What's Next Section  Using Markup  Thank You!  er Sheet  Results For Adding Your First Layer   | 593<br>597<br>597<br>597<br>598<br>599<br>600<br>600<br>600<br>602<br><b>603</b>   |
|    | 19.3 <b>Appe</b> 20.1 20.2 20.3 20.4 20.5 20.6 20.7 20.8 20.9 20.10 <b>Answ</b> 21.1 21.2   | Lesson: Working with spatialite databases in QGIS  ndix: Contributing To This Manual  Downloading Resources  Manual Format  Adding a Module  Adding a Lesson  Adding a Section  Add a Conclusion  Add a Further Reading Section  Add a What's Next Section  Using Markup  Thank You!  cer Sheet  Results For Adding Your First Layer  Results For An Overview of the Interface  | 593<br>597<br>597<br>597<br>598<br>599<br>600<br>600<br>600<br>603<br>603<br>603   |
|    | 19.3 <b>Apper</b> 20.1 20.2 20.3 20.4 20.5 20.6 20.7 20.8 20.9 20.10 <b>Answ</b> 21.1 21.2 21.3   | Lesson: Working with spatialite databases in QGIS  ndix: Contributing To This Manual  Downloading Resources  Manual Format  Adding a Module  Adding a Lesson  Adding a Section  Add a Conclusion  Add a Further Reading Section  Add a What's Next Section  Using Markup  Thank You!  er Sheet  Results For Adding Your First Layer  Results For An Overview of the Interface  Results For Working with Vector Data   | 593<br>597<br>597<br>597<br>598<br>600<br>600<br>600<br>603<br>603<br>603  |
|    | 19.3 <b>Apper</b> 20.1 20.2 20.3 20.4 20.5 20.6 20.7 20.8 20.9 20.10 <b>Answ</b> 21.1 21.2 21.3   | Lesson: Working with spatialite databases in QGIS  ndix: Contributing To This Manual  Downloading Resources  Manual Format  Adding a Module  Adding a Lesson  Adding a Section  Add a Conclusion  Add a Further Reading Section  Add a What's Next Section  Using Markup  Thank You!  cer Sheet  Results For Adding Your First Layer  Results For An Overview of the Interface  | 593<br>597<br>597<br>597<br>598<br>600<br>600<br>600<br>603<br>603<br>603  |
|    | 19.3 <b>Appe</b> 20.1 20.2 20.3 20.4 20.5 20.6 20.7 20.8 20.9 20.10 <b>Answ</b> 21.1 21.2 21.3 21.4   | Lesson: Working with spatialite databases in QGIS  ndix: Contributing To This Manual  Downloading Resources  Manual Format  Adding a Module  Adding a Lesson  Adding a Section  Add a Conclusion  Add a Further Reading Section  Add a What's Next Section  Using Markup  Thank You!  er Sheet  Results For Adding Your First Layer  Results For An Overview of the Interface  Results For Working with Vector Data   | 593<br>597<br>597<br>597<br>597<br>598<br>600<br>600<br>600<br>603<br>603<br>603<br>603                                    |
|    | 19.3 <b>Appe</b> 20.1 20.2 20.3 20.4 20.5 20.6 20.7 20.8 20.9 20.10 <b>Answ</b> 21.1 21.2 21.3 21.4 21.5  | Lesson: Working with spatialite databases in QGIS  ndix: Contributing To This Manual  Downloading Resources  Manual Format  Adding a Module  Adding a Lesson  Adding a Section  Add a Conclusion  Add a Further Reading Section  Add a What's Next Section  Using Markup  Thank You!  cer Sheet  Results For Adding Your First Layer  Results For An Overview of the Interface  Results For Working with Vector Data  Results For Symbology   | 593<br>597<br>597<br>597<br>598<br>598<br>600<br>600<br>600<br>603<br>603<br>603<br>603<br>604                             |
|    | 19.3 <b>Appe</b> 20.1 20.2 20.3 20.4 20.5 20.6 20.7 20.8 20.9 20.10 <b>Answ</b> 21.1 21.2 21.3 21.4 21.5 21.6                                   | Lesson: Working with spatialite databases in QGIS  ndix: Contributing To This Manual  Downloading Resources  Manual Format  Adding a Module  Adding a Lesson  Adding a Section  Add a Conclusion  Add a Further Reading Section  Add a What's Next Section  Using Markup  Thank You!  er Sheet  Results For Adding Your First Layer  Results For An Overview of the Interface  Results For Symbology  Results For Attribute Data  Results For The Label Tool  | 593<br>597<br>597<br>597<br>598<br>599<br>600<br>600<br>600<br>603<br>603<br>603<br>604<br>609                             |
|    | 19.3 <b>Apper</b> 20.1 20.2 20.3 20.4 20.5 20.6 20.7 20.8 20.9 20.10 <b>Answ</b> 21.1 21.2 21.3 21.4 21.5 21.6 21.7                             | Lesson: Working with spatialite databases in QGIS  ndix: Contributing To This Manual  Downloading Resources  Manual Format  Adding a Module  Adding a Lesson  Adding a Section  Add a Conclusion  Add a Further Reading Section  Add a What's Next Section  Using Markup  Thank You!  er Sheet  Results For Adding Your First Layer  Results For An Overview of the Interface  Results For Symbology  Results For Attribute Data  Results For The Label Tool  Results For Classification  | 593<br>597<br>597<br>597<br>597<br>598<br>599<br>600<br>600<br>600<br>603<br>603<br>603<br>603<br>604<br>609<br>610<br>614 |
|    | 19.3 <b>Appe</b> 20.1 20.2 20.3 20.4 20.5 20.6 20.7 20.8 20.9 20.10 <b>Answ</b> 21.1 21.2 21.3 21.4 21.5 21.6 21.7 21.8                         | Lesson: Working with spatialite databases in QGIS  ndix: Contributing To This Manual  Downloading Resources  Manual Format  Adding a Module  Adding a Lesson  Adding a Section  Add a Conclusion  Add a Further Reading Section  Add a What's Next Section  Using Markup  Thank You!  er Sheet  Results For Adding Your First Layer  Results For An Overview of the Interface  Results For Symbology  Results For Attribute Data  Results For Attribute Data  Results For The Label Tool  Results For Classification  Results For Creating a New Vector Dataset   | 593<br>597<br>597<br>597<br>597<br>598<br>599<br>600<br>600<br>600<br>603<br>603<br>603<br>604<br>609<br>614<br>615        |
|    | 19.3 <b>Apper</b> 20.1 20.2 20.3 20.4 20.5 20.6 20.7 20.8 20.9 20.10 <b>Answ</b> 21.1 21.2 21.3 21.4 21.5 21.6 21.7 21.8 21.9                   | Lesson: Working with spatialite databases in QGIS  Indix: Contributing To This Manual Downloading Resources Manual Format Adding a Module Adding a Module Adding a Lesson Adding a Section Add a Conclusion Add a Further Reading Section Add a Further Reading Section Using Markup Thank You!  Indicate the Section | 593 597 597 597 597 598 599 600 600 600 603 603 603 604 615 619  |
|    | 19.3 <b>Appe</b> 20.1 20.2 20.3 20.4 20.5 20.6 20.7 20.8 20.9 20.10 <b>Answ</b> 21.1 21.2 21.3 21.4 21.5 21.6 21.7 21.8 21.9 21.10              | Lesson: Working with spatialite databases in QGIS  ndix: Contributing To This Manual  Downloading Resources  Manual Format  Adding a Rodule  Adding a Lesson  Adding a Section  Add a Conclusion  Add a Further Reading Section  Add a What's Next Section  Using Markup  Thank You!  er Sheet  Results For Adding Your First Layer  Results For An Overview of the Interface  Results For Working with Vector Data  Results For Attribute Data  Results For The Label Tool  Results For Classification  Results For Creating a New Vector Dataset  Results For Vector Analysis  Results For Vector Analysis  | 593 597 597 597 597 597 598 600 600 600 603 603 603 604 615 619 630  |
|    | 19.3 <b>Appe</b> 20.1 20.2 20.3 20.4 20.5 20.6 20.7 20.8 20.9 20.10 <b>Answ</b> 21.1 21.2 21.3 21.4 21.5 21.6 21.7 21.8 21.9 21.10 21.11        | Lesson: Working with spatialite databases in QGIS  ndix: Contributing To This Manual  Downloading Resources  Manual Format  Adding a Module  Adding a Lesson  Adding a Section  Add a Conclusion  Add a Further Reading Section  Add a What's Next Section  Using Markup  Thank You!  er Sheet  Results For Adding Your First Layer  Results For An Overview of the Interface  Results For Symbology  Results For Attribute Data  Results For The Label Tool  Results For Classification  Results For Creating a New Vector Dataset  Results For Vector Analysis  Results For Raster Analysis  Results For Raster Analysis  Results For Completing the Analysis   | 593 597 597 597 597 597 598 600 600 600 600 603 603 604 615 619 630 635  |
|    | 19.3 <b>Appe</b> 20.1 20.2 20.3 20.4 20.5 20.6 20.7 20.8 20.9 20.10 <b>Answ</b> 21.1 21.2 21.3 21.4 21.5 21.6 21.7 21.8 21.9 21.110 21.11       | Lesson: Working with spatialite databases in QGIS  ndix: Contributing To This Manual  Downloading Resources  Manual Format  Adding a Module  Adding a Lesson  Adding a Section  Add a Conclusion  Add a Further Reading Section  Add a What's Next Section  Using Markup  Thank You!  er Sheet  Results For Adding Your First Layer  Results For An Overview of the Interface  Results For Working with Vector Data  Results For Attribute Data  Results For The Label Tool  Results For Creating a New Vector Dataset  Results For Vector Analysis  Results For Raster Analysis  Results For Completing the Analysis  | 593 597 597 597 597 597 598 600 600 600 600 603 603 603 604 619 630 635 641  |
|    | 19.3 <b>Apper</b> 20.1 20.2 20.3 20.4 20.5 20.6 20.7 20.8 20.9 20.10 <b>Answ</b> 21.1 21.2 21.3 21.4 21.5 21.6 21.7 21.8 21.9 21.11 21.12 21.13 | Lesson: Working with spatialite databases in QGIS  ndix: Contributing To This Manual  Downloading Resources  Manual Format  Adding a Module  Adding a Lesson  Adding a Section  Add a Conclusion  Add a Further Reading Section  Add a What's Next Section  Using Markup  Thank You!  er Sheet  Results For Adding Your First Layer  Results For An Overview of the Interface  Results For Symbology  Results For Attribute Data  Results For The Label Tool  Results For Classification  Results For Creating a New Vector Dataset  Results For Vector Analysis  Results For Raster Analysis  Results For Raster Analysis  Results For Completing the Analysis   | 593 597 597 597 597 597 598 600 600 600 600 603 603 603 603 604 619 630 635 641 644  |

| 22 | Indeksit ja taulut                      | 65 | 51         |
|----|---|----|------------|
|    | 21.16 Results For Simple Feature Model  | 64 | 18         |
|    | 21.15 Results For Geometry Construction | 64 | <b>‡</b> 7 |

#### Johdatus kurssiin

#### 1.1 Foreword

#### 1.1.1 Background

In 2008 we launched the *Gentle Introduction to GIS*, a completely free, open content resource for people who want to learn about GIS without being overloaded with jargon and new terminology. It was sponsored by the South African government and has been a phenomenal success, with people all over the world writing to us to tell us how they are using the materials to run University Training Courses, teach themselves GIS and so on. The Gentle Introduction is not a software tutorial, but rather aims to be a generic text (although we used QGIS in all examples) for someone learning about GIS. There is also the QGIS manual which provides a detailed functional overview of the QGIS application. However, it is not structured as a tutorial, but rather as a reference guide. At Linfiniti Consulting CC. we frequently run training courses and have realised that a third resource is needed - one that leads the reader sequentially through learning the key aspects of QGIS in a trainer-trainee format - which prompted us to produce this work.

This training manual is intended to provide all the materials needed to run a 5 day course on QGIS, PostgreSQL and PostGIS. The course is structured with content to suit novice, intermediate and advanced users alike and has many exercises complete with annotated answers throughout the text.

#### 1.1.2 License



The Free Quantum GIS Training Manual by Linfiniti Consulting CC. is based on an earlier version from Linfiniti and is licensed under a Creative Commons Attribution 4.0 International. Permissions beyond the scope of this license may be available at below.

We have published this QGIS training manual under a liberal license that allows you to freely copy, modify and redistribute this work. A complete copy of the license is available at the end of this document. In simple terms, the usage guidelines are as follows:

- You may not represent this work as your own work, or remove any authorship text or credits from this work.
- You may not redistribute this work under more restrictive permissions than those under which it was provided to you.
- If you add a substantive portion to the work and contribute it back to the project (at least one complete module) you may add your name to the end of the authors list for this document (which will appear on the front page)
- If you contribute minor changes and corrections you may add yourself to the contributors list below.

- If you translate this document in its entirety, you may add your name to the authors list in the form "Translated by Joe Bloggs".
- If you sponsor a module or lesson, you may request the author to include an acknowledgement in the beginning of each lesson contributed, e.g.:

Muista: This lesson was sponsored by MegaCorp.

- If you are unsure about what you may do under this license, please contact us at office@linfiniti.com and we will advise you if what you intend doing is acceptable.
- If you publish this work under a self publishing site such as http://lulu.com we request that you donate the profits to the QGIS project.
- You may not commercialise this work, except with the expressed permission of the authors. To be clear, by commercialisation we mean that you may not sell for profit, create commercial derivative works (e.g. selling content for use as articles in a magazine). The exception to this is if all the profits are given to the QGIS project. You may (and we encourage you to do so) use this work as a text book when conducting training courses, even if the course itself is commercial in nature. In other words, you are welcome to make money by running a training course that uses this work as a text book, but you may not profit off the sales of the book itself all such profits should be contributed back to QGIS.

#### 1.1.3 Sponsoring Chapters

This work is by no means a complete treatise on all the things you can do with QGIS and we encourage others to add new materials to fill any gaps. Linfiniti Consulting CC. can also create additional materials for you as a commercial service, with the understanding that all such works produced should become part of the core content and be published under the same license.

#### 1.1.4 Authors

- Rüdiger Thiede (rudi@linfiniti.com) Rudi has written the QGIS instructional materials and parts of the PostGIS materials.
- Tim Sutton (tim@linfiniti.com) Tim has overseen and guided the project and co-authored the PostgreSQL and PostGIS parts. Tim also authored the custom sphinx theme used for this manual.
- Horst Düster (horst.duester@kappasys.ch ) Horst co-authored the PostgreSQL and PostGIS parts
- Marcelle Sutton (marcelle@linfiniti.com) Marcelle provided proof-reading and editorial advice during the creation of this work.

#### 1.1.5 Individual Contributors

Your name here!

#### 1.1.6 Sponsors

Cape Peninsula University of Technology

#### 1.1.7 Data

**Muista:** The sample data used throughout the manual can be downloaded here: https://github.com/qgis/QGIS-Training-Data/archive/QGIS-Training-Data-v1.0.zip. You can save the files in a folder named **exercise\_data**.

The sample data that accompanies this resource is freely available and comes from the following sources:

- Streets and Places datasets from OpenStreetMap (http://www.openstreetmap.org/)
- Property boundaries (urban and rural), water bodies from NGI (http://www.ngi.gov.za/)
- SRTM DEM from the CGIAR-CGI (http://srtm.csi.cgiar.org/)

#### 1.1.8 Source files and Issue reports

The source of this document is available at GitHub QGIS Documentation repository. Consult GitHub.com for instructions on how to use the git version control system.

Despite our efforts, you could find some errors or miss some information while following this training. Please report them at https://github.com/qgis/QGIS-Documentation/issues.

#### 1.1.9 Latest Version

You can always obtain the latest version of this document by visiting the online version which is part of the QGIS documentation website (http://docs.qgis.org).

Muista: There are links to online and PDF versions of the Documentation and Training manuals.

Tim Sutton, May 2012

### 1.2 Preparing Exercise Data

The sample data provided with the Training Manual refers to the town of Swellendam and its surroundings. Swellendam is located about 2 hours' east of Cape Town in the Western Cape of South Africa. The dataset contains feature names in both English and Afrikaans.

Anyone can use this dataset without difficulty, but you may prefer to use data from your own country or home town. If you choose to do so, your localised data will be used in all lessons from Module 3 to Module 7.2. Later modules use more complex data sources which may or may not be available for your region.

**Muista:** This process is intended for course conveners, or more experienced QGIS users who wish to create localised sample data sets for their course. Default data sets are provided with the Training Manual, but you may follow these instructions if you wish to replace the default data sets.

**Muista:** The sample data used throughout the manual can be downloaded here: https://github.com/qgis/QGIS-Training-Data/archive/QGIS-Training-Data-v1.0.zip. You can save the files in a folder named **exercise\_data**.




**Muista:** These instructions assume you have a good knowledge of QGIS and are not intended to be used as teaching material.


If you wish to replace the default data set with localised data for your course, this can easily be done with tools built into QGIS. The region you choose to use should have a good mix of urban and rural areas, containing roads of differing significance, area boundaries (such as nature reserves or farms) and surface water, such as streams and rivers.

- · Open a new QGIS project
- In the *Vector* menu dropdown, select *OpenStreetMap*  $\rightarrow$  *Download Data*. You can then manually enter the co-ordinates of the region you wish to use, or you can use an existing layer to set the co-ordinates.


• Choose a location to save the resulting .osm file and click *Ok*:



- You can then open the .osm file using the *Add Vector Layer* button. You may need to select *All files* in the browser window. Alternatively, you can drag and drop the file into the QGIS window.
- In the dialog which opens, select all the layers, *except* the other\_relations and multilinestrings layer:



This will OSM's load three layers into your map which relate to nam-Zoom Full ing conventions data). (you may need to the vector see



We need to extract the useful data from these layers, rename them and create corresponding shape files:

- First, double-click the multipolygons layer to open the Layer properties dialog.
- In the General tab, click Query Builder to open the Query builder window.


This layer contains three fields whose data we will need to extract for use throughout the Training Manual:

- building
- natural (specifically, water)
- landuse

You can sample the data your region contains in order to see what kind of results your region will yield. If you find that "landuse" returns no results, then feel free to exclude it.

You'll need to write filter expressions for each field to extract the data we need. We'll use the "building" field as an example here:

• Enter the following expression into the text area: building != "NULL" and click *Test* to see how many results the query will return. If the number of results is small, you may wish to have a look at the layer's *Attribute Table* to see what data OSM has returned for your region:



• Click Ok and you'll see that the layer elements which are not buildings have been removed from the map.

We now need to save the resulting data as a shapefile for you to use during your course:

- Right-click the *multipolygons* layer and select *Save As...*
- Make sure the file type is ESRI Shapefile and save the file in your new exercise\_data directory, under a directory called "epsg4326".
- Make sure No Symbology is selected (we'll add symbology as part of the course later on).
- You can also select Add saved file to map.

Once the *buildings* layer has been added to the map, you can repeat the process for the natural and landuse fields using the following expressions:

**Muista:** Make sure you clear the previous filter (via the *Layer properties* dialog) from the *multipolygons* layer before proceeding with the next filter expression!

- natural: "natural = 'water"
- landuse: "landuse != 'NULL"


Each resulting data set should be saved in the "epsg4326" directory in your new exercise\_data directory (i.e. "water", "landuse").

You should then extract and save the following fields from the lines and points layers to their corresponding directories:

- lines: "highway != 'NULL" to roads, and "waterway != 'NULL" to rivers
- points: "place != 'NULL'" to places

Once you have finished extracting the above data, you can remove the *multipolygons*, *lines* and *points* layers.

You should now have a map which looks something like this (the symbology will certainly be very different, but that is fine):



The important thing is that you have 6 layers matching those shown above and that all those layers have some data

The last step is to create a spatiallite file from the landuse layer for use during the course:

- Right-click the landuse layer and select Save as...
- Select *SpatialLite* as the format and save the file as landuse under the "epsg4326" directory.
- Click Ok.
- Delete the landuse.shp and its related files (if created).

## 122 🥜

### **Try Yourself Create SRTM DEM tiff Files**

For Module 6 (Creating Vector Data) and Module 8 (Rasters), you'll also need raster images (SRTM DEM) which cover the region you have selected for your course.

The CGIAR-CGI (http://srtm.csi.cgiar.org/) provides some SRTM DEM you can download from http://srtm.csi.cgiar.org/SELECTION/inputCoord.asp.

You'll need images which cover the entire region you have chosen to use. If you kept same data as the training manual, you can use the extent shown in the figure\_set\_osm\_region figure above, otherwise adapt your extent.

Keep the GeoTiff format. Once the form is filled, click on the *Click here to Begin Search* >> button and download the file(s).

Once you have downloaded the required file(s), they should be saved in the  $exercise\_data$  directory, under raster/SRTM subfolders.

# 1.2.3

## Try Yourself Create imagery tiff Files

In Module 6, Lesson 1.2 shows close-up images of three school sports fields which students are asked to digitize. You'll therefore need to reproduce these images using your new SRTM DEM tiff file(s). There is no obligation to use school sports fields: any three school land-use types can be used (e.g. different school buildings, playgrounds or car parks).

For reference, the images in the example data are:





# 1.2.4 Try Yourself Replace Tokens

Having created your localised dataset, the final step is to replace the tokens in the conf.py file so that the appropriate names will appear in your localised version of the Training Manual.

The tokens you need to replace are as follows:

- majorUrbanName: this defaults to "Swellendam". Replace with the name of the major town in your region.
- schoolAreaType1: this defaults to "athletics field". Replace with the name of the largest school area type in your region.
- largeLandUseArea: this defaults to "Bontebok National Park". Replace with the name of a large landuse polygon in your region.
- srtmFileName: this defaults to srtm\_41\_19.tif. Replace this with the filename of your SRTM DEM file.
- localCRS: this defaults to WGS 84 / UTM 34S. You should replace this with the correct CRS for your region.

Module: Käyttöliittymä

#### 2.1 Lesson: A Brief Introduction

Welcome to our course! Over the next few days, we'll be showing you how to use QGIS easily and efficiently. If you're new to GIS, we'll tell you what you need to get started. If you're an experienced user, you'll see how QGIS fulfills all the functions you expect from a GIS program, and more!

In this module we introduce the QGIS project itself, as well as explaining the user interface.

After completing this section, you will be able to correctly identify the main elements of the screen in QGIS and know what each of them does, and load a shapefile into QGIS.

**Varoitus:** This course includes instructions on adding, deleting and altering GIS datasets. We have provided training datasets for this purpose. Before using the techniques described here on your own data, always ensure you have proper backups!

#### 2.1.1 How to use this tutorial

Any text that looks like this refers to something on the screen that you can click on.

Text that  $looks \rightarrow like \rightarrow this$  directs you through menus.

This kind of text refers to something you can type, such as a command, path, or file name.

#### 2.1.2 Tiered course objectives

This course caters to different user experience levels. Depending on which category you consider yourself to be in, you can expect a different set of course outcomes. Each category contains information that is essential for the next one, so it's important to do all exercises that are at or below your level of experience.



#### Basic

In this category, the course assumes that you have little or no prior experience with theoretical GIS knowledge or the operation of a GIS program.

Limited theoretical background will be provided to explain the purpose of an action you will be performing in the program, but the emphasis is on learning by doing.

When you complete the course, you will have a better concept of the possibilities of GIS, and how to harness their power via QGIS.



In this category, it is assumed that you have working knowledge and experience of the everyday uses of GIS.

Following the instructions for the beginner level will provide you with familiar ground, as well as to make you aware of the cases where QGIS does things slightly differently from other software you may be used to. You will also learn how to use analysis functions in QGIS.

When you complete the course, you should be comfortable with using QGIS for all of the functions you usually need from a GIS for everyday use.



#### Advanced

In this category, the assumption is that you are experienced with GIS, have knowledge of and experience with spatial databases, using data on a remote server, perhaps writing scripts for analysis purposes, etc.

Following the instructions for the other two levels will familiarize you with the approach that the QGIS interface follows, and will ensure that you know how to access the basic functions that you need. You will also be shown how to make use of QGIS' plugin system, database access system, and so on.

When you complete the course, you should be well-acquainted with the everyday operation of QGIS, as well as its more advanced functions.

#### 2.1.3 Why QGIS?

As information becomes increasingly spatially aware, there is no shortage of tools able to fulfill some or all commonly used GIS functions. Why should anyone be using QGIS over some other GIS software package?

Here are only some of the reasons:

- It's free, as in lunch. Installing and using the QGIS program costs you a grand total of zero money. No initial fee, no recurring fee, nothing.
- *It's free, as in liberty.* If you need extra functionality in QGIS, you can do more than just hope it will be included in the next release. You can sponsor the development of a feature, or add it yourself if you are familiar with programming.
- It's constantly developing. Because anyone can add new features and improve on existing ones, QGIS never stagnates. The development of a new tool can happen as quickly as you need it to.
- Extensive help and documentation is available. If you're stuck with anything, you can turn to the extensive documentation, your fellow QGIS users, or even the developers.
- Cross-platform. QGIS can be installed on MacOS, Windows and Linux.

Now that you know why you want to use QGIS, we can show you how. The first lesson will guide you in creating your first QGIS map.

### 2.2 Lesson: Adding your first layer

We will start the application, and create a basic map to use for examples and exercises.

**The goal for this lesson:** To get started with an example map.

**Muista:** Before starting this exercise, QGIS must be installed on your computer. Also, download the training\_manual\_exercise\_data.zip file from the QGIS data downloads area.

Launch QGIS from its desktop shortcut, menu item, etc., depending on how you configured its installation.


**Muista:** The screenshots for this course were taken in QGIS 2.0 running on MacOS. Depending on your setup, the screens you encounter may well appear somewhat different. However, all the same buttons will still be available, and the instructions will work on any OS. You will need QGIS 2.0 (the latest version at time of writing) to use this course.

Let's get started right away!



### Follow Along: Prepare a map

- Open QGIS. You will have a new, blank map.
- Look for the *Add Vector Layer* button:
- Click on it to open the following dialog:



• Click on the *Browse* button and navigate to the file exercise\_data/epsg4326/roads.shp (in your course directory). With this file selected, click *Open*. You will see the original dialog, but with the file path filled in. Click *Open* here as well. The data you specified will now load.

Congratulations! You now have a basic map. Now would be a good time to save your work.

- Click on the *Save As* button:
- Save the map under exercise\_data/ and call it basic\_map.qgs.

Check your results

#### 2.2.2 In Conclusion

You've learned how to add a layer and create a basic map!

#### 2.2.3 What's Next?


Now you're familiar with the function of the *Add Vector Layer* button, but what about all the others? How does this interface work? Before we go on with the more involved stuff, let's first take a good look at the general layout of the QGIS interface. This is the topic of the next lesson.

#### 2.3 Lesson: An Overview of the Interface

We will explore the QGIS user interface so that you are familiar with the menus, toolbars, map canvas and layers list that form the basic structure of the interface.

The goal for this lesson: To understand the basics of the QGIS user interface.





The elements identified in the figure above are:

- 1. Layers List / Browser Panel
- 2. Toolbars
- 3. Map canvas
- 4. Status bar
- 5. Side Toolbar



In the Layers list, you can see a list, at any time, of all the layers available to you.

Expanding collapsed items (by clicking the arrow or plus symbol beside them) will provide you with more information on the layer's current appearance.

Right-clicking on a layer will give you a menu with lots of extra options. You will be using some of them before long, so take a look around!

Some versions of QGIS have a separate *Control rendering order* checkbox just underneath the Layers list. Don't worry if you can't see it. If it is present, ensure that it's checked for now.

**Muista:** A vector layer is a dataset, usually of a specific kind of object, such as roads, trees, etc. A vector layer can consist of either points, lines or polygons.



#### The Browser Panel

The QGIS Browser is a panel in QGIS that lets you easily navigate in your database. You can have access to common vector files (e.g. ESRI shapefile or MapInfo files), databases (e.g.PostGIS, Oracle, Spatialite or MSSQL Spatial) and WMS/WFS connections. You can also view your GRASS data.



#### **Toolbars**

Your most oft-used sets of tools can be turned into toolbars for basic access. For example, the File toolbar allows you to save, load, print, and start a new project. You can easily customize the interface to see only the tools you use most often, adding or removing toolbars as necessary via the  $Settings \rightarrow Toolbars$  menu.

Even if they are not visible in a toolbar, all of your tools will remain accessible via the menus. For example, if you remove the *File* toolbar (which contains the *Save* button), you can still save your map by clicking on the *Project* menu and then clicking on *Save*.



#### The Map Canvas

This is where the map itself is displayed.



#### The Status Bar

Shows you information about the current map. Also allows you to adjust the map scale and see the mouse cursor's coordinates on the map.

## 2.3.2

### 9

### Try Yourself 1

Try to identify the four elements listed above on your own screen, without referring to the diagram above. See if you can identify their names and functions. You will become more familiar with these elements as you use them in the coming days.

Check your results



## Try Yourself 2

Try to find each of these tools on your screen. What is their purpose?



**Muista:** If any of these tools is not visible on the screen, try enabling some toolbars that are currently hidden. Also keep in mind that if there isn't enough space on the screen, a toolbar may be shortened by hiding some of its tools. You can see the hidden tools by clicking on the double right arrow button in any such collapsed toolbar. You can see a tooltip with the name of any tool by holding your mouse over the tool for a while.

Check your results

#### 2.3.4 What's Next?

Now you've seen how the QGIS interface works, you can use the tools available to you and start improving on your map! This is the topic of the next lesson.

### Module: Creating a Basic Map

In this module, you will create a basic map which will be used later as a basis for further demonstrations of QGIS functionality.

### 3.1 Lesson: Working with Vector Data

Vector data is arguably the most common kind of data you will find in the daily use of GIS. It describes geographic data in terms of points, that may be connected into lines and polygons. Every object in a vector dataset is called a **feature**, and is associated with data that describes that feature.

The goal for this lesson: To learn about the structure of vector data, and how to load vector datasets into a map.



## Follow Along: Viewing Layer Attributes

It's important to know that the data you will be working with does not only represent **where** objects are in space, but also tells you **what** those objects are.

From the previous exercise, you should have the *roads* layer loaded in your map. What you can see right now is merely the position of the roads.

To see all the data available to you, with the *roads* layer selected in the Layers panel:

• Click on this button:



It will show you a table with more data about the *roads* layer. This extra data is called *attribute data*. The lines that you can see on your map represent where the roads go; this is the *spatial data*.

These definitions are commonly used in GIS, so it's essential to remember them!

• You may now close the attribute table.

Vector data represents features in terms of points, lines and polygons on a coordinate plane. It is usually used to store discrete features, like roads and city blocks.

## 312

## Follow Along: Loading Vector Data From Shapefiles

The Shapefile is a specific file format that allows you to store GIS data in an associated group of files. Each layer consists of several files with the same name, but different file types. Shapefiles are easy to send back and forth, and most GIS software can read them.

Refer back to the introductory exercise in the previous section for instructions on how to add vector layers.

Load the data sets from the epsg4326 folder into your map following the same method:

- "places"
- "water"
- "rivers"
- "buildings"

Check your results



## Follow Along: Loading Vector Data From a Database

Databases allow you to store a large volume of associated data in one file. You may already be familiar with a database management system (DBMS) such as Microsoft Access. GIS applications can also make use of databases. GIS-specific DBMSes (such as PostGIS) have extra functions, because they need to handle spatial data.

• Click on this icon:


(If you're sure you can't see it at all, check that the *Manage Layers* toolbar is enabled.)

It will give you a new dialog. In this dialog:

- Click the New button.
- In the same <code>epsg4326</code> folder, you should find the file <code>landuse.sqlite</code>. Select it and click <code>Open</code>.

You will now see the first dialog again. Notice that the dropdown select above the three buttons now reads "landuse.sqlite@...", followed by the path of the database file on your computer.

• Click the *Connect* button. You should see this in the previously empty box:



• Click on the landuse layer to select it, then click Add

**Muista:** Remember to save the map often! The map file doesn't contain any of the data directly, but it remembers which layers you loaded into your map.

Check your results

#### 3.1.4 Follow Along: Reordering the Layers

The layers in your Layers list are drawn on the map in a certain order. The layer at the bottom of the list is drawn first, and the layer at the top is drawn last. By changing the order that they are shown on the list, you can change the order they are drawn in.

**Muista:** Depending on the version of QGIS that you are using, you may have a checkbox beneath your Layers list reading *Control rendering order*. This must be checked (switched on) so that moving the layers up and down in the Layers list will bring them to the front or send them to the back in the map. If your version of QGIS doesn't have this option, then it is switched on by default and you don't need to worry about it.

The order in which the layers have been loaded into the map is probably not logical at this stage. It's possible that the road layer is completely hidden because other layers are on top of it.


For example, this layer order...



... would result in roads and places being hidden as they run underneath urban areas.

To resolve this problem:

- Click and drag on a layer in the Layers list.
- Reorder them to look like this:



You'll see that the map now makes more sense visually, with roads and buildings appearing above the land use regions.

#### 3.1.5 In Conclusion

Now you've added all the layers you need from several different sources.

#### 3.1.6 What's Next?

Using the random palette automatically assigned when loading the layers, your current map is probably not easy to read. It would be preferable to assign your own choice of colors and symbols. This is what you'll learn to do in the next lesson.

### 3.2 Lesson: Symbology

The symbology of a layer is its visual appearance on the map. The basic strength of GIS over other ways of representing data with spatial aspects is that with GIS, you have a dynamic visual representation of the data you're working with.

Therefore, the visual appearance of the map (which depends on the symbology of the individual layers) is very important. The end user of the maps you produce will need to be able to easily see what the map represents. Equally as important, you need to be able to explore the data as you're working with it, and good symbology helps a lot.

In other words, having proper symbology is not a luxury or just nice to have. In fact, it's essential for you to use a GIS properly and produce maps and information that people will be able to use.

The goal for this lesson: To be able to create any symbology you want for any vector layer.

# 3.2.1

### Follow Along: Changing Colors

To change a layer's symbology, open its Layer Properties. Let's begin by changing the color of the landuse layer.


- Right-click on the *landuse* layer in the Layers list.
- Select the menu item *Properties* in the menu that appears.

Muista: By default, you can also access a layer's properties by double-clicking on the layer in the Layers list.

In the *Properties* window:

• Select the *Style* tab at the extreme left:

3.2. Lesson: Symbology



• Click the color select button next to the *Color* label.

A standard color dialog will appear.

- Choose a gray color and click OK.
- Click *OK* again in the *Layer Properties* window, and you will see the color change being applied to the layer.



Change the *water* layer to a light blue color.

Check your results


# 3.2.3 Follow Along: Changing Symbol Structure

This is good stuff so far, but there's more to a layer's symbology than just its color. Next we want to eliminate the lines between the different land use areas so as to make the map less visually cluttered.

• Open the Layer Properties window for the landuse layer.

Under the *Style* tab, you will see the same kind of dialog as before. This time, however, you're doing more than just quickly changing the color.

• In the Symbol Layers panel, expand the Fill dropdown (if necessary) and select the Simple fill option:



- Click on the *Border style* dropdown. At the moment, it should be showing a short line and the words *Solid Line*.
- Change this to No Pen.
- Click OK.

Now the *landuse* layer won't have any lines between areas.

# 3.2.4 Try Yourself


- Change the water layer's symbology again so that it is has a darker blue outline.
- Change the *rivers* layer's symbology to a sensible representation of waterways.

Check your results

# 3.2.5 Follow Along: Scale-Based Visibility

Sometimes you will find that a layer is not suitable for a given scale. For example, a dataset of all the continents may have low detail, and not be very accurate at street level. When that happens, you want to be able to hide the dataset at inappropriate scales.


In our case, we may decide to hide the buildings from view at small scales. This map, for example ...



... is not very useful. The buildings are hard to distinguish at that scale.

To enable scale-based rendering:

- Open the Layer Properties dialog for the buildings layer.
- Activate the *General* tab.
- Enable scale-based rendering by clicking on the checkbox labelled *Scale dependent visibility*:



- Change the *Minimum* value to 1:10,000.
- Click OK.

Test the effects of this by zooming in and out in your map, noting when the *buildings* layer disappears and reappears.

**Muista:** You can use your mouse wheel to zoom in increments. Alternatively, use the zoom tools to zoom to a window:



## 3.2.6


### Follow Along: Adding Symbol Layers

Now that you know how to change simple symbology for layers, the next step is to create more complex symbology. QGIS allows you to do this using symbol layers.


• Go back to the *landuse* layer's symbol properties panel (by clicking *Simple fill* in the *Symbol layers* panel).

In this example, the current symbol has no outline (i.e., it uses the *No Pen* border style).

Select the Fill in the Symbol layers panel. Then click the Add symbol layer button:



• Click on it and the dialog will change to look somewhat like this:




(It may appear somewhat different in color, for example, but you're going to change that anyway.)

Now there's a second symbol layer. Being a solid color, it will of course completely hide the previous kind of symbol. Plus, it has a *Solid Line* border style, which we don't want. Clearly this symbol has to be changed.

**Muista:** It's important not to get confused between a map layer and a symbol layer. A map layer is a vector (or raster) that has been loaded into the map. A symbol layer is part of the symbol used to represent a map layer. This course will usually refer to a map layer as just a layer, but a symbol layer will always be called a symbol layer, to prevent confusion.


With the new Simple Fill layer selected:

- Set the border style to No Pen, as before.
- Change the fill style to something other than *Solid* or *No brush*. For example:



• Click OK. Now you can see your results and tweak them as needed.

You can even add multiple extra symbol layers and create a kind of texture for your layer that way.



It's fun! But it probably has too many colors to use in a real map...



• Remembering to zoom in if necessary, create a simple, but not distracting texture for the *buildings* layer using the methods above.


Check your results

# 3.2.8 Follow Along: Ordering Symbol Levels

When symbol layers are rendered, they are also rendered in a sequence, similar to the way the different map layers are rendered. This means that in some cases, having many symbol layers in one symbol can cause unexpected results.

- Give the *roads* layer an extra symbol layer (using the method for adding symbol layers demonstrated above).
- Give the base line a *Pen width* of 0.3, a white color and select *Dashed Line* from the *Pen Style* dropdown.
- Give the new, uppermost layer a thickness of 1 . 3 and ensure that it is a *Solid Line*.


You'll notice that this happens:



Well that's not what we want at all!


To prevent this from happening, you can sort the symbol levels and thereby control the order in which the different symbol layers are rendered.

To change the order of the symbol layers, select the *Line* layer in the *Symbol layers* panel, then click  $Advanced \rightarrow Symbol levels...$  in the bottom right-hand corner of the window. This will open a dialog like this:



Select *Enable symbol levels*. You can then set the layer ordering of each symbol by entering the corresponding level number. 0 is the bottom layer.

In our case, we want to reverse the ordering, like this:



This will render the dashed, white line above the thick black line.

• Click *OK* twice to return to the map.

The map will now look like this:



Also note that the meeting points of roads are now "merged", so that one road is not rendered above another.


When you're done, remember to save the symbol itself so as not to lose your work if you change the symbol again in the future. You can save your current symbol style by clicking the *Save Style* ... button under the *Style* tab of the *Layer Properties* dialog. Generally, you should save as *QGIS Layer Style File*.

Save your style under <code>exercise\_data/styles</code>. You can load a previously saved style at any time by clicking the *Load Style* ... button. Before you change a style, keep in mind that any unsaved style you are replacing will be lost.



• Change the appearance of the *roads* layer again.

The roads must be narrow and mid-gray, with a thin, pale yellow outline. Remember that you may need to change the layer rendering order via the  $Advanced \rightarrow Symbol\ levels...$  dialog.




Check your results



Symbol levels also work for classified layers (i.e., layers having multiple symbols). Since we haven't covered classification yet, you will work with some rudimentary pre-classified data.

- Create a new map and add only the *roads* dataset.
- Apply the style advanced\_levels\_demo.qml provided in exercise\_data/styles.
- Zoom in to the Swellendam area.
- Using symbol layers, ensure that the outlines of layers flow into one another as per the image below:



Check your results




In addition to setting fill colors and using predefined patterns, you can use different symbol layer types entirely. The only type we've been using up to now was the *Simple Fill* type. The more advanced symbol layer types allow you to customize your symbols even further.


Each type of vector (point, line and polygon) has its own set of symbol layer types. First we will look at the types available for points.

### **Point Symbol Layer Types**

- Open your basic\_map project.
- Change the symbol properties for the *places* layer:



• You can access the various symbol layer types by selecting the *Simple marker* layer in the *Symbol layers* panel, then click the *Symbol layer type* dropdown:




• Investigate the various options available to you, and choose a symbol with styling you think is appropriate.

• If in doubt, use a round *Simple marker* with a white border and pale green fill, with a *size* of 3,00 and an *Outline width* of 0.5.


### **Line Symbol Layer Types**

To see the various options available for line data:


• Change the symbol layer type for the *roads* layer's topmost symbol layer to *Marker line*:



• Select the *Simple marker* layer in the *Symbol layers* panel. Change the symbol properties to match this dialog:



• Change the interval to 1,00:




• Ensure that the symbol levels are correct (via the *Advanced* → *Symbol levels* dialog we used earlier) before applying the style.


Once you have applied the style, take a look at its results on the map. As you can see, these symbols change direction along with the road but don't always bend along with it. This is useful for some purposes, but not for others. If you prefer, you can change the symbol layer in question back to the way it was before.

### **Polygon Symbol Layer Types**


To see the various options available for polygon data:

- Change the symbol layer type for the *water* layer, as before for the other layers.
- Investigate what the different options on the list can do.
- Choose one of them that you find suitable.
- If in doubt, use the *Point pattern fill* with the following options:





- Add a new symbol layer with a normal Simple fill.
- Make it the same light blue with a darker blue border.
- Move it underneath the point pattern symbol layer with the *Move down* button:




As a result, you have a textured symbol for the water layer, with the added benefit that you can change the size, shape and distance of the individual dots that make up the texture.

# 3.2.12 Follow Along: Creating a Custom SVG Fill

Muista: To do this exercise, you will need to have the free vector editing software Inkscape installed.

• Start the Inkscape program.


You will see the following interface:




You should find this familiar if you have used other vector image editing programs, like Corel.

First, we'll change the canvas to a size appropriate for a small texture.


- Click on the menu item  $File \rightarrow Document Properties$ . This will give you the *Document Properties* dialog.
- Change the *Units* to *px*.
- Change the Width and Height to 100.
- Close the dialog when you are done.
- Click on the menu item  $View \rightarrow Zoom \rightarrow Page$  to see the page you are working with.
- Select the *Circle* tool:



- Click and drag on the page to draw an ellipse. To make the ellipse turn into a circle, hold the Ctrl button while you're drawing it.
- Right-click on the circle you just created and open its *Fill and Stroke* options. You can modify its rendering, such as:
  - Change the Fill color to a somehow pale grey-blue,
  - Assign to the border a darker color in Stroke paint tab,
  - And reduce the border thickness under *Stroke style* tab.




- Draw a line using the *Pencil* tool:
  - Click once to start the line. Hold ctrl to make it snap to increments of 15 degrees.
  - Move the pointer horizontally and place a point with a simple click.
  - Click and snap to the vertex of the line and trace a vertical line, ended by a simple click.
  - Now join the two end vertices.
  - Change the color and width of the triangle symbol to match the circle's stroke and move it around as necessary, so that you end up with a symbol like this one:




• If the symbol you get satisfies you, then save it as *landuse\_symbol* under the directory that the course is in, under exercise\_data/symbols, as SVG file.

### In QGIS:


- Open the Layer Properties for the landuse layer.
- In the *Style* tab, change the symbol structure by selecting SVG Fill as *Symbol Layer Type* option, as shown below.
- Click the Browse button to select your SVG image. It's added to the symbol tree and you can now customize its different characteristics (colors, angle, effects, units...).



You may also wish to update the svg layer's border (see below):



Once you validate the dialog, features in landuse layer should now be covered by a set of symbols, showing a texture like the one on the following map. If textures are not visible, you may need to zoom in the map canvas or set in the layer properties a bigger *Texture width*.



### 3.2.13 In Conclusion

Changing the symbology for the different layers has transformed a collection of vector files into a legible map. Not only can you see what's happening, it's even nice to look at!

### 3.2.14 Further Reading

Examples of Beautiful Maps

### 3.2.15 What's Next?

Changing symbols for whole layers is useful, but the information contained within each layer is not yet available to someone reading these maps. What are the streets called? Which administrative regions do certain areas belong to? What are the relative surface areas of the farms? All of this information is still hidden. The next lesson will explain how to represent this data on your map.

Muista: Did you remember to save your map recently?

### **Module: Classifying Vector Data**

Classifying vector data allows you to assign different symbols to features (different objects in the same layer), depending on their attributes. This allows someone who uses the map to easily see the attributes of various features.

### 4.1 Lesson: Attribute Data

Up to now, none of the changes we have made to the map have been influenced by the objects that are being shown. In other words, all the land use areas look alike, and all the roads look alike. When looking at the map, the viewers don't know anything about the roads they are seeing; only that there is a road of a certain shape in a certain area.

But the whole strength of GIS is that all the objects that are visible on the map also have attributes. Maps in a GIS aren't just pictures. They represent not only objects in locations, but also information about those objects.

The goal of this lesson: To explore the attribute data of an object and understand what the various data can be useful for.

# 4.1.1 Follow Along: Attribute data

Open the attribute table for the *places* layer (refer back to the section "*Working with Vector Data*" if necessary). Which field would be the most useful to represent in label form, and why?

Check your results

#### 4.1.2 In Conclusion

You now know how to use the attribute table to see what is actually in the data you're using. Any dataset will only be useful to you if it has the attributes that you care about. If you know which attributes you need, you can quickly decide if you're able to use a given dataset, or if you need to look for another one that has the required attribute data.

### 4.1.3 What's Next?

Different attributes are useful for different purposes. Some of them can be represented directly as text for the map user to see. You'll learn how to do this in the next lesson.

### 4.2 Lesson: The Label Tool

Labels can be added to a map to show any information about an object. Any vector layer can have labels associated with it. These labels rely on the attribute data of a layer for their content.

**Muista:** The *Layer Properties* dialog does have a *Labels* tab, which now offers the same functionality, but for this example we'll use the *Label tool*, accessed via a toolbar button.

The goal for this lesson: To apply useful and good-looking labels to a layer.



### Follow Along: Using Labels

Before being able to access the Label tool, you will need to ensure that it has been activated.


- Go to the menu item  $View \rightarrow Toolbars$ .
- Ensure that the *Label* item has a check mark next to it. If it doesn't, click on the *Label* item, and it will be activated.
- Click on the *places* layer in the *Layers list*, so that it is highlighted.
- Click on the following toolbar button:

This gives you the Layer labeling settings dialog.

• Check the box next to Label this layer with....


You'll need to choose which field in the attributes will be used for the labels. In the previous lesson, you decided that the NAME field was the most suitable one for this purpose.

• Select *name* from the list:



### • Click OK.


The map should now have labels like this:



## 4.2.2 Follow Along: Changing Label Options


Depending on the styles you chose for your map in earlier lessons, you'll might find that the labels are not appropriately formatted and either overlap or are too far away from their point markers.

- Open the Label tool again by clicking on its button as before.
- Make sure *Text* is selected in the left-hand options list, then update the text formatting options to match those shown here:




That's the font problem solved! Now let's look at the problem of the labels overlapping the points, but before we do that, let's take a look at the *Buffer* option.

- Open the Label tool dialog.
- Select Buffer from the left-hand options list.
- Select the checkbox next to *Draw text buffer*, then choose options to match those shown here:




• Click Apply.

You'll see that this adds a colored buffer or border to the place labels, making them easier to pick out on the map:



Now we can address the positioning of the labels in relation to their point markers.

- In the *Label tool* dialog, go to the *Placement* tab.
- Change the value of *Distance* to 2mm and make sure that *Around point* is selected:



• Click Apply.

You'll see that the labels are no longer overlapping their point markers.

## 4.2.3

## Follow Along: Using Labels Instead of Layer Symbology

In many cases, the location of a point doesn't need to be very specific. For example, most of the points in the *places* layer refer to entire towns or suburbs, and the specific point associated with such features is not that specific on a large scale. In fact, giving a point that is too specific is often confusing for someone reading a map.


To name an example: on a map of the world, the point given for the European Union may be somewhere in Poland, for instance. To someone reading the map, seeing a point labeled *European Union* in Poland, it may seem that the capital of the European Union is therefore in Poland.

So, to prevent this kind of misunderstanding, it's often useful to deactivate the point symbols and replace them completely with labels.


In QGIS, you can do this by changing the position of the labels to be rendered directly over the points they refer to.

- Open the *Layer labeling settings* dialog for the *places* layer.
- Select the *Placement* option from the options list.
- Click on the Offset from point button.


This will reveal the *Quadrant* options which you can use to set the position of the label in relation to the point marker. In this case, we want the label to be centered on the point, so choose the center quadrant:



• Hide the point symbols by editing the layer style as usual, and setting the size of the *Ellipse marker* width and height to 0:



• Click *OK* and you'll see this result:



If you were to zoom out on the map, you would see that some of the labels disappear at larger scales to avoid overlapping. Sometimes this is what you want when dealing with datasets that have many points, but at other times you will lose useful information this way. There is another possibility for handling cases like this, which we'll cover in a later exercise in this lesson.

## 4.2.4 Try You

## **Try Yourself Customize the Labels**

• Return the label and symbol settings to have a point marker and a label offset of 2.00mm. You may like to adjust the styling of the point marker or labels at this stage.


#### Check your results

- Set the map to the scale 1:100000. You can do this by typing it into the Scale box in the Status Bar.
- Modify your labels to be suitable for viewing at this scale.

### Check your results


## 4.2.5 Follow Along: Labeling Lines

Now that you know how labeling works, there's an additional problem. Points and polygons are easy to label, but what about lines? If you label them the same way as the points, your results would look like this:




We will now reformat the *roads* layer labels so that they are easy to understand.

- Hide the *Places* layer so that it doesn't distract you.
- Activate labels for the *streets* layer as before.
- Set the font *Size* to 10 so that you can see more labels.
- Zoom in on the Swellendam town area.
- In the *Label tool* dialog's *Advanced* tab, choose the following settings:




You'll probably find that the text styling has used default values and the labels are consequently very hard to read. Set the label text format to have a dark-grey or black Color and a light-yellow buffer.

The map will look somewhat like this, depending on scale:



You'll see that some of the road names appear more than once and that's not always necessary. To prevent this from happening:

• In the *Label labelling settings* dialog, choose the *Rendering* option and select the *Merge connected lines to avoid duplicate labels*:



#### • Click OK


Another useful function is to prevent labels being drawn for features too short to be of notice.

• In the same *Rendering* panel, set the value of *Suppress labeling of features smaller than* ... to 5mm and note the results when you click *Apply*.

Try out different *Placement* settings as well. As we've seen before, the *horizontal* option is not a good idea in this case, so let's try the *curved* option instead.

• Select the Curved option in the Placement panel of the Layer labeling settings dialog.

Here's the result:




As you can see, this hides a lot of the labels that were previously visible, because of the difficulty of making some of them follow twisting street lines and still be legible. You can decide which of these options to use, depending on what you think seems more useful or what looks better.

## 4.2.6 Follow Along: Data Defined Settings


- Deactivate labeling for the Streets layer.
- Reactivate labeling for the *Places* layer.
- Open the attribute table for *Places* via the button.

It has one fields which is of interest to us now: place which defines the type of urban area for each object. We can use this data to influence the label styles.


- Navigate to the *Text* panel in the *places Labels* panel.
- In the *Italic* dropdown, select Edit... to open the *Expression string builder*:



In the text input, type: "place" = 'town' and click Ok twice:



Notice its effects:



### **Try Yourself Using Data Defined Settings**

**Muista:** We're jumping ahead a bit here to demonstrate some advanced labeling settings. At the advanced level, it's assumed that you'll know what the following means. If you don't, feel free to leave out this section and come back later when you've covered the requisite materials.


- Open the Attribute Table for *places*.
- Enter edit mode by clicking this button:



• Add a new column:



• Configure it like this:



• Use this to set custom font sizes for each different type of place (i.e., each key in the PLACE field).

Check your results

## 4.2.8 Further Possibilities With Labeling

We can't cover every option in this course, but be aware that the *Label tool* has many other useful functions. You can set scale-based rendering, alter the rendering priority for labels in a layer, and set every label option using layer attributes. You can even set the rotation, XY position, and other properties of a label (if you have attribute fields allocated for the purpose), then edit these properties using the tools adjacent to the main *Label tool*:



(These tools will be active if the required attribute fields exist and you are in edit mode.)

Feel free to explore more possibilities of the labeling system.

#### 4.2.9 In Conclusion


You've learned how to use layer attributes to create dynamic labels. This can make your map a lot more informative and stylish!

#### 4.2.10 What's Next?

Now that you know how attributes can make a visual difference for your map, how about using them to change the symbology of objects themselves? That's the topic for the next lesson!

### 4.3 Lesson: Classification

Labels are a good way to communicate information such as the names of individual places, but they can't be used for everything. For example, let's say that someone wants to know what each landuse area is used for. Using labels, you'd get this:




This makes the map's labeling difficult to read and even overwhelming if there are numerous different landuse areas on the map.

The goal for this lesson: To learn how to classify vector data effectively.




## Follow Along: Classifying Nominal Data

- Open the Layer Properties dialog for the landuse layer.
- Go to the Style tab.
- Click on the dropdown that says Single Symbol and change it to Categorized:




- In the new panel, change the *Column* to *landuse* and the *Color ramp* to *Greens*.
- Click the button labeled *Classify*:




#### • Click OK.

You'll see something like this:



• Click the arrow (or plus sign) next to *landuse* in the *Layer list*, you'll see the categories explained:




Now our landuse polygons are appropriately colored and are classified so that areas with the same land use are the same color. You may wish to remove the black border from the *landuse* layer:


- Open Layer Properties, go to the Style tab and select Symbol.
- Change the symbol by removing the border from the Simple Fill layer and click OK.

You'll see that the landuse polygon outlines have been removed, leaving just our new fill colours for each categorisation.

• If you wish to, you can change the fill color for each landuse area by double-clicking the relevant color block:



Notice that there is one category that's empty:



This empty category is used to color any objects which do not have a landuse value defined or which have a *NULL* value. It is important to keep this empty category so that areas with a *NULL* value are still represented on the map. You may like to change the color to more obviously represent a blank or *NULL* value.

Remember to save your map now so that you don't lose all your hard-earned changes!

# 4.3.2 Try Yourself More Classification

If you're only following the basic-level content, use the knowledge you gained above to classify the *buildings* layer. Set the categorisation against the *building* column and use the *Spectral* color ramp.

Muista: Remember to zoom into an urban area to see the results.

# 4.3.3 Follow Along: Ratio Classification

There are four types of classification: *nominal*, *ordinal*, *interval* and *ratio*.

In nominal classification, the categories that objects are classified into are name-based; they have no order. For example: town names, district codes, etc.

In ordinal classification, the categories are arranged in a certain order. For example, world cities are given a rank depending on their importance for world trade, travel, culture, etc.

In interval classification, the numbers are on a scale with positive, negative and zero values. For example: height above/below sea level, temperature above/below freezing (0 degrees Celsius), etc.

In ratio classification, the numbers are on a scale with only positive and zero values. For example: temperature above absolute zero (0 degrees Kelvin), distance from a point, the average amount of traffic on a given street per month, etc.

In the example above, we used nominal classification to assign each farm to the town that it is administered by. Now we will use ratio classification to classify the farms by area.

• Save your landuse symbology (if you want to keep it) by clicking on the *Save Style* ... button in the *Style* dialog.

We're going to reclassify the layer, so existing classes will be lost if not saved.

- Close the Style dialog.
- Open the Attributes Table for the *landuse* layer.

We want to classify the landuse areas by size, but there's a problem: they don't have a size field, so we'll have to make one.


• Enter edit mode by clicking this button:



• Add a new column with this button:



• Set up the dialog that appears, like this:



• Click OK.

The new field will be added (at the far right of the table; you may need to scroll horizontally to see it). However, at the moment it is not populated, it just has a lot of  $\mathtt{NULL}$  values.

To solve this problem, we'll need to calculate the areas.

• Open the field calculator:




You'll get this dialog:


78



• Change the values at the top of the dialog to look like this:



• In the Function List, select Geometry  $\rightarrow$  \$area:




- Double-click on it so that it appears in the Expression field.
- Click OK.


Now your AREA field is populated with values (you may need to click the column header to refresh the data). Save the edits and click Ok.

Muista: These areas are in degrees. Later, we will compute them in square meters.

- Open the Layer properties dialog's Style tab.
- Change the classification style from *Categorized* to *Graduated*.
- Change the *Column* to *AREA*:
- Under *Color ramp*, choose the option *New color ramp*... to get this dialog:




• Choose *Gradient* (if it's not selected already) and click *OK*. You'll see this:



You'll be using this to denote area, with small areas as *Color 1* and large areas as *Color 2*.


• Choose appropriate colors.

In the example, the result looks like this:




- Click OK.
- Choose a suitable name for the new color ramp.
- Click *OK* after filling in the name.

Now you'll have something like this:



Leave everything else as-is.

• Click *Ok*:



## 4.3.4 💚 Trv

### Try Yourself Refine the Classification

- Get rid of the lines between the classes.
- Change the values of *Mode* and *Classes* until you get a classification that makes sense.


Check your results

## 4.3.5


### Follow Along: Rule-based Classification


It's often useful to combine multiple criteria for a classification, but unfortunately normal classification only takes one attribute into account. That's where rule-based classification comes in handy.

- Open the Layer Properties dialog for the landuse layer.
- Switch to the Style tab.
- Switch the classification style to *Rule-based*. You'll get this:



- Click the *Add rule* button: 🗣.
- A new dialog then appears.
- Click the ellipsis ... button next to the *Filter* text area.
- Using the query builder that appears, enter the criterion "landuse" = 'residential' AND "name" != ' |majorUrbanName| ', click Ok and choose a pale blue-grey for it and remove the border:






- Add a new criterion "landuse" != 'residential' AND "AREA" >= 0.00005 and choose a mid-green color.
- Add another new criterion "name" = ' | majorUrbanName | ' and assign it a darker grey-blue color in order to indicate the town's importance in the region.
- Click and drag this criterion to the top of the list.

These filters are exclusive, in that they collectively exclude some areas on the map (i.e. those which are smaller that 0.00005, are not residential and are not 'Swellendam'). This means that the excluded polygons take the style of the default (*no filter*) category.


We know that the excluded polygons on our map cannot be residential areas, so give the default category a suitable pale green color.

Your dialog should now look like this:



• Apply this symbology.

Your map will look something like this:



Now you have a map with Swellendam the most prominent residential area and other non-residential areas colored according to their size.

#### 4.3.6 In Conclusion

Symbology allows us to represent the attributes of a layer in an easy-to-read way. It allows us as well as the map reader to understand the significance of features, using any relevant attributes that we choose. Depending on the problems you face, you'll apply different classification techniques to solve them.

#### 4.3.7 What's Next?

Now we have a nice-looking map, but how are we going to get it out of QGIS and into a format we can print out, or make into an image or PDF? That's the topic of the next lesson!

### **Module: Creating Maps**

In this module, you'll learn how to use the QGIS Map Composer to produce quality maps with all the requisite map components.

### 5.1 Lesson: Using Map Composer

Now that you've got a map, you need to be able to print it or to export it to a document. The reason is, a GIS map file is not an image. Rather, it saves the state of the GIS program, with references to all the layers, their labels, colors, etc. So for someone who doesn't have the data or the same GIS program (such as QGIS), the map file will be useless. Luckily, QGIS can export its map file to a format that anyone's computer can read, as well as printing out the map if you have a printer connected. Both exporting and printing is handled via the Map Composer.

The goal for this lesson: To use the QGIS Map Composer to create a basic map with all the required settings.




### Follow Along: The Composer Manager


QGIS allows you to create multiple maps using the same map file. For this reason, it has a tool called the *Composer Manager*.

- Click on the *Project* → *Composer Manager* menu entry to open this tool. You'll see a blank *Composer manager* dialog appear.
- Click the *Add* button and give the new composer the name of Swellendam.
- Click OK.
- Click the Show button.

(You could also close the dialog and navigate to a composer via the  $File \rightarrow Print\ Composers$  menus, as in the image below.)



Whichever route you take to get there, you will now see the *Print Composer* window:





### Follow Along: Basic Map Composition

In this example, the composition was already the way we wanted it. Ensure that yours is as well.


- In the *Print Composer* window, check that the values under *Composition* → *Paper and Quality* are set to the following:
- Size: A4 (210x297mm)
- Orientation: Landscape
- Quality: 300dpi

Now you've got the page layout the way you wanted it, but this page is still blank. It clearly lacks a map. Let's fix that!

• Click on the *Add New Map* button:


With this tool activated, you'll be able to place a map on the page.

• Click and drag a box on the blank page:




The map will appear on the page.

• Move the map by clicking and dragging it around:



• Resize it by clicking and dragging the boxes in the corners:



**Muista:** Your map may look a lot different, of course! This depends on how your own project is set up. But not to worry! These instructions are general, so they will work the same regardless of what the map itself looks like.

- Be sure to leave margins along the edges, and a space along the top for the title.
- Zoom in and out on the page (but not the map!) by using these buttons:



• Zoom and pan the map in the main QGIS window. You can also pan the map using the Move item content

tool:

When zooming in, the map view will not refresh by itself. This is so that it doesn't waste your time redrawing the map while you're zooming the page to where you want it, but it also means that if you zoom in or out, the map will be at the wrong resolution and will look ugly or unreadable.

• Force the map to refresh by clicking this button:



Remember that the size and position you've given the map doesn't need to be final. You can always come back and change it later if you're not satisfied. For now, you need to ensure that you've saved your work on this map. Because a *Composer* in QGIS is part of the main map file, you'll need to save your main project. Go to the main QGIS window (the one with the *Layers list* and all the other familiar elements you were working with before), and save your project from there as usual.

## 5.1.3

### Follow Along: Adding a Title

Now your map is looking good on the page, but your readers/users are not being told what's going on yet. They need some context, which is what you'll provide for them by adding map elements. First, let's add a title.


- Click on this button:
- Click on the page, above the map, and a label will appear at the top of the map.
- Resize it and place it in the top center of the page. It can be resized and moved in the same way that you resized and moved the map.

As you move the title, you'll notice that guidelines appear to help you position the title in the center of the page.

However, there is also a tool to help position the title relative to the map (not the page):



- Click the map to select it.
- Hold in shift on your keyboard and click on the label so that both the map and the label are selected.
- Look for the *Align* button and click on the dropdown arrow next to it to reveal the positioning options and click *Align center*:




To make sure that you don't accidentally move these elements around now that you've aligned them:

• Right-click on both the map and the label.

A small lock icon will appear in the corner to tell you that an element can't be dragged right now. You can always right-click on an element again to unlock it, though.

Now the label is centered to the map, but not the contents. To center the contents of the label:

- Select the label by clicking on it.
- Click on the *Item Properties* tab in the side panel of the *Composer* window.
- Change the text of the label to "Swellendam":
- Use this interface to set the font and alignment options:




• Choose a large but sensible font (the example will use the default font with a size of 36) and set the *Horizontal Alignment* to *Center*.

You can also change the font color, but it's probably best to keep it black as per the default.

The default setting is not to add a frame to the title's text box. However, if you wish to add a frame, you can do so:

- In the Item Properties tab, scroll down until you see the Frame option.
- Click the Frame checkbox to enable the frame. You can also change the frame's color and width.


In this example, we won't enable the frame, so here is our page so far:



## 5.1.4 Follow Along: Adding a Legend

The map reader also needs to be able to see what various things on the map actually mean. In some cases, like the place names, this is quite obvious. In other cases, it's more difficult to guess, like the colors of the farms. Let's add a new legend.

- Click on this button:
- Click on the page to place the legend, and move it to where you want it:



## 5.1.5


### Follow Along: Customizing Legend Items

Not everything on the legend is necessary, so let's remove some unwanted items.


- In the Item Properties tab, you'll find the Legend items panel.
- Select the *buildings* entry.
- Delete it from the legend by clicking the *minus* button:

You can also rename items.

- Select a layer from the same list.
- Click the *Edit* button:
- Rename the layers to Places, Roads and Streets, Surafce Water, and Rivers.
- Set landuse to *Hidden*, then click the down arrow and edit each category to name them on the legend. You can also reorder the items:



As the legend will likely be widened by the new layer names, you may wish to move and resize the legend and or map. This is the result:



## Follow Along: Exporting Your Map

**Muista:** Did you remember to save your work often?

Finally the map is ready for export! You'll see the export buttons near the top left corner of the *Composer* window:



The button on the left is the Print button, which interfaces with a printer. Since the printer options will differ depending on the model of printer that you're working with, it's probably better to consult the printer manual or a general guide to printing for more information on this topic.

The other three buttons allow you to export the map page to a file. There are three export formats to choose from:

- Export as Image
- · Export as SVG
- Export as PDF

Exporting as an image will give you a selection of various common image formats to choose from. This is probably the simplest option, but the image it creates is "dead" and difficult to edit.

The other two options are more common.

If you're sending the map to a cartographer (who may want to edit the map for publication), it's best to export as an SVG. SVG stands for "Scalable Vector Graphic", and can be imported to programs like Inkscape or other vector image editing software.

If you need to send the map to a client, it's most common to use a PDF, because it's easier to set up printing options for a PDF. Some cartographers may prefer PDF as well, if they have a program that allows them to import and edit this format.

For our purposes, we're going to use PDF.

• Click the *Export as PDF* button:



- Choose a save location and a file name as usual.
- Click Save.

#### 5.1.7 In Conclusion

- Close the *Composer* window.
- · Save your map.
- Find your exported PDF using your operating system's file manager.
- · Open it.
- · Bask in its glory.

Congratulations on your first completed QGIS map project!

#### 5.1.8 What's Next?

On the next page, you will be given an assignment to complete. This will allow you to practice the techniques you have learned so far.

### 5.2 Assignment 1

Open your existing map project and revise it thoroughly. If you have noticed small errors or things you'd have liked to fix earlier, do so now.

While customizing your map, keep asking yourself questions. Is this map easy to read and understand for someone who's unfamiliar with the data? If I saw this map on the Internet, or on a poster, or in a magazine, would it capture my attention? Would I want to read this map if it wasn't mine?

If you're doing this course at a Basic or Intermediate level, read up on techniques from the more advanced sections. If you see something you'd like to do in your map, why not try to implement it?

If this course is being presented to you, the course presenter may require you to submit a final version of your map, exported to PDF, for evaluation. If you're doing this course by yourself, it's recommended that you evaluate your own map using the same criteria. Your map will be evaluated on the overall appearance and symbology of the map itself, as well as the appearance and layout of the map page and elements. Remember that the emphasis for evaluating the appearance of maps will always be *ease of use*. The nicer the map is to look at and the easier it is to understand at a glance, the better.

Happy customizing!

#### 5.2.1 In Conclusion

The first four modules have taught you how to create and style a vector map. In the next four modules, you'll learn how to use QGIS for a complete GIS analysis. This will include creating and editing vector data; analyzing vector data; using and analyzing raster data; and using GIS to solve a problem from start to finish, using both raster and vector data sources.

### **Module: Creating Vector Data**

Creating maps using existing data is just the beginning. In this module, you'll learn how to modify existing vector data and create new datasets entirely.

### 6.1 Lesson: Creating a New Vector Dataset

The data that you use has to come from somewhere. For most common applications, the data exists already; but the more particular and specialized the project, the less likely it is that the data will already be available. In such cases, you'll need to create your own new data.

**The goal for this lesson:** To create a new vector dataset.


## 6.1.1 Follow Along: The Layer Creation Dialog

Before you can add new vector data, you need a vector dataset to add it to. In our case, you'll begin by creating new data entirely, rather than editing an existing dataset. Therefore, you'll need to define your own new dataset first.

You'll need to open the New Vector Layer dialog that will allow you to define a new layer.

• Navigate to and click on the menu entry  $Layer \rightarrow New \rightarrow New$  Shapefile Layer.

You'll be presented with the following dialog:



It's important to decide which kind of dataset you want at this stage. Each different vector layer type is "built differently" in the background, so once you've created the layer, you can't change its type.

For the next exercise, we're going to be creating new features which describe areas. For such features, you'll need to create a polygon dataset.

• Click on the *Polygon* radio button:




This has no impact on the rest of the dialog, but it will cause the correct type of geometry to be used when the vector dataset is created.

The next field allows you to specify the Coordinate Reference System, or CRS. A CRS specifies how to describe a point on Earth in terms of coordinates, and because there are many different ways to do this, there are many different CRSs. The CRS of this project is WGS84, so it's already correct by default:




Next there is a collection of fields grouped under *New attribute*. By default, a new layer has only one attribute, the id field (which you should see in the *Attributes list*) below. However, in order for the data you create to be useful, you actually need to say something about the features you'll be creating in this new layer. For our current purposes, it will be enough to add one field called name.

• Replicate the setup below, then click the *Add to attributes list* button:



• Check that your dialog now looks like this:



- Click *OK*. A save dialog will appear.
- Navigate to the exercise\_data directory.
- $\bullet$  Save your new layer as  ${\tt school\_property.shp.}$

The new layer should appear in your Layers list.


## 6.1.2 Follow Along: Data Sources

When you create new data, it obviously has to be about objects that really exist on the ground. Therefore, you'll need to get your information from somewhere.

There are many different ways to obtain data about objects. For example, you could use a GPS to capture points in the real world, then import the data into QGIS afterwards. Or you could survey points using a theodolite, and enter the coordinates manually to create new features. Or you could use the digitizing process to trace objects from remote sensing data, such as satellite imagery or aerial photography.

For our example, you'll be using the digitizing approach. Sample raster datasets are provided, so you'll need to import them as necessary.

- Click on the Add Raster Layer button:
- Navigate to exercise\_data/raster/.
- Select the file 3420C\_2010\_327\_RGB\_LATLNG.tif.
- Click Open. An image will load into your map.
- Find the new image in the *Layers list*.
- Click and drag it to the bottom of the list so that you can still see your other layers.
- Find and zoom to this area:



**Muista:** If your *buildings* layer symbology is covering part or all of the raster layer, you can temporarily disable the layer by deselecting it in the *Layers panel*. You may also wish to hide the *roads* symbology if you find it distracting.

You'll be digitizing these three fields:



In order to begin digitizing, you'll need to enter **edit mode**. GIS software commonly requires this to prevent you from accidentally editing or deleting important data. Edit mode is switched on or off individually for each layer.

To enter edit mode for the school\_property layer:

- Click on the layer in the *Layer list* to select it. (Make very sure that the correct layer is selected, otherwise you'll edit the wrong layer!)
- Click on the *Toggle Editing* button:

If you can't find this button, check that the *Digitizing* toolbar is enabled. There should be a check mark next to the  $View \rightarrow Toolbars \rightarrow Digitizing$  menu entry.

As soon as you are in edit mode, you'll see the digitizing tools are now active:



Four other relevant buttons are still inactive, but will become active when we start interacting with our new data:



From left to right on the toolbar, they are:

- Save Edits: saves changes made to the layer.
- Add Feature: start digitizing a new feature.

- *Move Feature(s)*: move an entire feature around.
- Node Tool: move only one part of a feature.
- Delete Selected: delete the selected feature.
- Cut Features: cut the selected feature.
- Copy Features: copy the selected feature.
- Paste Features: paste a cut or copied feature back into the map.

You want to add a new feature.


• Click on the *Add Feature* button now to begin digitizing our school fields.

You'll notice that your mouse cursor has become a crosshair. This allows you to more accurately place the points you'll be digitizing. Remember that even as you're using the digitizing tool, you can zoom in and out on your map by rolling the mouse wheel, and you can pan around by holding down the mouse wheel and dragging around in the map.

The first feature you'll be digitizing is the athletics field:




- Start digitizing by clicking on a point somewhere along the edge of the field.
- Place more points by clicking further along the edge, until the shape you're drawing completely covers the field.
- After placing your last point, *right-click* to finish drawing the polygon. This will finalize the feature and show you the *Attributes* dialog.
- Fill in the values as below:



• Click OK and you've created a new feature!

Remember, if you've made a mistake while digitizing a feature, you can always edit it after you're done creating it. If you've made a mistake, continue digitizing until you're done creating the feature as above. Then:

• Select the feature with the *Select Single Feature* tool:



#### You can use:

- the *Move Feature*(*s*) tool to move the entire feature,
- the Node Tool to move only one point where you may have miss-clicked,
- Delete Selected to get rid of the feature entirely so you can try again, and

• the  $Edit \rightarrow Undo$  menu item or the ctrl + z keyboard shortcut to undo mistakes.

# 6.1.3 Try Yourself

• Digitize the school itself and the upper field. Use this image to assist you:



Remember that each new feature needs to have a unique id value!

Muista: When you're done adding features to a layer, remember to save your edits and then exit edit mode.


**Muista:** You can style the fill, outline and label placement and formatting of the *school\_property* using techniques learnt in earlier lessons. In our example, we will use a dashed outline of light purple color with no fill.




• Create a new line feature called routes.shp with attributes id and type. (Use the approach above to guide you.)

• We're going to digitize two routes which are not already marked on the roads layer; one is a path, the other is a track.

Our path runs along the southern edge of the suburb of Railton, starting and ending at marked roads:



Our track is a little further to the south:



One at a time, digitize the path and the track on the *routes* layer. Try to follow the routes as accurately as possible, using points (left-click) at any corners or turns.

When creating each route, give them the type attribute value of path or track.

You'll probably find that only the points are marked; use the *Layer Properties* dialog to add styling to your routes. Feel free to give different styles to the path and track.

Save your edits and toggle *Edit* mode.

Check your results

#### 6.1.5 In Conclusion

Now you know how to create features! This course doesn't cover adding point features, because that's not really necessary once you've worked with more complicated features (lines and polygons). It works exactly the same, except that you only click once where you want the point to be, give it attributes as usual, and then the feature is created.

Knowing how to digitize is important because it's a very common activity in GIS programs.

#### 6.1.6 What's Next?

Features in a GIS layer aren't just pictures, but objects in space. For example, adjacent polygons know where they are in relation to one another. This is called *topology*. In the next lesson you'll see an example of why this can be useful.

#### 6.2 Lesson: Feature Topology

Topology is a useful aspect of vector data layers, because it minimizes errors such as overlap or gaps.


For example: if two features share a border, and you edit the border using topology, then you won't need to edit first one feature, then another, and carefully line up the borders so that they match. Instead, you can edit their shared border and both features will change at the same time.

The goal for this lesson: To understand topology using examples.


## 6.2.1 Follow Along: Snapping

To make topological editing easier, it's best if you enable snapping. This will allow your mouse cursor to snap to other objects while you digitize. To set snapping options:


- Navigate to the menu entry  $Settings \rightarrow Snapping \ Options...$
- Set up your Snapping options dialog as shown:



- Ensure that the box in the *Avoid Int*. column is checked (set to true).
- Click *OK* to save your changes and leave the dialog.
- Enter edit mode with the *landuse* layer selected.
- Check under  $View \rightarrow Toolbars$  to make sure that your Advanced Digitizing toolbar is enabled.
- Zoom to this area (enable layers and labels if necessary):



• Digitize this new (fictional) area of the Bontebok National Park:



• When prompted, give it a OGC\_FID of 999, but feel free to leave the other values unchanged.

If you're careful while digitizing and allow the cursor to snap to the vertices of adjoining farms, you'll notice that there won't be any gaps between your new farm and the existing farms adjacent to it.


• Note the undo/redo tools in the *Advanced Digitizing* toolbar:






## Follow Along: Correct Topological Features

Topology features can sometimes need to be updated. In our example, the *landuse* layer has some complex forest areas which have recently been joined to form one area:




Instead of creating new polygons to join the forest areas, we're going to use the *Node Tool* to edit the existing polygons and join them.


- Enter edit mode, if it isn't active already.
- Select the *Node Tool*.
- Pick an area of forest, select a corner and move it to an adjoining corner so two forest sections meet:




• Click and drag the nodes until they snap into place.



The topologically correct border looks like this:



Go ahead and join a few more areas using the *Node Tool*. You can also use the *Add Feature* tool if it is appropriate. If you are using our example data, you should have a forest area looking something like this:




Don't worry if you have joined more, less or different areas of forest.

## 6.2.3 Follow Along: Tool: Simplify Feature


This is the Simplify Feature tool:



- Click on it to activate it.
- Click on one of the areas which you joined using either the *Node Tool* or *Add Feature* tool. You'll see this dialog:



• Move the slider from side to side and watch what happens:



This allows you to reduce the amount of nodes in complex features.

#### • Click Ok

Notice what the tool does to the topology. The simplified polygon is now no longer touching the adjacent polygons as it should. This shows that this tool is better suited to generalizing stand-alone features. The advantage is that it provides you with a simple, intuitive interface for generalization.

Before you go on, set the polygon back to its original state by undoing the last change.



This is the *Add Ring* tool:



It allows you to take a hole out of a feature, as long as the hole is bounded on all side by the feature. For example, if you've digitized the outer boundaries of South Africa and you need to add a hole for Lesotho, you'd use this tool.

If you experiment with this tool, you'll notice that the current snapping options prevent you from creating a ring in the middle of the polygon. This would be fine if the area you wished to exclude linked to the polygon's boundaries.

- Disable snapping for the landuse layer via the dialog you used earlier.
- Now try using the Add Ring tool to create a gap in the middle of the Bontebok National Park.
- Delete your new feature by using the *Delete Ring* tool:



Muista: You need to select a corner of the ring in order to delete it.

Check your results



## Try Yourself Tool: Add Part

This is the Add Part tool:



It allows you to create an extra part of the feature, not directly connected to the main feature. For example, if you've digitized the boundaries of mainland South Africa but you haven't yet added the Prince Edward Islands, you'd use this tool to create them.

• To use this tool, you must first select the polygon to which you wish to add the part by using the *Select Single Feature* tool:



- Now try using the Add Part tool to add an outlying area to the Bontebok National Park.
- Delete your new feature by using the *Delete Part* tool:



Muista: You need to select a corner of the part in order to delete it.

Check your results




## Follow Along: Tool: Reshape Features

This is the *Reshape Features* tool:




It can add a bump to an existing feature. With this tool selected:

- Left-click inside the Bontebok National Park to start drawing a polygon.
- Draw a polygon with three corners, the last of which should be back inside the original polygon, forming an open-sided rectangle.
- Right-click to finish marking points:




This will give a result similar to:




You can do the opposite, too:

- Click outside the polygon.
- Draw a rectangle into the polygon.
- Right-click outside the polygon again:



The result of the above:



# 6.2.7 Try Yourself Tool: Split Features


The *Split Features* tool is similar to how you took part of the farm away, except that it doesn't delete either of the two parts. Instead, it keeps them both.




• First, re-enable snapping for the *landuse* layer.

We will use the tool to split a corner from the Bontebok National Park.

• Select the *Split Features* tool and click on a vertex to begin drawing a line. Click the vertex on the opposite side of the corner you wish to split and right-click to complete the line:



- At this point, it may seem as if nothing has happened. But remember that your symbology for the landuse layer does not have any border, so the new division line will not be shown.
- Use the Select Single Feature tool to select the corner you just split; the new feature will now be highlighted:



# 6.2.8 Try Yourself Tool: Merge Features

Now we will re-join the feature you just created to the original polygon:

- Experiment with the Merge Selected Features and Merge Attributes of Selected Features tools.
- Note the differences.

Check your results

#### 6.2.9 In Conclusion

Topology editing is a powerful tool that allows you to create and modify objects quickly and easily, while ensuring that they remain topologically correct.

#### 6.2.10 What's Next?

Now you know how to digitize the shape of the objects easily, but adding in the attributes is still a bit of a headache! Next we'll show you how to use forms so that attribute editing is simpler and more effective.

#### 6.3 Lesson: Forms

When you add new data via digitizing, you're presented with a dialog that lets you fill in the attributes for that feature. However, this dialog is not, by default, very nice to look at. This can cause a usability problem, especially if you have large datasets to create, or if you want other people to help you digitize and they find the default forms to be confusing.

Fortunately, QGIS lets you create your own custom dialogs for a layer. This lesson shows you how.

The goal for this lesson: To create a form for a layer.



### Follow Along: Using QGIS' Form Design Functionality


- Select the *roads* layer in the *Layers list*.
- Enter Edit Mode as before.
- Open its Attribute Table.
- Right-click on any cell in the table. A short menu will appear, with the only entry being *Open form*.
- Click on it to see the form that QGIS generates for this layer.

Obviously it would be nice to be able to do this while looking at the map, rather than needing to search for a specific street in the *Attribute Table* all the time.

- Select the *roads* layer in the *Layers list*.
- Using the *Identify* tool, click on any street in the map.



- The *Identify Results* panel opens and shows in a tree view the fields values and other general information about the clicked feature.
- At the bottom of the panel, Check the Auto open form checkbox
- Now, click again on any street in the map. Along the previous *Identify Results* dialog, you'll see the now-familiar form:



• Each time you click on a single feature with the *Identify* tool, its form pops-up unless the *Auto open form* is unchecked.




### Try Yourself Using the Form to Edit Values

If you are in edit mode, you can use this form to edit a feature's attributes.

6.3. Lesson: Forms

- Activate edit mode (if it isn't already activated).
- Using the *Identify* tool, click on the main street running through Swellendam:



- Edit its highway value to be secondary.
- Save your edits.
- Exit edit mode.
- Open the *Attribute Table* and note that the value has been updated in the attributes table and therefore in the source data.


Muista: If you're using the default dataset, you'll find that there is more than one road on this map called Voortrek Street.



## Follow Along: Setting Form Field Types


It's nice to edit things using a form, but you still have to enter everything by hand. Fortunately, forms have different kinds of so-called *widgets* that allow you to edit data in various different ways.

- Open the *roads* layer's *Layer Properties*.
- Switch to the *Fields* tab. You'll see this:



- Click on the Line edit button in the same row as man\_made and you'll be given a new dialog.
- Select *Checkbox* in the list of options:

6.3. Lesson: Forms



- Click OK.
- Enter edit mode (if the *roads* layer is not already in edit mode.
- Click on the *Identify* tool.
- Click on the same main road you chose earlier.

You'll now see that the *man\_made* attribute has a checkbox next to it denoting True (checked) or False (unchecked).




Set a more appropriate form widget for the highway field.

Check your results



You can also design your own custom form completely from scratch.


- Create a simple point layer named test-data with two attributes:
  - Name (text)
  - Age (text)



• Capture a few points on your new layer using the digitizing tools so that you have a little data to play with. You should be presented with the default QGIS generated attribute capture form each time you capture a new point.

Muista: You may need to disable Snapping if still enabled from earlier tasks.

6.3. Lesson: Forms



# 6.3.6


## Follow Along: Creating a New Form

Now we want to create our own custom form for the attribute data capture phase. To do this, you need to have *Qt4 Designer* installed (only needed for the person who creates the forms). It should be provided as part of your course materials, if you're using Windows. You may need to look for it if you're using another OS. In Ubuntu, do the following in the terminal:

**Muista:** At the time of writing, Qt5 is the latest version available. However, this process specifically requires Qt4 and is not necessarily compatible with Qt5.

sudo apt-get install qt4-designer

- ... and it should install automatically. Otherwise, look for it in the Software Center.
  - Start *Designer* by opening its *Start Menu* entry in Windows (or whatever approach is appropriate in your OS).
  - In the dialog that appears, create a new dialog:



- Look for the Widget Box along the left of your screen (default). It contains an item called Line Edit.
- Click and drag this item into your form. This creates a new *Line Edit* in the form.
- With the new line edit element selected, you'll see its *properties* along the side of your screen (on the right by default):

6.3. Lesson: Forms

| O O Property Editor  |                    |  |
|----------------------|--------------------|--|
|                      |                    |  |
| Filter - P           |                    |  |
| lineEdit : QLineEdit |                    |  |
| Pro                  | perty              | Value  |
|                      | QObject            |  |
|                      | objectName         | lineEdit •   |
| 7                    | QWidget            |  |
|                      | enabled            | ✓  |
| ▶                    | geometry           | [(80, 40), 113 x 21]                                   |
| ▶                    | sizePolicy         | [Expanding, Fixed, 0, 0]                               |
| ▶                    | minimumSize        | 0 x 0  |
| ▶                    | maximumSize        | 16777215 x 16777215                                    |
| ▶                    | sizeIncrement      | 0 x 0  |
| ▶                    | baseSize           | 0 x 0  |
|                      | palette            | Inherited  |
| ▶                    | font               | A [.Lucida Grande UI, 13]                              |
|                      | cursor             | Ĭ lBeam  |
|                      | mouseTracking      |  |
|                      | focusPolicy        | StrongFocus  |
|                      | contextMenuPolicy  | DefaultContextMenu                                     |
|                      | acceptDrops        | ✓  |
| ▶                    | toolTip            |  |
| ▶                    | statusTip          |  |
| ▶                    | whatsThis          |  |
| ▶                    | accessibleName     |  |
| ▶                    | accessibleDescrip  |  |
|                      | layoutDirection    | LeftToRight  |
|                      | autoFillBackground |  |
|                      | styleSheet         |  |
| ▶                    | locale             | English, SouthAfrica                                   |
| ▶                    | inputMethodHints   | ImhNone  |
| V                    |                    |  |
| ▶                    | inputMask          |  |
| <b></b>              | text               |  |
|                      | maxLength          | 32767  |
|                      | frame              | ✓  |
|                      | echoMode           | Normal   |
|                      | cursorPosition     | 0  |
| <b></b>              | alignment          | AlignLeft, AlignVCenter                                |
|                      | dragEnabled        |  |
|                      | readOnly           |  |
| <b>&gt;</b>          | placeholderText    |  |
| 30                   | cursorMoveStyle    | LogicalMoveStyle Chapter 6. Module: Creating Vector Da |


- Set its name to Name.
- Using the same approach, create a new spinbox and set its name to Age.
- Add a *Label* with the text Add a New Person in a bold font (look in the object *properties* to find out how to set this). Alternatively, you may want to set the title of the dialog itself (rather than adding a label).
- Click anywhere in your dialog.
- Find the *Lay Out Vertically* button (in a toolbar along the top edge of the screen, by default). This lays out your dialog automatically.
- Set the dialog's maximum size (in its properties) to 200 (width) by 100 (height).
- Save your new form as exercise\_data/forms/add\_people.ui.
- When it's done saving, you can close the Qt4 Designer program.

### 6.3.7 🥏

## Follow Along: Associating the Form with Your Layer

- · Go back to QGIS.
- Double click the *test-data* layer in the legend to access its properties.
- Click on the Fields tab in the Layer Properties dialog.
- In the Attribute editor layout dropdown, select Provide ui-file.
- Click the ellipsis button and choose the add\_people.ui file you just created:

6.3. Lesson: Forms



- Click OK on the Layer Properties dialog.
- Enter edit mode and capture a new point.
- When you do so, you will be presented with your custom dialog (instead of the generic one that QGIS usually creates).
- If you click on one of your points using the *Identify* tool, you can now bring up the form by right clicking in the identify results window and choosing *View Feature Form* from the context menu.
- If you are in edit mode for this layer, that context menu will show *Edit Feature Form* instead, and you can then adjust the attributes in the new form even after initial capture.

#### 6.3.8 In Conclusion

Using forms, you can make life easier for yourself when editing or creating data. By editing widget types or creating an entirely new form from scratch, you can control the experience of someone who digitizes new data for that layer, thereby minimizing misunderstandings and unnecessary errors.

#### 6.3.9 Further Reading

If you completed the advanced section above and have knowledge of Python, you may want to check out this blog entry about creating custom feature forms with Python logic, which allows advanced functions including data validation, autocompletion, etc.

#### 6.3.10 What's Next?

Opening a form on identifying a feature is one of the standard actions that QGIS can perform. However, you can also direct it to perform custom actions that you define. This is the subject of the next lesson.

#### 6.4 Lesson: Actions

Now that you've seen a default action in the previous lesson, it's time to define your own actions. An action is something that happens when you click on a feature. It can add a lot of extra functionality to your map, allowing you to retrieve additional information about an object, for example. Assigning actions can add a whole new dimension to your map!

The goal for this lesson: To learn how to add custom actions.




Use the *school\_property* layer you created previously. The course materials include photos of each of the three properties you digitized. What we're going to do next is to associate each property with its image. Then we'll create an action that will open the image for a property when clicking on the property.

## 6.4.2 Follow Along: Add a Field for Images


The *school\_property* layer has no way to associate an image with a property yet. First we'll create a field for this purpose.

- Open the Layer Properties dialog.
- Click on the Fields tab.
- Toggle editing mode:

6.4. Lesson: Actions




• Add a new column:




• Enter the values below:

6.4. Lesson: Actions




- After the field has been created, click on the *Line edit* button next to the new field.
- Set it up for a *File name*:



- Click OK on the Layer Properties dialog.
- Use the *Identify* tool to click on one of the three features in the *school\_property* layer.

Since you're still in edit mode, the dialog should be active and look like this:


6.4. Lesson: Actions



- Click on the browse button (the ... next to the *image* field).
- Select the path for your image. The images are in exercise\_data/school\_property\_photos/ and are named the same as the features they should be associated with.
- Click OK.
- Associate all of the images with the correct features using this method.
- Save your edits and exit edit mode.

## 6.4.3 Follow Along: Creating an Action

- Open the Actions form for the school\_property layer.
- In the Action properties panel, enter the words Show Image into the Name field:



What to do next varies according to your operating system, so choose the appropriate course to follow:

#### **Windows**

• Click on the *Type* dropdown and choose *Open*.

#### **Ubuntu Linux**

• Under *Action*, write eog for the *Gnome Image Viewer*, or write display to use *ImageMagick*. Remember to put a space after the command!

#### **MacOS**


- Click on the *Type* dropdown and choose *Mac*.
- Under Action, write open. Remember to put a space after the command!

6.4. Lesson: Actions

#### Continue writing the command

You want to open the image, and QGIS knows where the image is. All it needs to do is to tell the *Action* where the image is.

• Select *image* from the list:



- Click the Insert field button. QGIS will add the phrase [% "image" %] in the Action field.
- Click the *Add to action list* button.
- Click OK on the Layer Properties dialog.

Now we will test the new Action:

- Click on the school\_property layer in the Layers list so that it is highlighted.
- Find the *Run feature action* button (on the same toolbar as the *Open Attribute Table* button):



- Click on the down arrow to the right of this button. There's only one action defined for this layer so far, which is the one you just created.
- Click the button itself to activate the tool.
- Using this tool, click on any of the three school properties.
- The image for that property will now open.



### Follow Along: Searching the Internet

Let's say we're looking at the map and want to know more about the area that a farm is in. Suppose you know nothing of the area in question and want to find general information about it. Your first impulse, considering that you're using a computer right now, would probably be to Google the name of the area. So let's tell QGIS to do that automatically for us!

• Open the attribute table for the *landuse* layer.

We'll be using the name field for each of our landuse areas to search Google.

- Close the attribute table.
- Go back to Actions in Layer Properties.
- In the field  $Action\ Properties \rightarrow Name$ , write Google Search.

What to do next varies according to your operating system, so choose the appropriate course to follow:

#### **Windows**

• Under *Type*, choose *Open*. This will tell Windows to open an Internet address in your default browser, such as Internet Explorer.

#### **Ubuntu Linux**

• Under *Action*, write xdg-open. This will tell Ubuntu to open an Internet address in your default browser, such as Chrome or Firefox.

#### **MacOS**

• Under Action, write open. This will tell MacOS to open an Internet address in your default browser, such as Safari.

#### Continue writing the command

Whichever command you used above, you need to tell it which Internet address to open next. You want it to visit Google, and to search for a phrase automatically.


Usually when you use Google, you enter your search phrase into the Google Search bar. But in this case, you want your computer to do this for you. The way you tell Google to search for something (if you don't want to use its search bar directly) is by giving your Internet browser the address http://www.google.com/search?q=SEARCH\_PHRASE, where SEARCH\_PHRASE is what you want to search for. Since we don't know what phrase to search for yet, we'll just enter the first part (without the search phrase).

• In the *Action* field, write http://www.google.com/search?q=. Remember to add a space after your initial command before writing this in!


Now you want QGIS to tell the browser to tell Google to search for the value of name for any feature that you could click on.

- Select the *name* field.
- Click Insert field:

6.4. Lesson: Actions 141



This will tell QGIS to add the phrase next:



What this means is that QGIS is going to open the browser and send it to the address http://www.google.com/search?q=[% "name" %]. But [% "name" %] tells QGIS to use the contents of the name field as the phrase to search for.

So if, for example, the landuse area you click on is named Marloth Nature Reserve, then QGIS is going to send the browser to http://www.google.com/search?q=Marloth%20Nature%20Reserve, which will cause your browser to visit Google, which will in turn search for "Marloth Nature Reserve".

- If you haven't done so already, set everything up as explained above.
- Click the *Add to action list* button. The new action will appear in the list above.
- Click OK on the Layer Properties dialog.

Now to test the new action.

- With the *landuse* layer active in the *Layers list*, click on the *Run feature action* button.
- Click on any landuse area you can see on the map. Your browser will now open, and will automatically start a Google search for the town that is recorded as that area's name value.

**Muista:** If your action doesn't work, check that everything was entered correctly; typos are common with this kind of work!



### Follow Along: Open a Webpage Directly in QGIS

Above, you've seen how to open a webpage in an external browser. There are some shortcomings with this approach in that it adds an unknowable dependency – will the end-user have the software required to execute the action on their system? As you've seen, they don't necessarily even have the same kind of base command for the same kind of action, if you don't know which OS they'll be using. With some OS versions, the above commands to open the browser might not work at all. This could be an insurmountable problem.

However, QGIS sits on top of the incredibly powerful and versatile Qt4 library. Also, QGIS actions can be arbitrary, tokenized (i.e. using variable information based on the contents of a field attribute) Python commands!

Now you'll see how to use a python action to show a web page. It's the same general idea as opening a site in an external browser, but it requires no browser on the user's system since it uses the Qt4 QWebView class (which is a webkit based html widget) to display the content in a pop up window.


Instead of Google, let's use Wikipedia this time. So the URL you request will look like this:

http://wikipedia.org/wiki/SEARCH\_PHRASE

To create the layer action:

- Open the Layer Properties dialog and head over to the Actions tab.
- Set up a new action using the following properties for the action:
  - Type: Python
  - Name: Wikipedia
  - Action (all on one line): from PyQt4.QtCore import QUrl; from
    PyQt4.QtWebKit import QWebView; myWV = QWebView(None);
    myWV.load(QUrl('http://wikipedia.org/wiki/[% "name" %]'));
    myWV.show()

6.4. Lesson: Actions 143



There are a couple of things going on here:

- All the python code is in a single line with semi-colons separating commands (instead of newlines, the usual way of separating Python commands).
- [% "name" %] will be replaced by the actual attribute value when the action is invoked (as before).
- The code simply creates a new QWebView instance, sets its URL, and then calls show () on it to make it visible as a window on the user's desktop.

Note that this is a somewhat contrived example. Python works with semantically significant indentation, so separating things with semicolons isn't the best way to write it. So, in the real world, you'd be more likely to import your logic from a Python module and then call a function with a field attribute as parameter.

You could equally use the approach to display an image without requiring that the user has a particular image viewer on their system.

• Try using the methods described above to load a Wikipedia page using the Wikipedia action you just created.

#### 6.4.6 In Conclusion

Actions allow you to give your map extra functionality, useful to the end-user who views the same map in QGIS. Due to the fact that you can use shell commands for any operating system, as well as Python, the sky's the limit in terms of the functions you could incorporate!

### 6.4.7 What's Next?

Now that you've done all kinds of vector data creation, you'll learn how to analyze this data to solve problems. That's the topic of the next module.

6.4. Lesson: Actions 145

### **Module: Vector Analysis**

Now that you have edited a few features, you must want to know what else one can do with them. Having features with attributes is nice, but when all is said and done, this doesn't really tell you anything that a normal, non-GIS map can't.

The key advantage of a GIS is this: a GIS can answer questions.

For the next three modules, we'll endeavor to answer a *research question* using GIS functions. For example, you are an estate agent and you are looking for a residential property in Swellendam for clients who have the following criteria:

- 1. It needs to be in Swellendam.
- 2. It must be within reasonable driving distance of a school (say 1km).
- 3. It must be more than 100m squared in size.
- 4. Closer than 50m to a main road.
- 5. Closer than 500m to a restaurant.

Within the next few modules, we'll harness the power of GIS analysis tools to locate suitable farm properties for this new residential development.

### 7.1 Lesson: Reprojecting and Transforming Data

Let's talk about Coordinate Reference Systems (CRSs) again. We've touched on this briefly before, but haven't discussed what it means practically.

The goal for this lesson: To reproject and transform vector datasets.

## 7.1.1 Follow Along: Projections

The CRS that all the data as well as the map itself are in right now is called WGS84. This is a very common Geographic Coordinate System (GCS) for representing data. But there's a problem, as we will see.

- Save your current map.
- Then open the map of the world which you'll find under exercise\_data/world/world.qgs.
- Zoom in to South Africa by using the *Zoom In* tool.
- Try setting a scale in the *Scale* field, which is in the *Status Bar* along the bottom of the screen. While over South Africa, set this value to 1:5000000 (one to five million).
- Pan around the map while keeping an eye on the Scale field.

Notice the scale changing? That's because you're moving away from the one point that you zoomed into at 1:5000000, which was at the center of your screen. All around that point, the scale is different.

To understand why, think about a globe of the Earth. It has lines running along it from North to South. These longitude lines are far apart at the equator, but they meet at the poles.

In a GCS, you're working on this sphere, but your screen is flat. When you try to represent the sphere on a flat surface, distortion occurs, similar to what would happen if you cut open a tennis ball and tried to flatten it out. What this means on a map is that the longitude lines stay equally far apart from each other, even at the poles (where they are supposed to meet). This means that, as you travel away from the equator on your map, the scale of the objects that you see gets larger and larger. What this means for us, practically, is that there is no constant scale on our map!

To solve this, let's use a Projected Coordinate System (PCS) instead. A PCS "projects" or converts the data in a way that makes allowance for the scale change and corrects it. Therefore, to keep the scale constant, we should reproject our data to use a PCS.

### 7.1.2 Follow Along: "On the Fly" Reprojection

QGIS allows you to reproject data "on the fly". What this means is that even if the data itself is in another CRS, QGIS can project it as if it were in a CRS of your choice.

• To enable "on the fly" projection, click on the CRS Status button in the Status Bar along the bottom of the QGIS window:



- In the dialog that appears, check the box next to Enable 'on the fly' CRS transformation.
- Type the word global into the Filter field. One CRS (NSIDC EASE-Grid Global) should appear in the list below.
- Click on the NSIDC EASE-Grid Global to select it, then click OK.
- Notice how the shape of South Africa changes. All projections work by changing the apparent shapes of objects on Earth.
- Zoom in to a scale of 1:5000000 again, as before.
- Pan around the map.
- Notice how the scale stays the same!

"On the fly" reprojection is also used for combining datasets that are in different CRSs.

- Deactivate "on the fly" re-projection again:
  - Click on the CRS Status button again.
  - Un-check the Enable 'on the fly' CRS transformation box.
  - Clicking OK.
- In QGIS 2.0, the 'on the fly' reprojection is automatically activated when layers with different CRSs are loaded in the map. To understand what 'on the fly' reprojection does, deactivate this automatic setting:
  - **–** Go to *Settings*  $\rightarrow$  *Options*...
  - On the left panel of the dialog, select CRS.
  - Un-check Automatically enable 'on the fly' reprojection if layers have different CRS.
  - Click OK.
- · Add another vector layer to your map which has the data for South Africa only. You'll find it as exercise data/world/RSA.shp.

What do you notice?

The layer isn't visible! But that's easy to fix, right?

- Right-click on the RSA layer in the Layers list.
- Select Zoom to Layer Extent.

OK, so now we see South Africa... but where is the rest of the world?

It turns out that we can zoom between these two layers, but we can't ever see them at the same time. That's because their Coordinate Reference Systems are so different. The *continents* dataset is in *degrees*, but the *RSA* dataset is in *meters*. So, let's say that a given point in Cape Town in the *RSA* dataset is about 4 100 000 meters away from the equator. But in the *continents* dataset, that same point is about 33.9 degrees away from the equator.


This is the same distance - but QGIS doesn't know that. You haven't told it to reproject the data. So as far as it's concerned, the version of South Africa that we see in the *RSA* dataset has Cape Town at the correct distance of 4 100 000 meters from the equator. But in the *continents* dataset, Cape Town is only 33.9 *meters* away from the equator! You can see why this is a problem.

QGIS doesn't know where Cape Town is *supposed* to be - that's what the data should be telling it. If the data tells QGIS that Cape Town is 34 meters away from the equator and that South Africa is only about 12 meters from north to south, then that is what QGIS will draw.

To correct this:

- Click on the CRS Status button again and switch Enable 'on the fly' CRS transformation on again as before.
- Zoom to the extents of the RSA dataset.

Now, because they're made to project in the same CRS, the two datasets fit perfectly:



When combining data from different sources, it's important to remember that they might not be in the same CRS. "On the fly" reprojection helps you to display them together.

Before you go on, you probably want to have the 'on the fly' reprojection to be automatically activated whenever you open datasets having different CRS:

- Open again Settings  $\rightarrow$  Options... and select CRS.
- Activate Automatically enable 'on the fly' reprojection if layers have different CRS.

### 7.1.3

### Follow Along: Saving a Dataset to Another CRS

Remember when you calculated areas for the buildings in the *Classification* lesson? You did it so that you could classify the buildings according to area.


- Open your usual map again (containing the Swellendam data).
- Open the attribute table for the *buildings* layer.
- Scroll to the right until you see the AREA field.

Notice how the areas are all very small; probably zero. This is because these areas are given in degrees - the data isn't in a Projected Coordinate System. In order to calculate the area for the farms in square meters, the data has to be in square meters as well. So, we'll need to reproject it.

But it won't help to just use 'on the fly' reprojection. 'On the fly' does what it says - it doesn't change the data, it just reprojects the layers as they appear on the map. To truly reproject the data itself, you need to export it to a new file using a new projection.

- Right-click on the buildings layer in the Layers list.
- Select Save As... in the menu that appears. You will be shown the Save vector layer as... dialog.
- Click on the Browse button next to the Save as field.
- Navigate to exercise\_data/ and specify the name of the new layer as buildings\_reprojected.shp.
- Leave the Encoding unchanged.
- Change the value of the *Layer CRS* dropdown to *Selected CRS*.
- Click the *Browse* button beneath the dropdown.
- The CRS Selector dialog will now appear.
- In its *Filter* field, search for 34S.
- Choose WGS 84 / UTM zone 34S from the list.
- Leave the Symbology export unchanged.


The Save vector layer as... dialog now looks like this:



- Click OK.
- Start a new map and load the reprojected layer you just created.


Refer back to the lesson on Classification to remember how you calculated areas.

• Update (or add) the AREA field by running the same expression as before:



This will add an AREA field with the size of each building in square meters

• To calculate the area in another unit of measurement, for example hectares, use the AREA field to create a second column:




Look at the new values in your attribute table. This is much more useful, as people actually quote building size in meters, not in degrees. This is why it's a good idea to reproject your data, if necessary, before calculating areas, distances, and other values that are dependent on the spatial properties of the layer.

## 7.1.4 Follow Along: Creating Your Own Projection

There are many more projections than just those included in QGIS by default. You can also create your own projections.

- Start a new map.
- $\bullet$   $Load\ the\ {\tt world/oceans.shp}$  dataset.
- Go to Settings  $\rightarrow$  Custom CRS... and you'll see this dialog:



• Click on the *Add new CRS* button to create a new projection.


An interesting projection to use is called Van der Grinten I.

• Enter its name in the *Name* field.


This projection represents the Earth on a circular field instead of a rectangular one, as most other projections do.

• For its parameters, use the following string:

```
+proj=vandg +lon_0=0 +x_0=0 +y_0=0 +R_A +a=6371000 +b=6371000 +units=m +no_defs
```



- Click OK.
- Enable "on the fly" reprojection.
- Choose your newly defined projection (search for its name in the *Filter* field).
- On applying this projection, the map will be reprojected thus:



#### 7.1.5 In Conclusion

Different projections are useful for different purposes. By choosing the correct projection, you can ensure that the features on your map are being represented accurately.

### 7.1.6 Further Reading

Materials for the Advanced section of this lesson were taken from this article.

Further information on Coordinate Reference Systems is available here.

#### 7.1.7 What's Next?

In the next lesson you'll learn how to analyze vector data using QGIS' various vector analysis tools.

### 7.2 Lesson: Vector Analysis

Vector data can also be analyzed to reveal how different features interact with each other in space. There are many different analysis-related functions in GIS, so we won't go through them all. Rather, we'll pose a question and try to solve it using the tools that QGIS provides.

The goal for this lesson: To ask a question and solve it using analysis tools.

## 7.2.1 The GIS Process

Before we start, it would be useful to give a brief overview of a process that can be used to solve any GIS problem. The way to go about it is:

- 1. State the Problem
- 2. Get the Data
- 3. Analyze the Problem
- 4. Present the Results

## 7.2.2 The problem

Let's start off the process by deciding on a problem to solve. For example, you are an estate agent and you are looking for a residential property in Swellendam for clients who have the following criteria:

- 1. It needs to be in Swellendam.
- 2. It must be within reasonable driving distance of a school (say 1km).
- 3. It must be more than 100m squared in size.
- 4. Closer than 50m to a main road.
- 5. Closer than 500m to a restaurant.

## 7.2.3 The data

To answer these questions, we're going to need the following data:

- 1. The residential properties (buildings) in the area.
- 2. The roads in and around the town.
- 3. The location of schools and restaurants.
- 4. The size of buildings.


All of this data is available through OSM and you should find that the dataset you have been using throughout this manual can also be used for this lesson. However, in order to ensure we have the complete data, we will re-download the data from OSM using QGIS' built-in OSM download tool.

**Muista:** Although OSM downloads have consistent data fields, the coverage and detail does vary. If you find that your chosen region does not contain information on restaurants, for example, you may need to chose a different region.

### 7.2.4 Foll

### Follow Along: Start a Project

- Start a new QGIS project.
- Use the OpenStreetMap data download tool found in the *Vector* → *OpenStreetMap* menu to download the data for your chosen region.
- Save the data as osm\_data.osm in your exercise\_data folder.
- Note that the *osm* format is a type of vector data. Add this data as a vector layer as usually *Layer* → *Add vector layer...*, browse to the new osm\_data.osm file you just downloaded. You may need to select *Show All Files* as the file format.
- Select osm data.osm and click Open
- In the dialog which opens, select all the layers, *except* the other\_relations and multilinestrings layer:



This will import the OSM data as separate layers into your map.

The data you just downloaded from OSM is in a geographic coordinate system, WGS84, which uses latitude and longitude coordinates, as you know from the previous lesson. You also learnt that to calculate distances in meters, we need to work with a projected coordinate system. Start by setting your project's coordinate system to a suitable *CRS* for your data, in the case of Swellendam, *WGS* 84 / *UTM zone* 34S:


- Open the Project Properties dialog, select CRS and filter the list to find WGS 84 / UTM zone 34S.
- Click OK.

We now need to extract the information we need from the OSM dataset. We need to end up with layers representing all the houses, schools, restaurants and roads in the region. That information is inside the *multipolygons* layer and can be extracted using the information in its *Attribute Table*. We'll start with the schools layer:

- Right-click on the *multipolygons* layer in the *Layers list* and open the *Layer Properties*.
- Go to the General menu.
- Under Feature subset click on the [Query Builder] button to open the Query builder dialog.
- In the *Fields* list on the left of this dialog until you see the field amenity.
- Click on it once.
- Click the *All* button underneath the *Values* list:

Now we need to tell QGIS to only show us the polygons where the value of amenity is equal to school.

- Double-click the word amenity in the *Fields* list.
- Watch what happens in the *Provider specific filter expression* field below:



The word "amenity" has appeared. To build the rest of the query:

- Click the = button (under *Operators*).
- Double-click the value school in the Values list.
- Click OK twice.

This will filter OSM's multipolygons layer to only show the schools in your region. You can now either:

- $\bullet$  Rename the filtered OSM layer to schools and re-import the multipolygons layer from  $\texttt{osm\_data.osm}, OR$
- Duplicate the filtered layer, rename the copy, clear the Query Builder and create your new query in the *Query Builder*.



### Try Yourself Extract Required Layers from OSM

Using the above technique, use the Query Builder tool to extract the remaining data from OSM to create the following layers:

- roads (from OSM's lines layer)
- restaurants (from OSM's multipolygons layer)

• houses (from OSM's multipolygons layer)

You may wish to re-use the roads. shp layer you created in earlier lessons.

#### Check your results

- Save your map under *exercise\_data*, as analysis.qgs (this map will be used in future modules).
- In your operating system's file manager, create a new folder under *exercise\_data* and call it residential\_development. This is where you'll save the datasets that will be the results of the analysis functions.



### Try Yourself Find important roads


Some of the roads in OSM's dataset are listed as unclassified, tracks, path and footway. We want to exclude these from our roads dataset.

• Open the Query Builder for the roads layer, click Clear and build the following query:

```
"highway" != 'NULL' AND "highway" != 'unclassified' AND "highway" != 'track' AND "highway" != 'path' AND "highway" != 'footway'
```

You can either use the approach above, where you double-clicked values and clicked buttons, or you can copy and paste the command above.

This should immediately reduce the number of roads on your map:






### Try Yourself Convert Layers' CRS

Because we are going to be measuring distances within our layers, we need to change the layers' CRS. To do this, we need to select each layer in turn, save the layer to a new shapefile with our new projection, then import that new layer into our map.

Muista: In this example, we are using the WGS 84 / UTM zone 34S CRS, but you may use a UTM CRS which is

more appropriate for your region.

- Right click the roads layer in the Layers panel.
- Click Save as...
- In the Save Vector As dialog, choose the following settings and click Ok (making sure you select Add saved file to map):



The new shapefile will be created and the resulting layer added to your map.

**Muista:** If you don't have activated *Enable 'on the fly' CRS transformation* or the *Automatically enable 'on the fly' reprojection if layers have different CRS* settings (see previous lesson), you might not be able to see the new layers you just added to the map. In this case, you can focus the map on any of the layers by right click on any layer and click *Zoom to layer extent*, or just enable any of the mentioned 'on the fly' options.

• Remove the old roads layer.

Repeat this process for each layer, creating a new shapefile and layer with "\_34S" appended to the original name and removing each of the old layers.

Once you have completed the process for each layer, right click on any layer and click *Zoom to layer extent* to focus the map to the area of interest.

Now that we have converted OSM's data to a UTM projection, we can begin our calculations.


# 7.2.8 Follow Along: Analyzing the Problem: Distances From Schools and Roads

QGIS allows you to calculate distances from any vector object.

- Make sure that only the *roads\_34S* and *houses\_34S* layers are visible, to simplify the map while you're working.
- Click on the  $Vector \rightarrow Geoprocessing\ Tools \rightarrow Fixed\ distance\ buffer\ tool:$

This gives you a new dialog.


• Set it up like this:



The *Distance* is in meters because our input dataset is in a Projected Coordinate System that uses meter as its basic measurement unit. This is why we needed to use projected data.


- Save the resulting layer under exercise\_data/residential\_development/ as roads\_buffer\_50m.shp.
- Click *OK* and it will create the buffer.
- When it asks you if it should "add the new layer to the TOC", click *Yes.* ("TOC" stands for "Table of Contents", by which it means the *Layers list*).
- Close the *Fixed distance buffer* dialog.

Now your map will look something like this:




If your new layer is at the top of the Layers list, it will probably obscure much of your map, but this gives us all the areas in your region which are within 50m of a road.

However, you'll notice that there are distinct areas within our buffer, which correspond to all the individual roads. To get rid of this problem, remove the layer and re-create the buffer using the settings shown here:



- Note that we're now checking the *Dissolve result* box.
- Save the output under the same name as before (click *Yes* when it asks your permission to overwrite the old one).
- Click OK and close the Fixed distance buffer dialog again.

Once you've added the layer to the Layers list, it will look like this:



Now there are no unnecessary subdivisions.

## 7.2.9 Try Yourself Distance from schools


• Use the same approach as above and create a buffer for your schools.

It needs to be 1  $\,$  km in radius, and saved under the usual directory as <code>schools\_buffer\_1km.shp</code>.

Check your results


## 7.2.10 Follow Along: Overlapping Areas

Now we have areas where the road is 50 meters away and there's a school within 1 km (direct line, not by road). But obviously, we only want the areas where both of these criteria are satisfied. To do that, we'll need to use the *Intersect* tool. Find it under  $Vector \rightarrow Geoprocessing\ Tools \rightarrow Intersect$ . Set it up like this:




The two input layers are the two buffers; the save location is as usual; and the file name is road\_school\_buffers\_intersect.shp. Once it's set up like this, click *OK* and add the layer to the *Layers list* when prompted.

In the image below, the blue areas show us where both distance criteria are satisfied at once!



You may remove the two buffer layers and only keep the one that shows where they overlap, since that's what we really wanted to know in the first place:




## 7.2.11 Follow Along: Select the Buildings


Now you've got the area that the buildings must overlap. Next, you want to select the buildings in that area.

• Click on the menu entry  $Vector \rightarrow Research\ Tools \rightarrow Select\ by\ location$ . A dialog will appear.

• Set it up like this:




- Click OK, then Close.
- You'll probably find that not much seems to have changed. If so, move the school\_roads\_intersect layer to the bottom of the layers list, then zoom in:



The buildings highlighted in yellow are those which match our criteria and are selected, while the buildings in green are those which do not. We can now save the selected buildings as a new layer.

- Right-click on the *houses\_34S* layer in the *Layers list*.
- Select Save Selection As....
- Set the dialog up like this:



- The file name is well\_located\_houses.shp.
- Click OK.

Now you have the selection as a separate layer and can remove the houses\_34S layer.

## 7.2.12 Try Yourself Further Filter our Buildings

We now have a layer which shows us all the buildings within 1km of a school and within 50m of a road. We now need to reduce that selection to only show buildings which are within 500m of a restaurant.


Using the processes described above, create a new layer called houses\_restaurants\_500m which further filters your well\_located\_houses layer to show only those which are within 500m of a restaurant.

Check your results




To see which buildings are the correct size (more than 100 square meters), we first need to calculate their size.

- Open the attribute table for the *houses\_restaurants\_500m* layer.
- Enter edit mode and open the field calculator.
- Set it up like this:



- If you can't find AREA in the list, try creating a new field as you did in the previous lesson of this module.
- Click OK.
- Scroll to the right of the attribute table; your AREA field now has areas in metres for all the buildings in your *houses\_restaurants\_500m* layer.
- Click the edit mode button again to finish editing, and save your edits when prompted.
- Build a query as earlier in this lesson:



• Click *OK*. Your map should now only show you those buildings which match our starting criteria and which are more than 100m squared in size.

## 7.2.14 Try Yourself

• Save your solution as a new layer, using the approach you learned above for doing so. The file should be saved under the usual directory, with the name solution.shp.

### 7.2.15 In Conclusion

Using the GIS problem-solving approach together with QGIS vector analysis tools, you were able to solve a problem with multiple criteria quickly and easily.

#### 7.2.16 What's Next?

In the next lesson, we'll look at how to calculate the shortest distance along the road from one point to another.

### 7.3 Lesson: Network Analysis

Calculating the shortest distance between two points is a commonly cited use for GIS. QGIS ships with this tool, but it's not visible by default. In this brief lesson, we'll show you what you need to get started.

The goal for this lesson: To activate, configure and use the *Road Graph* plugin.

## 7.3.1

### Follow Along: Activate the Tool

QGIS has many plugins that add to its basic functions. Many of these plugins are so useful that they ship along with the program straight out of the box. They're still hidden by default, though. So in order to use them, you need to activate them first.

To activate the Road Graph plugin:


- Start the *Plugin Manager* by clicking on the QGIS main window's menu item *Plugins* → *Manage and Install Plugins*.... A dialog appears.
- Select the plugin like this:



• Click *Close* on the *Plugin Manager* dialog.

**Muista:** If you do not see the plugin in your interface, go to  $View \rightarrow Panels$  and ensure that *Shortest path* has a check mark next to it.

This panel will appear in your interface:




## 7.3.2 Follow Along: Configure the Tool

To have a layer to calculate on, first save your current map. If you haven't already done so, save your roads\_34S layer to a shapefile by right-clicking the layer and selecting *Save as...*. Create a new map and load this layer into it.

Since so many different configurations are possible when analyzing networks, the plugin doesn't assume anything before you've set it up. This means that it won't do anything at all if you don't set it up first.

- Click on the menu item  $Vector \rightarrow Road\ graph \rightarrow settings$ . A dialog will appear.
- Make sure it's set up like this (use defaults unless otherwise specified):




• Time unit: hour

• Distance unit: kilometer

• Layer: roads\_34S

• Speed field: Always use default / km/h




• Direction: Two-way direction


• Speed: 60

## 7.3.3 Follow Along: Use the Tool


Find two points, on roads, on your map. They do not need to have any significance, but they should be connected by roads and separated by a reasonable distance:



• In the plugin panel, click on the *Capture Point* button next to the *Start* field:




- Click on your chosen start point.
- Use the Capture Point button next to the Stop field and capture your chosen end point.
- Click on the *Calculate* button to see the solution:




# 7.3.4 Follow Along: Using Criteria

Muista: Section developed by Linfiniti and S Motala (Cape Peninsula University of Technology)

- Add your restaurants\_34S layer to the map (extract it from your analyis map if necessary).
- Open the attribute table for the *roads\_34S* layer and enter edit mode.
- Add a new column with the name SPEED, and give it the type Whole number (integer) with a width of 3.
- In the main window, activate the Select Features by Rectangle tool:




• Select any main roads in urban - but not residential - areas:




(To select more than one road, hold the ctrl button and drag a box across any road that you want to include in the selection.)

• In the attribute table, select *Show selected features*.




• Set the SPEED value for all the selected streets to 60:




In context, this means that you're setting the speed limit on those roads to 60 km/h.


• Select any highways or major roads outside urban areas:



- Set the SPEED value for all the selected streets to 120.
- Close the attribute table, save your edits, and exit edit mode.
- Check the *Vector* → *Road graph* → *Road graph settings* to ensure that it's set up as explained previously in this lesson, but with the *Speed* value set to the SPEED field you just created.
- In the *Shortest path* panel, click the *Start point* button.
- Set the starting point on a minor road on one side of Swellendam and the end point on a major road on the other side of town:




- In the *Criterion* drop-down list in the *Shortest path* panel, select *Length*.
- Click *Calculate*. The route will be calculated for the shortest distance:



Notice the values of *Length* and *Time* in the *Shortest path* panel.

- Set the Criterion to Time.
- Click *Calculate* again. The route will be calculated for the shortest time:



You can switch back and forth between these criteria, recalculating each time, and note the changes in the *Length* and *Time* taken. Remember that the assumption being made to arrive at the time taken to travel a route does not

account for acceleration, and assumes that you will be traveling at the speed limit at all times. In a real situation, you may want to split roads into smaller sections and note the average or expected speed in each section, rather than the speed limit.

If, on clicking *Calculate*, you see an error stating that a path could not be found, make sure that the roads you digitized actually meet each other. If they're not quite touching, either fix them by modifying the features, or set the *Topology tolerance* in the plugin's settings. If they're passing over each other without intersecting, use the *Split features* tool to "split" roads at their intersections:



Remember that the *Split features* tool only works in edit mode on selected features, though!

You might also find that the shortest route is also the quickest if this error is returned.

#### 7.3.5 In Conclusion

Now you know how to use the *Road Graph* plugin to solve shortest-path problems.

#### 7.3.6 What's Next?

Next you'll see how to run spatial statistics algorithms on vector datasets.

### 7.4 Lesson: Spatial Statistics

Muista: Lesson developed by Linfiniti and S Motala (Cape Peninsula University of Technology)

Spatial statistics allow you to analyze and understand what is going on in a given vector dataset. QGIS includes several standard tools for statistical analysis which prove useful in this regard.

The goal for this lesson: To know how to use QGIS' spatial statistics tools.



### Follow Along: Create a Test Dataset

In order to get a point dataset to work with, we'll create a random set of points.


To do so, you'll need a polygon dataset defining the extents of the area you want to create the points in.

We'll use the area covered by streets.

- Create a new empty map.
- Add your roads\_34S layer, as well as the srtm\_41\_19.tif raster (elevation data) found in exercise\_data/raster/SRTM/.

**Muista:** You might find that your SRTM DEM layer has a different CRS to that of the roads layer. If so, you can reproject either the roads or DEM layer using techniques learnt earlier in this module.


• Use the *Convex hull(s)* tool (available under *Vector* → *Geoprocessing Tools*) to generate an area enclosing all the roads:




- Save the output under exercise\_data/spatial\_statistics/ as roads\_hull.shp.
- Check Add result to canvas option to add the output to the TOC (Layers list).

#### **Creating random points**

• Create random points in this area using the tool at  $Vector \rightarrow Research\ Tools \rightarrow Random\ points$ :




- $\bullet$  Save the output under <code>exercise\_data/spatial\_statistics/</code> as <code>random\_points.shp.</code>
- Check Add result to canvas option to add the output to the TOC (Layers list).



#### Sampling the data


- To create a sample dataset from the raster, you'll need to use the *Point sampling tool* plugin.
- Refer ahead to the module on plugins if necessary.
- ullet Search for the phrase point sampling in the Plugin o Manage and Install Plugins... and you will find the plugin.
- As soon as it has been activated with the *Plugin Manager*, you will find the tool under *Plugins*  $\rightarrow$  *Analyses*  $\rightarrow$  *Point sampling tool*:



- Select *random\_points* as the layer containing sampling points, and the SRTM raster as the band to get values from.
- Make sure that "Add created layer to the TOC" is checked.
- $\bullet$  Save the output under <code>exercise\_data/spatial\_statistics/</code> as <code>random\_samples.shp.</code>

Now you can check the sampled data from the raster file in the attributes table of the *random\_samples* layer, they will be in a column named srtm\_41\_19.tif.

A possible sample layer is shown here:




The sample points are classified by their value such that darker points are at a lower altitude.

You'll be using this sample layer for the rest of the statistical exercises.



Now get the basic statistics for this layer.

- Click on the  $Vector \rightarrow Analysis\ Tools \rightarrow Basic\ statistics$  menu entry.
- In the dialog that appears, specify the *random\_samples* layer as the source.
- Make sure that the *Target field* is set to srtm\_41\_19.tif which is the field you will calculate statistics for.
- Click *OK*. You'll get results like this:



Muista: You can copy and paste the results into a spreadsheet. The data uses a (colon:) separator.

|    | Α                      | В           |
|----|------------------------|-------------|
| 1  | Mean                   | 343.9       |
| 2  | StdDev                 | 254.4824748 |
| 3  | Sum                    | 34390       |
| 4  | Min                    | 34          |
| 5  | Max                    | 1226        |
| 6  | N                      | 100         |
| 7  | CV                     | 0.739989749 |
| 8  | Number of unique ∨alu• | 91          |
| 9  | Range                  | 1192        |
| 10 | Median                 | 269         |

• Close the plugin dialog when done.

To understand the statistics above, refer to this definition list:

**Mean** The mean (average) value is simply the sum of the values divided by the amount of values.

**StdDev** The standard deviation. Gives an indication of how closely the values are clustered around the mean. The smaller the standard deviation, the closer values tend to be to the mean.

Sum All the values added together.

Min The minimum value.

Max The maximum value.

**N** The amount of samples/values.

CV The spatial covariance of the dataset.

**Number of unique values** The number of values that are unique across this dataset. If there are 90 unique values in a dataset with N=100, then the 10 remaining values are the same as one or more of each other.

Range The difference between the minimum and maximum values.

**Median** If you arrange all the values from least to greatest, the middle value (or the average of the two middle values, if N is an even number) is the median of the values.




## Follow Along: Compute a Distance Matrix

- Create a new point layer in the same projection as the other datasets (WGS 84 / UTM 34S).
- Enter edit mode and digitize three point somewhere among the other points.
- Alternatively, use the same random point generation method as before, but specify only three points.
- Save your new layer as distance\_points.shp.

To generate a distance matrix using these points:

- Open the tool  $Vector \rightarrow Analysis\ Tools \rightarrow Distance\ matrix$ .
- Select the distance\_points layer as the input layer, and the random\_samples layer as the target layer.
- Set it up like this:



- $\bullet$   $\ensuremath{Save}$  the result as distance\_matrix.csv.
- Click *OK* to generate the distance matrix.
- Open it in a spreadsheet program to see the results. Here is an example:


| InputID | MEAN           | STDDEV | MIN            | MAX            |
|---------|----------------|--------|----------------|----------------|
| 3       | 0.195448627921 | 0      | 0.195448627921 | 0.195448627921 |
| 2       | 0.174928758638 | 0      | 0.174928758638 | 0.174928758638 |
| 1       | 0.174928758638 | 0      | 0.174928758638 | 0.174928758638 |
|         |                |        |                |                |
|         |                |        |                |                |
|         |                |        |                |                |
|         |                |        |                |                |
|         |                |        |                |                |
|         |                |        |                |                |



## Follow Along: Nearest Neighbor Analysis

To do a nearest neighbor analysis:

- Click on the menu item  $Vector \rightarrow Analysis\ Tools \rightarrow Nearest\ neighbor\ analysis.$
- In the dialog that appears, select the *random\_samples* layer and click *OK*.
- The results will appear in the dialog's text window, for example:



Muista: You can copy and paste the results into a spreadsheet. The data uses a (colon:) separator.

# 7.4.5 Follow Along: Mean Coordinates


To get the mean coordinates of a dataset:

- Click on the  $Vector \rightarrow Analysis\ Tools \rightarrow Mean\ coordinate(s)$  menu item.
- In the dialog that appears, specify *random\_samples* as the input layer, but leave the optional choices unchanged.
- Specify the output layer as mean\_coords.shp.
- Click OK.
- Add the layer to the *Layers list* when prompted.

Let's compare this to the central coordinate of the polygon that was used to create the random sample.

- Click on the  $Vector \rightarrow Geometry\ Tools \rightarrow Polygon\ centroids$  menu item.
- In the dialog that appears, select *roads\_hull* as the input layer.
- Save the result as center\_point.
- Add it to the *Layers list* when prompted.

As you can see from the example below, the mean coordinates and the center of the study area (in orange) don't necessarily coincide:



# 7.4.6 Follow


### Follow Along: Image Histograms

The histogram of a dataset shows the distribution of its values. The simplest way to demonstrate this in QGIS is via the image histogram, available in the *Layer Properties* dialog of any image layer.

- In your Layers list, right-click on the SRTM DEM layer.
- Select Properties.
- Choose the tab *Histogram*. You may need to click on the *Compute Histogram* button to generate the graphic. You will see a graph describing the frequency of values in the image.

Cancel

OK



• You can export it as an image:

• Select the *Metadata* tab, you can see more detailed information inside the *Properties* box.

The mean value is 332.8, and the maximum value is 1699! But those values don't show up on the histogram. Why not? It's because there are so few of them, compared to the abundance of pixels with values below the mean. That's also why the histogram extends so far to the right, even though there is no visible red line marking the frequency of values higher than about 250.

Therefore, keep in mind that a histogram shows you the distribution of values, and not all values are necessarily visible on the graph.

• (You may now close Layer Properties.)

Help

Apply

## 7.4.7 Follow Ale

## Follow Along: Spatial Interpolation


Let's say you have a collection of sample points from which you would like to extrapolate data. For example, you might have access to the *random\_samples* dataset we created earlier, and would like to have some idea of what the terrain looks like.

To start, launch the Grid (Interpolation) tool by clicking on the  $Raster \rightarrow Analysis \rightarrow Grid$  (Interpolation) menu item.

• In the *Input file* field, select random\_samples.

- Check the *Z Field* box, and select the field srtm\_41\_19.
- Set the Output file location to exercise\_data/spatial\_statistics/interpolation.tif.
- Check the *Algorithm* box and select *Inverse distance to a power*.
- Set the *Power* to 5.0 and the *Smoothing* to 2.0. Leave the other values as-is.
- Check the Load into canvas when finished box and click OK.
- When it's done, click *OK* on the dialog that says Process completed, click *OK* on the dialog showing feedback information (if it has appeared), and click *Close* on the *Grid* (*Interpolation*) dialog.

Here's a comparison of the original dataset (left) to the one constructed from our sample points (right). Yours may look different due to the random nature of the location of the sample points.







As you can see, 100 sample points aren't really enough to get a detailed impression of the terrain. It gives a very general idea, but it can be misleading as well. For example, in the image above, it is not clear that there is a high, unbroken mountain running from east to west; rather, the image seems to show a valley, with high peaks to the west. Just using visual inspection, we can see that the sample dataset is not representative of the terrain.

## 7.4.8 Try Yourself

- Use the processes shown above to create a new set of 1000 random points.
- Use these points to sample the original DEM.
- Use the *Grid* (*Interpolation*) tool on this new dataset as above.
- Set the output filename to interpolation\_1000.tif, with *Power* and *Smoothing* set to 5.0 and 2.0, respectively.


The results (depending on the positioning of your random points) will look more or less like this:





The border shows the *roads\_hull* layer (which represents the boundary of the random sample points) to explain the sudden lack of detail beyond its edges. This is a much better representation of the terrain, due to the much greater density of sample points.

Here is an example of what it looks like with 10 000 sample points:




**Muista:** It's not recommended that you try doing this with 10 000 sample points if you are not working on a fast computer, as the size of the sample dataset requires a lot of processing time.



### Follow Along: Additional Spatial Analysis Tools

Originally a separate project and then accessible as a plugin, the SEXTANTE software has been added to QGIS as a core function from version 2.0. You can find it as a new QGIS menu with its new name *Processing* from where you can access a rich toolbox of spatial analysis tools allows you to access various plugin tools from within a single interface.

• Activate this set of tools by enabling the *Processing* → *Toolbox* menu entry. The toolbox looks like this:



You will probably see it docked in QGIS to the right of the map. Note that the tools listed here are links to the actual tools. Some of them are SEXTANTE's own algorithms and others are links to tools that are accessed from external applications such as GRASS, SAGA or the Orfeo Toolbox. This external applications are installed with QGIS so you are already able to make use of them. In case you need to change the configuration of the Processing tools or, for example, you need to update to a new version of one of the external applications, you can access its setting from  $Processing \rightarrow Options \ and \ configurations$ .



### Follow Along: Spatial Point Pattern Analysis

For a simple indication of the spatial distribution of points in the *random\_samples* dataset, we can make use of SAGA's *Spatial Point Pattern Analysis* tool via the *Processing Toolbox* you just opened.

- In the *Processing Toolbox*, search for this tool *Spatial Point Pattern Analysis*.
- Double-click on it to open its dialog.

#### Installing SAGA

**Muista:** If SAGA is not installed on your system, the plugin's dialog will inform you that the dependency is missing. If this is not the case, you can skip these steps.

#### **On Windows**

Included in your course materials you will find the SAGA installer for Windows.

• Start the program and follow its instructions to install SAGA on your Windows system. Take note of the path you are installing it under!

Once you have installed SAGA, you'll need to configure SEXTANTE to find the path it was installed under.

- Click on the menu entry Analysis  $\rightarrow$  SAGA options and configuration.
- In the dialog that appears, expand the SAGA item and look for SAGA folder. Its value will be blank.
- In this space, insert the path where you installed SAGA.

#### On Ubuntu

- Search for SAGA GIS in the Software Center, or enter the phrase sudo apt-get install saga-gis in your terminal. (You may first need to add a SAGA repository to your sources.)
- QGIS will find SAGA automatically, although you may need to restart QGIS if it doesn't work straight away.

#### On Mac

Homebrew users can install SAGA with this command:

• brew install saga-core

If you do not use Homebrew, please follow the instructions here:


http://sourceforge.net/apps/trac/saga-gis/wiki/Compiling%20SAGA%20on%20Mac%20OS%20X

#### After installing


Now that you have installed and configured SAGA, its functions will become accessible to you.

#### **Using SAGA**

- Open the SAGA dialog.
- SAGA produces three outputs, and so will require three output paths.
- Save these three outputs under exercise\_data/spatial\_statistics/, using whatever file names you find appropriate.



The output will look like this (the symbology was changed for this example):



The red dot is the mean center; the large circle is the standard distance, which gives an indication of how closely the points are distributed around the mean center; and the rectangle is the bounding box, describing the smallest possible rectangle which will still enclose all the points.

# 7.4.11 Follow Along: Minimum Distance Analysis

Often, the output of an algorithm will not be a shapefile, but rather a table summarizing the statistical properties of a dataset. One of these is the *Minimum Distance Analysis* tool.

• Find this tool in the *Processing Toolbox* as *Minimum Distance Analysis*.

It does not require any other input besides specifying the vector point dataset to be analyzed.

- Choose the *random\_points* dataset.
- Click OK. On completion, a DBF table will appear in the Layers list.
- Select it, then open its attribute table. Although the figures may vary, your results will be in this format:

|   | NAME \(\neg\)      | VALUE         |
|---|--------------------|---------------|
| 0 | Mean Average       | 2823.45817848 |
| 1 | Minimum            | 424.0860061   |
| 2 | Maximum            | 9773.35250512 |
| 3 | Standard Deviation | 1662.40681133 |
| 4 | Duplicates         | 0             |

#### 7.4.12 In Conclusion

QGIS allows many possibilities for analyzing the spatial statistical properties of datasets.

#### 7.4.13 What's Next?

Now that we've covered vector analysis, why not see what can be done with rasters? That's what we'll do in the next module!

**Module: Rasters** 

We've used rasters for digitizing before, but raster data can also be used directly. In this module, you'll see how it's done in QGIS.

### 8.1 Lesson: Working with Raster Data

Raster data is quite different from vector data. Vector data has discrete features constructed out of vertices, and perhaps connected with lines and/or areas. Raster data, however, is like any image. Although it may portray various properties of objects in the real world, these objects don't exist as separate objects; rather, they are represented using pixels of various different color values.

During this module you're going to use raster data to supplement your existing GIS analysis.

The goal for this lesson: To learn how to work with raster data in the QGIS environment.



### Follow Along: Loading Raster Data

- Open your analysis.qgs map (which you should have created and saved during the previous module).
- Deactivate all the layers except the *solution* and *important\_roads* layers.
- Click on the *Load Raster Layer* button:



The Load Raster Layer dialog will open. The data for this project is in exercise\_data/raster.

• Either load them all in separately, or hold down ctrl and click on all four of them in turn, then open them at the same time.

The first thing you'll notice is that nothing seems to be happening in your map. Are the rasters not loading? Well, there they are in the *Layers list*, so obviously they did load. The problem is that they're not in the same projection. Luckily, we've already seen what to do in this situation.

- Select  $Project \rightarrow Project \ Properties$  in the menu:
- Select *CRS* tab in the menu:
- Enable "on the fly" reprojection.
- Set it to the same projection as the rest of your data (WGS 84 / UTM zone 33S).
- Click [OK].

The rasters should fit nicely:



There we have it - four aerial photographs covering our whole study area.

## 8.1.2 Follow Along: Create a Virtual Raster

Now as you can see from this, your solution layer lies across all four photographs. What this means is that you're going to have to work with four rasters all the time. That's not ideal; it would be better to have one file for one (composite) image, right?

Luckily, QGIS allows you to do exactly this, and without needing to actually create a new raster file, which could take up a lot of space. Instead, you can create a *Virtual Raster*. This is also often called a *Catalog*, which explains its function. It's not really a new raster. Rather, it's a way to organize your existing rasters into one catalog: one file for easy access.


To make a catalog:

- Click on the menu item  $Raster \rightarrow Miscellaneous \rightarrow Build Virtual Raster (Catalog)$ .
- In the dialog that appears, check the box next to *Use visible raster layers for input*.
- $\bullet$   $Enter\ \mbox{exercise\_data/residential\_development}$  as the output location.
- Enter aerial\_photos.vrt as the file name.
- Check the *Load into canvas when finished* button.

Notice the text field below. What this dialog is actually doing is that it's writing that text for you. It's a long command that QGIS is going to run.

Muista: Keep in mind that the command text is editable, so you can customize the command further if preferred. Search online for the initial command (in this case, gdalbuildvrt) for help on the syntax.

• Click *OK* to run the command.



It may take a while to complete. When it's done, it will tell you so with a message box.

- Click *OK* to chase the message away.
- Click *Close* on the *Build Virtual Raster (Catalog)* dialog. (Don't click *OK* again, otherwise it's going to start running that command again.)

- You can now remove the original four rasters from the Layers list.
- If necessary, click and drag the new *aerial\_photos* raster catalog layer to the bottom of the *Layers list* so that the other activated layers become visible.




## Transforming Raster Data

The above methods allow you to virtually merge datasets using a catalog, and to reproject them "on the fly". However, if you are setting up data that you'll be using for quite a while, it may be more efficient to create new rasters that are already merged and reprojected. This improves performance while using the rasters in a map, but it may take some time to set up initially.

#### Reprojecting rasters

• Click on the menu item  $Raster \rightarrow Projections \rightarrow Warp (Reproject)$ .

Note that this tool features a handy batch option for reprojecting the contents of whole directories. You can also reproject virtual rasters (catalogs), as well as enabling a multithreaded processing mode.




#### **Merging rasters**

• Click on the menu item  $Raster \rightarrow Miscellaneous \rightarrow Merge$ .

You can choose to process entire directories instead of single files, giving you a very useful built-in batch processing capability. You can specify a virtual raster as input file, too, and all of the rasters that it consists of will be processed.

You can also add your own command line options using the *Creation Options* checkbox and list. This only applies if you have knowledge of the GDAL library's operation.



#### 8.1.4 In Conclusion

QGIS makes it easy to include raster data into your existing projects.

#### 8.1.5 What's Next?

Next, we'll use raster data that isn't aerial imagery, and see how symbolization is useful in the case of rasters as well.

### 8.2 Lesson: Changing Raster Symbology

Not all raster data consists of aerial photographs. There are many other forms of raster data, and in many of those cases, it's essential to symbolize the data properly so that it becomes properly visible and useful.


**The goal for this lesson:** To change the symbology for a raster layer.

## 8.2.1 Try Yourself

- Start with the current map which you should have created during the previous exercise: analysis.qgs.
- Use the *Add Raster Layer* button to load the new raster dataset.
- Load the dataset srtm\_41\_19.tif, found under the directory exercise\_data/raster/SRTM/.
- Once it appears in the *Layers list*, rename it to DEM.
- Zoom to the extent of this layer by right-clicking on it in the Layer List and selecting Zoom to Layer Extent.

This dataset is a *Digital Elevation Model (DEM)*. It's a map of the elevation (altitude) of the terrain, allowing us to see where the mountains and valleys are, for example.


Once it's loaded, you'll notice that it's a basic stretched grayscale representation of the DEM. It's seen here with the vector layers on top:



QGIS has automatically applied a stretch to the image for visualization purposes, and we will learn more about how this works as we continue.


# 8.2.2 Follow Along: Changing Raster Layer Symbology

- Open the *Layer Properties* dialog for the *SRTM* layer by right-clicking on the layer in the Layer tree and selecting *Properties* option.
- Switch to the *Style* tab.




These are the current settings that QGIS applied for us by default. Its just one way to look at a DEM, so lets explore some others.

- Change the *Render type* to *Singleband pseudocolor*, and use the default options presented.
- Click the *Classify* button to generate a new color classification, and click *OK* to apply this classification to the DEM.




You'll see the raster looking like this:



This is an interesting way of looking at the DEM, but maybe we don't want to symbolize it using these colors.

- Open Layer Properties dialog again.
- Switch the Render Type back to Singleband gray.
- Click *OK* to apply this setting to the raster.


You will now see a totally gray rectangle that isn't very useful at all.



This is because we have lost the default settings which "stretch" the color values to show them contrast.

Let's tell QGIS to again "stretch" the color values based on the range of data in the DEM. This will make QGIS use all of the available colors (in *Grayscale*, this is black, white and all shades of gray in between).


- Specify the *Min* and *Max* values as shown below.
- Set the value Contrast enhancement to Stretch To MinMax:



But what are the minimum and maximum values that should be used for the stretch? The ones that are currently under *Min* and *Max* values are the same values that just gave us a gray rectangle before. Instead, we should be using the minimum and maximum values that are actually in the image, right? Fortunately, you can determine those values easily by loading the minimum and maximum values of the raster.


- Under Load min / max values, select Min / Max option.
- Click the *Load* button:

Notice how the *Custom min / max values* have changed to reflect the actual values in our DEM:



• Click *OK* to apply these settings to the image.

You'll now see that the values of the raster are again properly displayed, with the darker colors representing valleys and the lighter ones, mountains:



#### But isn't there a better or easier way?

Yes, there is. Now that you understand what needs to be done, you'll be glad to know that there's a tool for doing all of this easily.

- Remove the current DEM from the *Layers list*.
- Load the raster in again, renaming it to DEM as before. It's a gray rectangle again...
- Enable the tool you'll need by enabling  $View \rightarrow Toolbars \rightarrow Raster$ . These icons will appear in the interface:



The third button from the left *Local Histogram Stretch* will automatically stretch the minimum and maximum values to give you the best contrast in the local area that you're zoomed into. It's useful for large datasets. The button on the left *Local Cumulative Cut Stretch* ... will stretch the minimum and maximum values to constant values across the whole image.

• Click the fourth button from the left (*Stretch Histogram to Full Dataset*). You'll see the data is now correctly represented as before.

You can try the other buttons in this toolbar and see how they alter the stretch of the image when zoomed in to local areas or when fully zoomed out.

#### 8.2.3 In Conclusion

These are only the basic functions to get you started with raster symbology. QGIS also allows you many other options, such as symbolizing a layer using standard deviations, or representing different bands with different colors in a multispectral image.

#### 8.2.4 Reference

The SRTM dataset was obtained from http://srtm.csi.cgiar.org/

#### 8.2.5 What's Next?

Now that we can see our data displayed properly, let's investigate how we can analyze it further.

### 8.3 Lesson: Terrain Analysis

Certain types of rasters allow you to gain more insight into the terrain that they represent. Digital Elevation Models (DEMs) are particularly useful in this regard. In this lesson you will use terrain analysis tools to find out more about the study area for the proposed residential development from earlier.

The goal for this lesson: To use terrain analysis tools to derive more information about the terrain.




## Follow Along: Calculating a Hillshade

The DEM you have on your map right now does show you the elevation of the terrain, but it can sometimes seem a little abstract. It contains all the 3D information about the terrain that you need, but it doesn't look like a 3D object. To get a better look at the terrain, it is possible to calculate a *hillshade*, which is a raster that maps the terrain using light and shadow to create a 3D-looking image.

To work with DEMs, you should use QGIS' all-in-one DEM (Terrain models) analysis tool.

- Click on the menu item  $Raster \rightarrow Analysis \rightarrow DEM$  (Terrain models).
- In the dialog that appears, ensure that the *Input file* is the *DEM* layer.
- Set the Output file to hillshade.tif in the directory exercise\_data/residential\_development.
- Also make sure that the *Mode* option has *Hillshade* selected.
- Check the box next to Load into canvas when finished.
- You may leave all the other options unchanged.
- Click *OK* to generate the hillshade.
- When it tells you that processing is completed, click OK on the message to get rid of it.
- Click Close on the main DEM (Terrain models) dialog.

You will now have a new layer called *hillshade* that looks like this:




That looks nice and 3D, but can we improve on this? On its own, the hillshade looks like a plaster cast. Can't we use it together with our other, more colorful rasters somehow? Of course we can, by using the hillshade as an overlay.

## Follow Along: Using a Hillshade as an Overlay

A hillshade can provide very useful information about the sunlight at a given time of day. But it can also be used for aesthetic purposes, to make the map look better. The key to this is setting the hillshade to being mostly transparent.

- Change the symbology of the original *DEM* to use the *Pseudocolor* scheme as in the previous exercise.
- Hide all the layers except the *DEM* and *hillshade* layers.
- Click and drag the *DEM* to be beneath the *hillshade* layer in the *Layers list*.
- Set the hillshade layer to be transparent by opening its Layer Properties and go to the Transparency tab.
- Set the *Global transparency* to 50%:
- Click *OK* on the *Layer Properties* dialog. You'll get a result like this:



• Switch the hillshade layer off and back on in the Layers list to see the difference it makes.

Using a hillshade in this way, it's possible to enhance the topography of the landscape. If the effect doesn't seem strong enough to you, you can change the transparency of the *hillshade* layer; but of course, the brighter the hillshade becomes, the dimmer the colors behind it will be. You will need to find a balance that works for you.

Remember to save your map when you are done.

**Muista:** For the next two exercises, please use a new map. Load only the DEM raster dataset into it (exercise\_data/raster/SRTM/srtm\_41\_19.tif). This is to simplify matters while you're working with the raster analysis tools. Save the map as exercise\_data/raster\_analysis.qgs.


## 8.3.3

## Follow Along: Calculating the Slope


Another useful thing to know about the terrain is how steep it is. If, for example, you want to build houses on the land there, then you need land that is relatively flat.

To do this, you need to use the Slope mode of the DEM (Terrain models) tool.

- Open the tool as before.
- Select the *Mode* option *Slope*:



- Set the save location to exercise\_data/residential\_development/slope.tif
- Enable the Load into canvas... checkbox.
- Click *OK* and close the dialogs when processing is complete, and click *Close* to close the dialog. You'll see a new raster loaded into your map.
- With the new raster selected in the *Layers list*, click the *Stretch Histogram to Full Dataset* button. Now you'll see the slope of the terrain, with black pixels being flat terrain and white pixels, steep terrain:



## 8.3.4

## Try Yourself calculating the aspect

The *aspect* of terrain refers to the direction it's facing in. Since this study is taking place in the Southern Hemisphere, properties should ideally be built on a north-facing slope so that they can remain in the sunlight.

• Use the Aspect mode of the DEM (Terain models) tool to calculate the aspect of the terrain.

Check your results



## Follow Along: Using the Raster Calculator

Think back to the estate agent problem, which we last addressed in the *Vector Analysis* lesson. Let's imagine that the buyers now wish to purchase a building and build a smaller cottage on the property. In the Southern Hemisphere, we know that an ideal plot for development needs to have areas on it that are north-facing, and with a slope of less than five degrees. But if the slope is less than 2 degrees, then the aspect doesn't matter.

Fortunately, you already have rasters showing you the slope as well as the aspect, but you have no way of knowing where both conditions are satisfied at once. How could this analysis be done?

The answer lies with the Raster calculator.


- Click on *Raster > Raster calculator...* to start this tool.
- To make use of the *aspect* dataset, double-click on the item *aspect@1* in the *Raster bands* list on the left. It will appear in the *Raster calculator expression* text field below.

North is at 0 (zero) degrees, so for the terrain to face north, its aspect needs to be greater than 270 degrees and less than 90 degrees.


• In the Raster calculator expression field, enter this expression:

```
aspect@1 <= 90 OR aspect@1 >= 270
```

- $\bullet \ \ \textbf{Set the output file to} \ \ \textbf{aspect\_north.tif in the directory} \ \ \textbf{exercise\_data/residential\_development/}.$
- Ensure that the box *Add result to project* is checked.
- Click *OK* to begin processing.



Your result will be this:





Now that you've done the aspect, create two separate new analyses of the DEM layer.

- The first will be to identify all areas where the slope is less than or equal to 2 degrees.
- The second is similar, but the slope should be less than or equal to 5 degrees.
- Save them under exercise\_data/residential\_development/ as slope\_lte2.tif and slope\_lte5.tif.

Check your results



## Follow Along: Combining Raster Analysis Results

Now you have three new analysis rasters of the DEM layer:

- aspect\_north: the terrain faces north
- slope\_lte2: the slope is at or below 2 degrees
- slope\_lte5: the slope is at or below 5 degrees

Where the conditions of these layers are met, they are equal to 1. Elsewhere, they are equal to 0. Therefore, if you multiply one of these rasters by another one, you will get the areas where both of them are equal to 1.

The conditions to be met are: at or below 5 degrees of slope, the terrain must face north; but at or below 2 degrees of slope, the direction that the terrain faces in does not matter.

Therefore, you need to find areas where the slope is at or below 5 degrees AND the terrain is facing north; OR the slope is at or below 2 degrees. Such terrain would be suitable for development.

To calculate the areas that satisfy these criteria:

- Open your Raster calculator again.
- Use the *Raster bands* list, the *Operators* buttons, and your keyboard to build this expression in the *Raster calculator expression* text area:

```
( aspect_north@1 = 1 AND slope_lte5@1 = 1 ) OR slope_lte2@1 = 1
```

- Save the output under exercise\_data/residential\_development/ as all\_conditions.tif.
- Click *OK* on the *Raster calculator*. Your results:






### Follow Along: Simplifying the Raster

As you can see from the image above, the combined analysis has left us with many, very small areas where the conditions are met. But these aren't really useful for our analysis, since they're too small to build anything on. Let's get rid of all these tiny unusable areas.

- Open the *Sieve* tool (*Raster*  $\rightarrow$  *Analysis*  $\rightarrow$  *Sieve*).
- Set the *Input file* to all\_conditions, and the *Output file* to all\_conditions\_sieve.tif (under exercise\_data/residential\_development/).
- Set both the *Threshold* and *Pixel connections* values to 8, then run the tool.




Once processing is done, the new layer will load into the canvas. But when you try to use the histogram stretch tool to view the data, this happens:



What's going on? The answer lies in the new raster file's metadata.

• View the metadata under the *Metadata* tab of the *Layer Properties* dialog. Look in the *Properties* section at the bottom.



Whereas this raster, like the one it's derived from, should only feature the values 1 and 0, it has the STATISTICS\_MINIMUM value of a very large negative number. Investigation of the data shows that this number acts as a null value. Since we're only after areas that weren't filtered out, let's set these null values to zero.


• Open the Raster Calculator again, and build this expression:

```
(all\_conditions\_sieve@1 <= 0) = 0
```

This will maintain all existing zero values, while also setting the negative numbers to zero; which will leave all the areas with value 1 intact.

• Save the output under exercise\_data/residential\_development/ as all\_conditions\_simple.tif.

Your output looks like this:



This is what was expected: a simplified version of the earlier results. Remember that if the results you get from a tool aren't what you expected, viewing the metadata (and vector attributes, if applicable) can prove essential to solving the problem.

#### 8.3.9 In Conclusion

You've seen how to derive all kinds of analysis products from a DEM. These include hillshade, slope and aspect calculations. You've also seen how to use the raster calculator to further analyze and combine these results.

#### 8.3.10 What's Next?

Now you have two analyses: the vector analysis which shows you the potentially suitable plots, and the raster analysis that shows you the potentially suitable terrain. How can these be combined to arrive at a final result for this problem? That's the topic for the next lesson, starting in the next module.

### **Module: Completing the Analysis**

You now have two halves of an analysis: a vector and a raster part. In this module, you'll see how to combine them. You will conclude the analysis and present the final results.

#### 9.1 Lesson: Raster to Vector Conversion

Converting between raster and vector formats allows you to make use of both raster and vector data when solving a GIS problem, as well as using the various analysis methods unique to these two forms of geographic data. This increases the flexibility you have when considering data sources and processing methods for solving a GIS problem.


To combine a raster and vector analysis, you need to convert the one type of data to the other. Let's convert the raster result of the previous lesson to a vector.

The goal for this lesson: To get the raster result into a vector that can be used to complete the analysis.

## 9.1.1 Follow Along: The *Raster to Vector* Tool

Start with the map from the last module, raster\_analysis.qgs. There you should have the all\_conditions\_simple.tif calculated during the previous exercises.

- Click on  $Raster \rightarrow Conversion \rightarrow Polygonize$  (Raster to Vector). The tool dialog will appear.
- Set it up like this:



- Change the field name (describing the values of the raster) to suitable.
- Save the shapefile under exercise\_data/residential\_development as all\_terrain.shp.

Now you have a vector file which contains all the values of the raster, but the only areas you're interested in are those that are suitable; i.e., those polygons where the value of suitable is 1. You can change the style of this layer if you want to have a clearer visualization of it.

# 9.1.2 Try Yourself

Refer back to the module on vector analysis.

- Create a new vector file that contains only the polygons where suitable has the value of 1.
- Save the new file as exercise\_data/residential\_development/ as suitable\_terrain.shp.


Check your results



## Follow Along: The Vector to Raster Tool

Although unnecessary for our current problem, it's useful to know about the opposite conversion from the one performed above. Convert to raster the suitable\_terrain.shp vector file you just created in previous step.

• Click on *Raster* → *Conversion* → *Rasterize* (*Vector to Raster*) to start this tool, then set it up as in the screenshot below:



- *Input file* is *all\_terrain*;
- Output file... is exercise\_data/residential\_development/raster\_conversion.tif;
- Width and Height are 837 and 661, respectively.

**Muista:** The size of the output image is specified here to be the same as the original raster which was vectorized. To view the dimensions of an image, open its metadata (*Metadata* tab in the *Layer Properties*).

- Click *OK* on the dialog to begin the conversion process.
- When it is complete, gauge its success by comparing the new raster with the original one. They should match up exactly, pixel for pixel.

#### 9.1.4 In Conclusion

Converting between raster and vector formats allows you to widen the applicability of data, and need not lead to data degradation.

#### 9.1.5 What's Next?

Now that we have the results of the terrain analysis available in vector format, they can be used to solve the problem of which buildings we should consider for the residential development.

### 9.2 Lesson: Combining the Analyses


Using the vectorized results of the raster analysis will allow you to select only those buildings on suitable terrain.

**The goal for this lesson:** To use the vectorized terrain results to select suitable plots.

## 9.2.1 Try Yourself

- Save your current map (raster\_analysis.qgs).
- Open the map in which you created during the vector analysis earlier (you should have saved the file as analysis.ggs).
- In the *Layers list*, enable these layers:
  - hillshade,
  - solution (or buildings\_over\_100)
- In addition to these layers, which should already be loaded in the map from when you worked on it before, also add the suitable\_terrain.shp dataset.
- If you are missing some layers, you should find them in exercise\_data/residential\_development/
- Use the *Intersect* tool (*Vector* → *Geoprocessing Tools*) to create a new vector layer called new\_solution.shp which contains only those buildings which intersect the suitable\_terrain layer.

You should now have a layer showing certain buildings as your solution, for example:



**Muista:** If you find that the *Intersect* tool does not produce any results, check the CRS settings of each of your layers. The CRS must be the same for both the layers you are comparing. You may need to reproject one layer by saving the layer as a new shapefile with the required CRS. In our example, the suitable\_terrain layer was reprojected to WGS 84 / UTM 34S and named suitable\_terrain\_34S.



## Try Yourself Inspecting the Results

Look at each of the buildings in your *new\_solution* layer. Compare them with the *suitable\_terrain* layer by changing the symbology for the *new\_solution* layer so that it has outlines only. What do you notice about some of the buildings? Are they all suitable just because they intersect with the *suitable\_terrain* layer? Why or why not? Which ones would you deem to be unsuitable?

Check your results



## Try Yourself Refining the Analysis

You can see from the results that some buildings which were included were not really suitable, so we can now refine the analysis.

We want to ensure that our analysis returns only those buildings which fall entirely within the suitable\_terrain layer. How would you achieve this? Use one or more Vector Analysis tools and remember that our buildings are all over 100m squared in size.

Check your results

#### 9.2.4 In Conclusion

You have now answered the original research question, and can offer an opinion (with reasons, backed by analysis) for a recommendation regarding which property to develop.

#### 9.2.5 What's Next?

Next you will present these results as part of your second assignment.

### 9.3 Assignment

Using the Map Composer, make a new map representing the results of your analysis. Include these layers:

- places (with labels),
- hillshade,
- *solution* (or *new\_solution*),
- roads and
- either *aerial\_photos* or *DEM*.

Write a short explanatory text to accompany it. Include in this text the criteria that were used in considering a house for purchase and subsequent development, as well as explaining your recommendations for which buildings are suitable.

## 9.4 Lesson: Supplementary Exercise

In this lesson, you will be guided through a complete GIS analysis in QGIS.

Muista: Lesson developed by Linfiniti and S Motala (Cape Peninsula University of Technology)

9.3. Assignment 233

#### 9.4.1 Problem Statement

You are tasked with finding areas in and around the Cape Peninsula that are a suitable habitat for a rare fynbos plant species. The extent of your area of investigation in the Cape Peninsula is: south of Melkbosstrand, west of Strand. Botanists have provided you with the following preferences exhibited by the species in question:

- It grows on east facing slopes.
- It grows on slopes with a gradient between 15% and 60%.
- It grows in areas that have a total annual rainfall of > 1200 mm.
- It will only be found at least 250 m away from any human settlement.
- The area of vegetation in which it occurs should be at least 6000m2 in area.

As a volunteer for Cape Nature, you have agreed to search for the plant on the closest suitable piece of land to your house. Use your GIS skills to determine where you should go to look.

#### 9.4.2 Solution Outline

order solve to this problem, you will have to download data from https://www.dropbox.com/s/q5evvkizuunrcs0/more analysis.zip?dl=0 under and place it exercise\_data/more\_analysis folder. You will use it to find the candidate area that is closest to your house. If you don't live in Cape Town (where this problem is based) you can choose any house in the Cape Town region. The solution will involve:

- analysing the DEM to find the east facing slopes and the slopes with the correct gradients;
- analysing the rainfall raster to find the areas with the correct amount of rainfall;
- analysing the Zoning vector layer to find areas that are away from human settlement and are of the correct size.

#### 9.4.3 Setting up the Map

- Click on the "CRS status" button in the extreme lower right corner of the screen. Under the CRS tab of the screen that appears, you will see the box Coordinate reference systems of the world.
- In this box, navigate to Projected Coordinate Systems  $\rightarrow$  Universal Transverse Mercator (UTM).
- Select the entry WGS 84 / UTM zone 33S (with the EPSG code 32733).
- Click *OK*. The map is now in the UTM33S coordinate reference system.
- Save the map by clicking on the Save Project As toolbar button, or use the File → Save Project As... menu item.
- Save the map in a directory called Rasterprac that you should create somewhere on your computer. You will save whatever layers you create in this directory as well.

#### 9.4.4 Loading Data into the Map

In order to process the data, you will need to load the necessary layers (street names, zones, rainfall, DEM) into the map canvas.

#### For vectors ...

- Click on the Add Vector Layer button, or use the Layer  $\rightarrow$  Add Vector Layer... menu item.
- In the dialog that appears, ensure that the File radio button is selected.
- Click on the Browse button.

- In the dialog that appears, open the exercise\_data/more\_analysis/streets directory.
- Select the file Street\_Names\_UTM33S.shp.
- · Click Open.

The dialog closes and shows the original dialog, with the file path specified in the text field next to the *Browse* button. This allows you to ensure that the correct file is selected. It is also possible to enter the file path in this field manually, should you wish to do so.

- Click *Open*. The vector layer will load in your map. Its color is automatically assigned. It will be changed later.
- Rename the layer to Streets.
- Right-click on it in the *Layers list* (by default, the pane along the left-hand side of the screen).
- Click *Rename* in the dialog that appears and rename it, pressing the *Enter* key when done.
- Repeat the vector adding process, but this time select the *Generalised\_Zoning\_Dissolve\_UTM33S.shp* file in the *Zoning* directory.
- Rename it to Zoning.

#### For rasters ...

- Click on the Add Raster Layer button, or use the Layer  $\rightarrow$  Add Raster Layer... menu item.
- Navigate to the appropriate file, select it, and click *Open*.
- Do this for each of the two raster files. The files you want are *DEM/reproject/DEM* and *Rain-fall/reprojected/rainfall.tif*.
- Rename the rainfall raster to Rainfall (with an initial capital). Initially when you load them, the images will be gray rectangles. Don't worry, this will be changed later.
- Save the map.

In order to properly see what's going on, the symbology for the layers needs to be changed.

#### 9.4.5 Changing the symbology of vector layers

- In the *Layers list*, right-click on the *Streets* layer.
- Select *Properties* from the menu that appears.
- Switch to the *Style* tab in the dialog that appears.
- Click on the button labelled *Change*, with a square showing the current color of the *Streets* layer.
- Select a new color in the dialog that appears.
- Click OK.
- Click OK again in the Layer Properties dialog. This will change the color of the Streets layer.
- Follow a similar process for the Zoning layer and choose an appropriate color for it.

#### 9.4.6 Changing the symbology of raster layers

Raster layer symbology is somewhat different.

- Open the *Properties* dialog for the *Rainfall* raster.
- Switch to the *Style* tab. You'll notice that this style dialog is very different from the version used for vector layers.
- Ensure that the button *Use standard deviation* is selected.

- Change the value in the associated box to 2.00 (it should be set to 0.00 by default).
- Under the heading *Contrast enhancement*, change the value of the *Current* dropdown list to *Stretch to MinMax*.
- Click *OK*. The "Rainfall" raster, if visible, should change colors, allowing you to see different brightness values for each pixel.
- Repeat this process for the DEM, but set the standard deviations used for stretching to 4.00.

#### 9.4.7 Changing the layer order

- In the Layers list, click and drag layers up and down to change the order they appear in on the map.
- Newer versions of QGIS may have a *Control rendering order* checkbox beneath the *Layers list*. Ensure that it is checked.

Now that all the data is loaded and properly visible, the analysis can begin. It is best if the clipping operation is done first. This is so that no processing power is wasted on computing values in areas that aren't going to be used anyway.

#### 9.4.8 Find the Correct Districts

- Load the vector layer admin\_boundaries/Western\_Cape\_UTM33S.shp into your map.
- Rename it to Districts.
- Right-click on the *Districts* layer in the *Layers list*.
- In the menu that appears, select the Query... menu item. The Query Builder dialog appears.

You will now build a query to select only the following list of districts:

- Bellville,
- Cape,
- Goodwood,
- Kuils River,
- Mitchells Plain,
- Simons Town, and
- Wynberg.
- In the Fields list, double-click on the NAME\_2 field. It appears in the SQL where clause text field below.
- Click the = button; an = sign is added to the SQL query.
- Click the *All* button below the (currently empty) *Values* list. After a short delay, this will populate the *Values* list with the values of the selected field (*NAME 2*).
- Double-click the value Bellville in the Values list. As before, this will be added to the SQL query.

In order to select more than one district, you'll need to use the OR boolean operator.

- Click the *OR* button and it will be added to the SQL query.
- Using a process similar to the above, add the following to the existing SQL query:

```
"NAME_2" = 'Cape'
```

- Add another OR operator, then work your way through the list of districts above in a similar fashion.
- The final query should be

```
"NAME_2" = 'Bellville' OR "NAME_2" = 'Cape' OR "NAME_2" = 'Goodwood' OR "NAME_2" = 'Kuils River' OR "NAME_2" = 'Mitchells Plain' OR "NAME_2" = 'Simons Town' OR "NAME_2" = 'Wynberg'
```

• Click OK. The districts shown in your map are now limited to those in the list above.

#### 9.4.9 Clip the Rasters

Now that you have an area of interest, you can clip the rasters to this area.

- Ensure that the only layers that are visible are the *DEM*, *Rainfall* and *Districts* layers.
- Districts must be on top so that they are visible.
- Open the clipping dialog by selecting the menu item  $Raster \rightarrow Extraction \rightarrow Clipper$ .
- In the *Input file (raster)* dropdown list, select the *DEM* layer.
- Specify an output location in the *Output file* text field by clicking the *Select...* button.
- Navigate to your Rasterprac directory.
- Enter a file name.
- Save the file. Leave the No data value checkbox unchecked.
- Use the *Extent* clipping mode by ensuring the correct radio button is selected.
- Click and drag an area in the canvas, so that the area which includes the districts is selected.
- Check the *Load into canvas when finished* box.
- Click OK.
- After the clipping operation is completed, DO NOT CLOSE the *Clipper* dialog. (Doing so would cause you to lose the clipping area that you have already defined.)
- Select the *Rainfall* raster in the *Input file (raster)* dropdown list and choose a different output file name.
- Do not change any other options. Do not alter the existing clipping area which you drew previously. Leave everything the same and click *OK*.
- After the second clipping operation has completed, you may close the *Clipper* dialog.
- Save the map.

#### 9.4.10 Clean up the map

- Remove the original Rainfall and DEM layers from the Layers list:
- Right-click on these layers and select *Remove*.
  - This will not remove the data from your storage device, it will merely take it out of your map.
- Deactivate the labels on the *Streets* layer:
  - Click the *Labeling* button.
  - Uncheck the Label this layer with box.
  - Click OK.
- Show all the Streets again:
  - Right-click on the layer in the Layers list.
  - Select Query.
- In the *Query* dialog that appears, click the *Clear* button, then click *OK*.

- Wait while the data is loaded. All the streets will now be visible.
- Change the raster symbology as before (see *Changing the symbology of raster layers*).
- Save the map.
- You can now hide the vector layers by unchecking the box next to them in the *Layers list*. This will make the map render faster and will save you some time.

In order to create the hillshade, you will need to use a plugin that was written for this purpose.

#### 9.4.11 Activating the Raster Terrain Analysis plugin

This plugin is included by default in QGIS 1.8. However, it may not be immediately visible. To check if it is accessible on your system:

- Click on the menu item  $Plugins \rightarrow Manage Plugins...$
- Ensure that the box next to Raster Terrain Analysis plugin is selected.
- Click OK.

You will now have access to this plugin via the Raster  $\rightarrow$  Terrain analysis menu item.

Remember that plugins may sometimes depend on certain Python modules being installed on your system. Should a plugin refuse to work while complaining of missing dependencies, please ask your tutor or lecturer for assistance.

#### 9.4.12 Create the hillshade

- In the *Layers list*, ensure that the *DEM* is the active layer (i.e., it is highlighted by having been clicked on).
- Click on the *Raster* → *Terrain analysis* → *Hillshade* menu item to open the *Hillshade* dialog.
- Specify an appropriate location for the output layer and call it *hillshade*.
- Check the Add result to project box.
- Click OK.
- Wait for it to finish processing.

The new hillshade layer has appeared in your Layers list.

- Right-click on the hillshade layer in your Layers list and bring up the Properties dialog.
- Click on the *Transparency* tab and set the transparency slider to 80%.
- Click *OK* on the dialog.
- Note the effect when the transparent hillshade is superimposed over the clipped DEM.

#### 9.4.13 Slope

- Click on the menu item  $Raster \rightarrow Terrain \ analysis$ .
- Select the *Slope* analysis type, with the clipped DEM as the input layer.
- Specify an appropriate file name and location for output purposes.
- Check the *Add result to project* box.
- Click OK.

The slope image has been calculated and added to the map. However, as usual it is just a gray rectangle. To properly see what's going on, change the symbology as follows.

• Open the layer *Properties* dialog (as usual, via the right-click menu of the layer).

- Click on the Style tab.
- Where it says *Grayscale* (in the *Color map* dropdown menu), change it to *Pseudocolor*.
- Ensure that the *Use standard deviation* radio button is selected.

#### 9.4.14 Aspect

• Use the same approach as for calculating the slope, but select *Aspect* in the initial dialog box.

Remember to save the map periodically.

#### 9.4.15 Reclassifying rasters

- Click the menu item  $Raster \rightarrow Raster\ calculator$ .
- Specify your Rasterprac directory as the location for the output layer.
- Ensure that the Add result to project box is selected.

In the *Raster bands* list on the left, you will see all the raster layers in your *Layers list*. If your Slope layer is called *slope*, it will be listed as *slope@1*.

The slope needs to be between 15 and 60 degrees. Everything less than 15 or greater than 60 must therefore be excluded.

• Using the list items and buttons in the interface, build the following expression:

```
((slope@1 < 15) OR (slope@1 > 60)) = 0
```

- Set the Output layer field to an appropriate location and file name.
- Click OK.

Now find the correct aspect (east-facing: between 45 and 135 degrees) using the same approach.

• Build the following expression:

```
((aspect@1 < 45) OR (aspect@1 > 135)) = 0
```

• Find the correct rainfall (greater than 1200mm) the same way. Build the following expression:

```
(rainfall@1 < 1200) = 0
```

Having reclassified all the rasters, you will now see them displayed as gray rectangles in your map (assuming that they have been added to the map correctly). To properly display raster data with only two classes (1 and 0, meaning true or false), you will need to change their symbology.

#### 9.4.16 Setting the style for the reclassified layers

- Open the *Style* tab in the layer's *Properties* dialog as usual.
- Under the heading Load min / max values from band, select the Actual (slower) radio button.
- Click the *Load* button.

The *Custom min / max values* fields should now populate with 0 and 1, respectively. (If they do not, then there was a mistake with your reclassification of the data, and you will need to go over that part again.)

- Under the heading Contrast enhancement, set the Current dropdown list to Stretch To MinMax.
- Click OK.
- Do this for all three reclassified rasters, and remember to save your work!

The only criterion that remains is that the area must be 250m away from urban areas. We will satisfy this requirement by ensuring that the areas we compute are 250m or more from the edge of a rural area. Hence, we need to find all rural areas first.

#### 9.4.17 Finding rural areas

- Hide all layers in the *Layers list*.
- Unhide the Zoning vector layer.
- Right-click on it and bring up the Query dialog.
- Build the following query:

```
"Gen_Zoning" = 'Rural'
```

See the earlier instructions for building the *Streets* query if you get stuck.

• When you're done, close the *Query* dialog.

You should see a collection of polygons from the *Zoning* layer. You will need to save these to a new layer file.

- On the right-click menu for Zoning, select Save as....
- Save your layer under the Zoning directory.
- Name the output file rural.shp.
- Click OK.
- Add the layer to your map.
- Click the menu item  $Vector \rightarrow Geoprocessing\ Tools \rightarrow Dissolve$ .
- Select the rural layer as your input vector layer, while leaving the Use only selected features box unchecked.
- Under Dissolve field, select Dissolve all —.
- Save your layer under the Zoning directory.
- Click *OK*. A dialog will appear asking whether you want to add the new layer to the TOC ("Table of Contents", referring to the *Layers list*).
- · Click Yes.
- Close the *Dissolve* dialog.
- Remove the *rural* and *Zoning* layers.
- Save the map.

Now you need to exclude the areas that are within 250m from the edge of the rural areas. Do this by creating a negative buffer, as explained below.

#### 9.4.18 Creating a negative buffer

- Click the menu item  $Vector \rightarrow Geoprocessing\ Tools \rightarrow Buffer(s)$ .
- In the dialog that appears, select the *rural\_dissolve* layer as your input vector layer (*Use only selected features* should not be checked).
- Select the *Buffer distance* button and enter the value -250 into the associated field; the negative value means that the buffer must be an internal buffer.
- Check the *Dissolve buffer results* box.
- Set the output file to the same directory as the other rural vector files.
- Name the output file rural\_buffer.shp.

- · Click Save.
- Click OK and wait for the processing to complete.
- Select *Yes* on the dialog that appears.
- Close the Buffer dialog.
- Remove the *rural\_dissolve* layer.
- Save the map.

In order to incorporate the rural zones into the same analysis with the three existing rasters, it will need to be rasterized as well. But in order for the rasters to be compatible for analysis, they will need to be the same size. Therefore, before you can rasterize, you'll need to clip the vector to the same area as the three rasters. A vector can only be clipped by another vector, so you will first need to create a bounding box polygon the same size as the rasters.

#### 9.4.19 Creating a bounding box vector

- Click on the menu item  $Layer \rightarrow New \rightarrow New$  Shapefile Layer...
- Under the *Type* heading, select the *Polygon* button.
- Click *Specify CRS* and set the coordinate reference system WGS 84 / UTM zone 33S: EPSG: 32733.
- · Click OK.
- Click OK on the New Vector Layer dialog as well.
- Save the vector in the *Zoning* directory.
- Name the output file bbox.shp.
- Hide all layers except the new bbox layer and one of the reclassified rasters.
- Ensure that the *bbox* layer is highlighted in the *Layers list*.
- Navigate to the *View > Toolbars* menu item and ensure that *Digitizing* is selected. You should then see a toolbar icon with a pencil or koki on it. This is the *Toggle editing* button.
- Click the *Toggle editing* button to enter *edit mode*. This allows you to edit a vector layer.
- Click the *Add feature* button, which should be nearby the *Toggle editing* button. It may be hidden behind a double arrow button; if so, click the double arrows to show the *Digitizing* toolbar's hidden buttons.
- With the *Add feature* tool activated, left-click on the corners of the raster. You may need to zoom in with the mouse wheel to ensure that it is accurate. To pan across the map in this mode, click and drag in the map with the middle mouse button or mouse wheel.
- For the fourth and final point, right-click to finalize the shape.
- Enter any arbitrary number for the shape ID.
- Click OK.
- Click the Save edits button.
- Click the *Toggle editing* button to stop your editing session.
- Save the map.

Now that you have a bounding box, you can use it to clip the rural buffer layer.

#### 9.4.20 Clipping a vector layer

- Ensure that only the *bbox* and *rural\_buffer* layers are visible, with the latter on top.
- Click the menu item *Vector* > *Geoprocessing Tools* > *Clip*.
- In the dialog that appears, set the input vector layer to *rural\_buffer* and the clip layer to *bbox*, with both *Use only selected features* boxes unchecked.
- Put the output file under the *Zoning* directory.
- Name the output file rural\_clipped.
- Click OK.
- When prompted to add the layer to the TOC, click Yes.
- Close the dialog.
- Compare the three vectors and see the results for yourself.
- Remove the *bbox* and *rural\_buffer* layers, then save your map.

Now it's ready to be rasterized.

#### 9.4.21 Rasterizing a vector layer

You'll need to specify a pixel size for a new raster that you create, so first you'll need to know the size of one of your existing rasters.

- Open the *Properties* dialog of any of the three existing rasters.
- Switch to the *Metadata* tab.
- Make a note of the X and Y values under the heading *Dimensions* in the Metadata table.
- Close the *Properties* dialog.
- Click on the *Raster* → *Conversion* → *Rasterize* menu item. You may receive a warning about a dataset being unsupported. Click it away and ignore it.
- Select rural\_clipped as your input layer.
- Set an output file location inside the Zoning directory.
- Name the output file rural\_raster.tif.
- Check the *New size* box and enter the X and Y values you made a note of earlier.
- Check the Load into canvas box.
- Click the pencil icon next to the text field which shows the command that will be run. At the end of the existing text, add a space and then the text -burn 1. This tells the Rasterize function to "burn" the existing vector into the new raster and give the areas covered by the vector the new value of 1 (as opposed to the rest of the image, which will automatically be 0).
- Click OK.
- The new raster should show up in your map once it has been computed.
- The new raster will look like a grey rectangle you may change the display style as you did for the reclassified rasters.
- · Save your map.

Now that you have all four criteria each in a separate raster, you need to combine them to see which areas satisfy all the criteria. To do so, the rasters will be multiplied with each other. When this happens, all overlapping pixels with a value of 1 will retain the value of 1, but if a pixel has the value of 0 in any of the four rasters, then it will be 0 in the result. In this way, the result will contain only the overlapping areas.

#### 9.4.22 Combining rasters

- Click the  $Raster \rightarrow Raster\ calculator\ menu\ item.$
- Build the following expression (with the appropriate names for your layers, depending on what you called them):

```
[Rural raster] * [Reclassified aspect] * [Reclassified slope] *
[Reclassified rainfall]
```

- Set the output location to the Rasterprac directory.
- Name the output raster cross\_product.tif.
- Ensure that the *Add result to project* box is checked.
- · Click OK.
- Change the symbology of the new raster in the same way as you set the style for the other reclassified rasters. The new raster now properly displays the areas where all the criteria are satisfied.

To get the final result, you need to select the areas that are greater than 6000m^2. However, computing these areas accurately is only possible for a vector layer, so you will need to vectorize the raster.

#### 9.4.23 Vectorizing the raster

- Click on the menu item  $Raster \rightarrow Conversion \rightarrow Polygonize$ .
- Select the *cross\_product* raster.
- Set the output location to Rasterprac.
- Name the file candidate\_areas.shp.
- Ensure that Load into canvas when finished is checked.
- · Click OK.
- Close the dialog when processing is complete.

All areas of the raster have been vectorized, so you need to select only the areas that have a value of 1.

- Open the Query dialog for the new vector.
- Build this query:

```
"DN" = 1
```

- Click OK.
- Create a new vector file from the results by saving the *candidate\_areas* vector after the query is complete (and only the areas with a value of 1 are visible). Use the *Save as...* function in the layer's right-click menu for this.
- Save the file in the Rasterprac directory.
- Name the file candidate\_areas\_only.shp.
- Save your map.

#### 9.4.24 Calculating the area for each polygon

- Open the new vector layer's right-click menu.
- Select Open attribute table.
- Click the *Toggle editing mode* button along the bottom of the table, or press Ctrl+E.
- ullet Click the *Open field calculator* button along the bottom of the table, or press Ctrl+I.

- Under the *New field* heading in the dialog that appears, enter the field name area. The output field type should be an integer, and the field width should be 10.
- In Field calculator expression, type:

\$area

This means that the field calculator will calculate the area of each polygon in the vector layer and will then populate a new integer column (called *area*) with the computed value.

- Click OK.
- Do the same thing for another new field called id. In Field calculator expression, type:

\$id

This ensures that each polygon has a unique ID for identification purposes.

• Click Toggle editing mode again, and save your edits if prompted to do so.

#### 9.4.25 Selecting areas of a given size

Now that the areas are known:

• Build a query (as usual) to select only the polygons larger than 6000m^2. The query is:

```
"area" > 6000
```

• Save the selection as a new vector layer called *solution.shp*.

You now have your solution areas, from which you will pick the one nearest to your house.

### 9.4.26 Digitize your house

- Create a new vector layer as before, but this time, select the *Type* value as being a *Point*.
- Ensure that it is in the correct CRS!
- Name the new layer house.shp.
- Finish creating the new layer.
- Enter edit mode (while the new layer is selected).
- Click the point where your house or other current place of residence is, using the streets as a guide. You might have to open other layers to help you find your house. If you don't live anywhere nearby, just click somewhere among the streets where a house could conceivably be.
- Enter any arbitrary number for the shape ID.
- Click OK.
- Save your edits and exit edit mode.
- Save the map.

You will need to find the centroids ("centers of mass") for the solution area polygons in order to decide which is closest to your house.

#### 9.4.27 Calculate polygon centroids

- Click on the  $Vector \rightarrow Geometry\ Tools \rightarrow Polygon\ centroids$  menu item.
- Specify the input layer as solution.shp.
- Provide the output location as Rasterprac.

- Call the destination file solution\_centroids.shp.
- Click OK and add the result to the TOC (Layers list), then close the dialog.
- Drag the new layer to the top of the layer order so that you can see it.

#### 9.4.28 Calculate which centroid is closest to your house

- Click on the menu item  $Vector \rightarrow Analysis\ Tools \rightarrow Distance\ matrix$ .
- The input layer should be your house, and the target layer *solution\_centroids*. Both of these should use the id field as their unique ID field.
- The output matrix type should be *linear*.
- Set an appropriate output location and name.
- Click OK.
- Open the file in a text editor (or import it into a spreadsheet). Note which target ID is associated with the shortest *Distance*. There may be more than one at the same distance.
- Build a query in QGIS to select only the solution areas closest to your house (selecting it using the id field).

This is the final answer to the research question.

For your submission, include the semi-transparent hillshade layer over an appealing raster of your choice (such as the *DEM* or the *slope* raster, for example). Also include the polygon of the closest solution area(s), as well as your house. Follow all the best practices for cartography in creating your output map.

### **Module: Plugins**

Plugins allow you to extend the functionality QGIS offers. In this module, you'll be shown how to activate and use plugins.


## 10.1 Lesson: Installing and Managing Plugins

To begin using plugins, you need to know how to download, install and activate them. To do this, you will learn how to use the *Plugin Installer* and *Plugin Manager*.

The goal for this lesson: To understand and use QGIS' plugin system.

# 10.1.1 Follow Along: Managing Plugins

- To open the *Plugin Manager*, click on the menu item *Plugins* → *Manage and Install Plugins*.
- In the dialog that opens, find the *Processing* plugin:



• Click in the box next to this plugin and uncheck it to uninstall it.


- · Click Close.
- Looking at the menu, you will notice that the *Processing* menu is is now gone. This means that many of the processing functions you have been using before have disappeared! This is because they are part of the *Processing* plugin, which needs to be activated for you to use them.
- Open the *Plugin Manager* again and reactivate the *Processing* plugin by clicking in the checkbox next to it and clicking *Close*..
- The *Processing* menu should be available again.




## Follow Along: Installing New Plugins

The list of plugins that you can activate and deactivate draws from the plugins that you currently have installed.

• To install new plugins, select the *Not Installed* option in the *Plugin Manager* dialog. The plugins available for you to install will be listed here. This list will vary depending on your existing system setup.



• You can find information about each plugin by selecting it in the list of plugins displayed.



• A plugin can be installed by clicking the *Install Plugin* button below the plugin information panel.


# 10.1.3 Follow Along: Configuring Additional Plugin Repositories

The plugins that are available to you for installation depend on which plugin *repositories* you are configured to use.


QGIS plugins are stored online in repositories. By default, only the official repositories are active, meaning that you can only access official plugins. These are usually the first plugins you want, because they have been tested thoroughly and are often included in QGIS by default.

It is possible, however, to try out more plugins than the default ones. First, you want to configure additional repositories. To do this:


• Open the *Settings* tab in the *Plugin Manager* dialog:



- Click Add to find and add a new repository.
- Provide a Name and URL for the new repository you want to configure and make sure the *Enabled* checkbox is selected.



• You will now see the new plugin repo listed in the list of configured Plugin Repositories



- You can also select the option to display Experimental Plugins by selecting the *Show also experimental plugins* checkbox.
- If you now switch back to the *Get More* tab, you will see that additional plugins are now available for installation.
- To install a plugin, simply click on it in the list and then click the *Install plugin* button.

#### 10.1.4 In Conclusion

Installing plugins in QGIS is simple and effective!

#### 10.1.5 What's Next?

Next we'll introduce you to some useful plugins as examples.

## 10.2 Lesson: Useful QGIS Plugins

Now that you can install, enable and disable plugins, let's see how this can help you in practice by looking at some examples of useful plugins.


**The goal for this lesson:** To familiarize yourself with the plugin interface and get acquainted with some useful plugins.

# 10.2.1 Follow Along: The Raster Terrain Analysis Plugin


• Start a new map with only the *srtm\_41\_19.tif* raster dataset in it (look in exercise\_data/raster/SRTM).

From the lesson on raster analysis, you're already familiar with raster analysis functions. You used GDAL tools (accessible via  $Raster \rightarrow Analysis$ ) for this. However, you should also know about the Raster Terrain Analysis plugin. This ships standard with newer versions of QGIS, and so you don't need to install it separately.

• Open the *Plugin Manager* and check that the Raster Terrain Analysis plugin is enabled:




- Open the Raster menu. You should see a Terrain analysis submenu.
- Click on *Terrain analysis*  $\rightarrow$  *Relief* and input the following options:




- Save the new file under exercise\_data/plugins/relief.tif (create a new folder if necessary).
- ullet Leave the *Output format* and *Z factor* unchanged.

- Make sure the Add result to project box is checked.
- Click the *Create automatically* button. The list below will be populated:




These are the colors that the plugin will use to create the relief.

• If you like, you can change these colors by double-clicking on each row's color bar. For example:




• Click *OK* and the relief will be created:



This achieves a similar effect to when you used the semi-transparent hillshade as an overlay over another raster layer. The advantage of this plugin is that it creates this effect using only one layer.

# 10.2.2 Follow Along: The OpenLayers Plugin


- Start a new map and add the *roads.shp* layer to it.
- Zoom in over the Swellendam area.
- Using the *Plugin Manager*, find a new plugin by entering the word OpenLayers in the *Filter* field.
- Select the OpenLayers plugin from the filtered list:




- Click the *Install plugin* button to install.
- When it's done, close the *Plugin Manager*.

Before using it, make sure that both your map and the plugin are configured properly:


- Open the plugin's settings by clicking on  $Web \rightarrow OpenLayers\ Overview$ .
- Use the panel to choose a map type you want. In this example, we'll use the "Hybrid" type map, but you can choose any others if you want.




- Open the *Project Properties* Dialog by selecting *Project —> Project Properties* from the menu.
- Enable "on the fly" projection and use the Google Mercator projection:



• Now use the plugin to give you a Google map of the area. You can click on *Web* → *OpenLayers Plugin* → *Add Google Hybrid Layer* to add it:




This will load a new raster image in from Google that you can use as a backdrop, or to help you find out where you are on the map. Here is such a layer, with our own vector road layer as overlay:




**Muista:** You may need to drag your roads layer above the Google layer to make it visible above the background layer. It may also be necessary to zoom to the extent of the roads layer to re-center the map.

# 10.2.3 Follow Along: The GeoSearch Plugin


- Start a new map with no datasets.
- Open the *Plugin Manager* and filter for the GeoSearch Plugin and click *Install Plugin* to install it.



- Close the *Plugin Manager*.
- You can now use the GeoSearch plugin to search for placenames. Click on  $Plugins \rightarrow GeoSearch \ Plugin \rightarrow GeoSearch$  to open the GeoSearch dialog.



• Search for Swellendam in the GeoSearch Dialog to locate it on your map:



#### 10.2.4 In Conclusion

There are many useful plugins available for QGIS. Using the built-in tools for installing and managing these plugins, you can find new plugins and make optimum use of them.

#### 10.2.5 What's Next?

Next we'll look at how to use layers that are hosted on remote servers in real time.

#### **Module: Online Resources**

When considering data sources for a map, there is no need to be restricted to data which you have saved on the computer you're working on. There are online data sources which you can load data from as long as you are connected to the Internet.

In this module, we'll cover two kinds of web-based GIS services: Web Mapping Services (WMS) and Web Feature Services (WFS).

## 11.1 Lesson: Web Mapping Services


A Web Mapping Service (WMS) is a service hosted on a remote server. Similar to a website, you can access it as long as you have a connection to the server. Using QGIS, you can load a WMS directly into your existing map.

From the lesson on plugins, you will remember that it's possible to load a new raster image from Google, for example. However, this is a once-off transaction: once you have downloaded the image, it doesn't change. A WMS is different in that it's a live service that will automatically refresh its view if you pan or zoom on the map.

**The goal for this lesson:** To use a WMS and understand its limitations.

# 11.1.1 Follow Along: Loading a WMS Layer

For this exercise, you can either use the basic map you made at the start of the course, or just start a new map and load some existing layers into it. For this example, we used a new map and loaded the original *places* and *landuse* layers and adjusted the symbology:



- Load these layers into a new map, or use your original map with only these layers visible.
- Before starting to add the WMS layer, first deactivate "on the fly" projection. This may cause the layers to no longer overlap properly, but don't worry: we'll fix that later.
- To add WMS layers, click on the Add WMS Layer button:




Remember how you connected to a SpatiaLite database at the beginning of the course. The *landuse*, *places*, and *water* layers are in that database. To use those layers, you first needed to connect to the database. Using a WMS is similar, with the exception that the layers are on a remote server.


• To create a new connection to a WMS, click on the *New* button.

You'll need a WMS address to continue. There are several free WMS servers available on the Internet. One of these is terrestris, which makes use of the OpenStreetMap dataset.


• To make use of this WMS, set it up in your current dialog, like this:



- The value of the *Name* field should be terrestris.
- The value of the *URL* field should be http://ows.terrestris.de/osm/service.
- Click *OK*. You should see the new WMS server listed:



• Click *Connect*. In the list below, you should now see these new entries loaded:




These are all the layers hosted by this WMS server.

000 Add Layer(s) from a Server Layer Order | Tilesets | Server Search terrestris 4 Connect Edit Delete Save Load Add default servers New Abstract OpenStreetMap WMS Deutschland ₩ 0 Image encoding O PNG O JPEG G GIF Coordinate Reference System (13 available) Layer name OSM-WMS Tile size Feature limit for GetFeatureInfo 10 WGS 84 Change . Help Add Close 1 Layer(s) selected

• Click once on the OSM-WMS layer. This will display its Coordinate Reference System:

Since we're not using WGS 84 for our map, let's see all the CRSs we have to choose from.


- Click the *Change* button. You will see a standard *Coordinate Reference System Selector* dialog.
- We want a projected CRS, so let's choose WGS 84 / Pseudo Mercator.




- Click OK.
- Click Add and the new layer will appear in your map as OSM-WMS.
- In the *Layers list*, click and drag it to the bottom of the list.

You will notice that your layers aren't located correctly. This is because "on the fly" projection is disabled. Let's enable it again, but using the same projection as the OSM-WMS layer, which is WGS 84 / Pseudo Mercator.

- Enable "on the fly" projection.
- In the CRS tab (Project Properties dialog), enter the value pseudo in the Filter field:



- Choose WGS 84 / Pseudo Mercator from the list.
- Click OK.
- Now right-click on one of your own layers in the *Layers list* and click *Zoom to layer extent*. You should see the Swellendam area:



Note how the WMS layer's streets and our own streets overlap. That's a good sign!

#### The nature and limitations of WMS

By now you may have noticed that this WMS layer actually has many features in it. It has streets, rivers, nature reserves, and so on. What's more, even though it looks like it's made up of vectors, it seems to be a raster, but you can't change its symbology. Why is that?

This is how a WMS works: it's a map, similar to a normal map on paper, that you receive as an image. What usually happens is that you have vector layers, which QGIS renders as a map. But using a WMS, those vector layers are on the WMS server, which renders it as a map and sends that map to you as an image. QGIS can display this image, but can't change its symbology, because all that is handled on the server.


This has several advantages, because you don't need to worry about the symbology. It's already worked out, and should be nice to look at on any competently designed WMS.

On the other hand, you can't change the symbology if you don't like it, and if things change on the WMS server, then they'll change on your map as well. This is why you sometimes want to use a Web Feature Service (WFS) instead, which gives you vector layers separately, and not as part of a WMS-style map.

This will be covered in the next lesson, however. First, let's add another WMS layer from the *terrestris* WMS server.

# 11.1.2 Try Yourself

- Hide the OSM-WSM layer in the Layers list.
- Add the "ZAF CGS 1M Bedrock Lithostratigraphy" WMS server at this URL: http://196.33.85.22/cgi-bin/ZAF\_CGS\_Bedrock\_Geology/wms
- Load the *BEDROCKGEOLOGY* layer into the map (use the *Add WMS Layer* button as before). Remember to check that it's in the same *WGS 84 / World Mercator* projection as the rest of your map!
- You might want to set its *Encoding* to *JPEG* and its *Tile size* option to 200 by 200, so that it loads faster:



Check your results

# 11.1.3 Try Yourself

- Hide all other WMS layers to prevent them rendering unnecessarily in the background.
- Add the "OGC" WMS server at this URL: http://ogc.gbif.org:80/wms
- Add the bluemarble layer.

Check your results



Part of the difficulty of using WMS is finding a good (free) server.

• Find a new WMS at directory.spatineo.com (or elsewhere online). It must not have associated fees or restrictions, and must have coverage over the Swellendam study area.

Remember that what you need in order to use a WMS is only its URL (and preferably some sort of description).

Check your results

#### 11.1.5 In Conclusion

Using a WMS, you can add inactive maps as backdrops for your existing map data.

#### 11.1.6 Further Reading

- Spatineo Directory
- · Geopole.org
- OpenStreetMap.org list of WMS servers

#### 11.1.7 What's Next?

Now that you've added an inactive map as a backdrop, you'll be glad to know that it's also possible to add features (such as the other vector layers you added before). Adding features from remote servers is possible by using a Web Feature Service (WFS). That's the topic of the next lesson.

#### 11.2 Lesson: Web Feature Services

A Web Feature Service (WFS) provides its users with GIS data in formats that can be loaded directly in QGIS. Unlike a WMS, which provides you only with a map which you can't edit, a WFS gives you access to the features themselves.

The goal for this lesson: To use a WFS and understand how it differs from a WMS.


## 11.2.1

## Follow Along: Loading a WFS Layer


- Start a new map. This is for demo purposes and won't be saved.
- Ensure that "on the fly" re-projection is switched off.
- Click the Add WFS Layer button:




- Click the *New* button.
- In the dialog that appears, enter the *Name* as nside.org and the *URL* as http://nside.org/cgi-bin/atlas\_south?version=1.1.0.



- Click *OK*, and the new connection will appear in your *Server connections*.
- Click the *Connect*. A list of the available layers will appear:




- Find the layer *south\_poles\_wfs*.
- Click on the layer to select it:




#### • Click Add.

It may take a while to load the layer. When it has loaded, it will appear in the map. Here it is over the outlines of Antarctica (available on the same server, and by the name of *antarctica\_country\_border*):




How is this different from having a WMS layer? That will become obvious when you see the layers' attributes.

• Open the *south\_poles\_wfs* layer's attribute table. You should see this:



Since the points have attributes, we are able to label them, as well as change their symbology. Here's an example:



• Add labels to your layer to take advantage of the attribute data in this layer.

#### **Differences from WMS layers**

A Web Feature Service returns the layer itself, not just a map rendered from it. This gives you direct access to the data, meaning that you can change its symbology and run analysis functions on it. However, this is at the cost of much more data being transmitted. This will be especially obvious if the layers you're loading have complicated shapes, a lot of attributes, or many features; or even if you're just loading a lot of layers. WFS layers typically take a very long time to load because of this.

# 11.2.2 Follow Along: Querying a WFS Layer


Although it is of possible to query a WFS layer after having loaded it, it's often more efficient to query it before you load it. That way, you're only requesting the features you want, meaning that you use far less bandwidth.

For example, on the WFS server we're currently using, there is a layer called *countries* (*excluding Antarctica*). Let's say that we want to know where South Africa is relative to the *south\_poles\_wfs* layer (and perhaps also the *antarctica\_country\_border* layer) that's already been loaded.


There are two ways to do this. You can load the whole *countries* ... layer, and then build a query as usual once it's loaded. However, transmitting the data for all the countries in the world and then only using the data for South Africa seems a bit wasteful of bandwidth. Depending on your connection, this dataset can take several minutes to load.

The alternative is to build the query as a filter before even loading the layer from the server.


- In the *Add WFS Layer* ... dialog, connect to the server we used before and you should see the list of available layers.
- Double-click next to the *countries* ... layer in the *Filter* field, or click *Build query*:




• In the dialog that appears, build the query "Countryeng" = 'South Africa':



• It will appear as the *Filter* value:



• Click *Add* with the *countries* layer selected as above. Only the country with the Countryeng value of South Africa will load from that layer:



You don't have to, but if you tried both methods, you'll notice that this is a lot faster than loading all the countries before filtering them!

#### Notes on WFS availability

It is rare to find a WFS hosting features you need, if your needs are very specific. The reason why Web Feature Services are relatively rare is because of the large amounts of data that must be transmitted to describe a whole feature. It is therefore not very cost-effective to host a WFS rather than a WMS, which sends only images.

The most common type of WFS you'll encounter will therefore probably be on a local network or even on your own computer, rather than on the Internet.

#### 11.2.3 In Conclusion

WFS layers are preferable over WMS layers if you need direct access to the attributes and geometries of the layers. However, considering the amount of data that needs to be downloaded (which leads to speed problems and also a lack of easily available public WFS servers) it's not always possible to use a WFS instead of a WMS.

#### 11.2.4 What's Next?

Next, you'll see how to use QGIS Server to provide OGC services.

**Module: QGIS Server** 

Module contributed by Tudor Bărăscu.

In this module, we'll cover how to install and use QGIS Server.

For an introduction to what QGIS Server is (see the *label\_qgisserver* section)

#### 12.1 Lesson: Install QGIS Server

The goal for this lesson: To learn how to install QGIS Server on Debian Stretch. With negligible variations (prepending sudo to all admin commands) you can also follow it for any Debian based distribution like Ubuntu and its derivatives.

## 12.1.1

## Follow Along: Install from packages

In this lesson we're going to do only the install from packages as shown here.

First add the QGIS repository by creating the /etc/apt/sources.list.d/debian-qgis.list file with the following content:

```
# latest stable
deb http://qgis.org/debian stretch main
deb-src http://qgis.org/debian stretch main
```

After you add the qgis.org repository public key to your apt keyring (follow the above link on how to do it) you can run the apt-get update command to refresh the packages list and apt-get dist-upgrade to upgrade the packages.

**Muista:** Currently Debian stable has LTR qgis packages in the source <code>jessie-backports</code>, so the above steps are not necessary. Just add the <code>jessie-backports</code> repository and install with the <code>-t jessie-backports</code> option.

#### Install QGIS Server with:

apt-get install qgis-server python-qgis

**Muista:** adding -y at the end of the apt-get command will run it straight away, without requiring confirmation.

QGIS Server should be used in production without QGIS Desktop (with the accompagning X Server) installed on the same machine.

## 12.1.2

### Follow Along: QGIS Server Executable

The QGIS Server executable is qgis\_mapserv.fcgi. You can check where it has been installed by running find / -name 'qgis\_mapserv.fcgi' which should output something like /usr/lib/cgi-bin/qgis\_mapserv.fcgi.

Optionally, if you want to do a command line test at this time you can run the /usr/lib/cgi-bin/ggis\_mapserv.fcgi command which should output something like:

This is a good thing, it tells you we're on the right track as the server is saying that we haven't asked for a supported service. We'll see later on how to make WMS requests.

#### 12.1.3 Follow Along: HTTP Server Configuration

In order to access on the installed QGIS server from an Internet Browser we need to use an HTTP server.

In this lesson we're going to use the Apache HTTP server, colloquially called Apache.

SetEnv QGIS\_PROJECT\_FILE /home/qgis/projects/world.qgs

First we need to install Apache by running the following command in a terminal: apt-get install apache2 libapache2-mod-fcgid.

In the /etc/apache2/sites-available directory let's create a file called qgis.demo.conf, with this content:

```
<VirtualHost *:80>
 ServerAdmin webmaster@localhost
 ServerName qgis.demo
 DocumentRoot /var/www/html
 # Apache logs (different than QGIS Server log)
 ErrorLog ${APACHE LOG DIR}/ggis.demo.error.log
 CustomLog ${APACHE_LOG_DIR}/qqis.demo.access.log combined
  # Longer timeout for WPS... default = 40
 FcgidIOTimeout 120
 FcgidInitialEnv LC_ALL "en_US.UTF-8"
 FcgidInitialEnv PYTHONIOENCODING UTF-8
 FcgidInitialEnv LANG "en_US.UTF-8"
  # QGIS log (different from apache logs) see http://docs.qgis.org/testing/en/docs/user_manual/wo
 FcgidInitialEnv QGIS_SERVER_LOG_FILE /var/log/qgis/qgisserver.log
 FcgidInitialEnv QGIS_SERVER_LOG_LEVEL 0
 FcgidInitialEnv QGIS_DEBUG 1
  # default QGIS project
```

```
# QGIS_AUTH_DB_DIR_PATH must lead to a directory writeable by the Server's FCGI process user
 FcqidInitialEnv QGIS_AUTH_DB_DIR_PATH "/home/qqis/qqisserverdb/"
 FcgidInitialEnv QGIS_AUTH_PASSWORD_FILE "/home/ggis/ggisserverdb/ggis-auth.db"
  # See http://docs.qgis.org/testing/en/docs/user_manual/working_with_vector/supported_data.html#
 SetEnv PGSERVICEFILE /home/qgis/.pg_service.conf
 FcgidInitialEnv PGPASSFILE "/home/qgis/.pgpass"
  # Tell QGIS Server instances to use a specific display number
 FcgidInitialEnv DISPLAY ":99"
  # if qgis-server is installed from packages in debian based distros this is usually /usr/lib/cg
  # run "locate qgis_mapserv.fcgi" if you don't know where qgis_mapserv.fcgi is
 ScriptAlias /cgi-bin/ /usr/lib/cgi-bin/
  <Directory "/usr/lib/cgi-bin/">
   AllowOverride None
   Options +ExecCGI -MultiViews -SymLinksIfOwnerMatch
   Order allow, deny
   Allow from all
   Require all granted
 </Directory>
<IfModule mod_fcgid.c>
FcgidMaxRequestLen 26214400
FcgidConnectTimeout 60
</IfModule>
</VirtualHost>
```

You can do the above in a linux Desktop system by pasting and saving the above configuration after doing sudo nano /etc/apache2/sites-available/qgis.demo.conf.

**Muista:** See some of the configuration options are explained in the Server server\_env\_variables section.

Let's now create the directories that will store the QGIS Server logs and the authentication database:

```
sudo mkdir /var/log/qgis/
sudo chown www-data:www-data /var/log/qgis

mkdir /home/qgis/qgisserverdb
sudo chown www-data:www-data /home/qgis/qgisserverdb
```

Muista: www-data is the Apache user on Debian based systems and we need Apache to have access to those locations or files. The chown www-data... commands changes the owner of the respective directories and files to www-data.

We can now enable the virtual host, enable the fcgid mod if it's not already enabled and restart the apache2 service:

```
sudo a2enmod fcgid
sudo a2ensite qgis.demo
sudo service apache2 restart
```

**Muista:** If you installed QGIS Server without running an X Server (included in Linux Desktop) and if you also want to use the GetPrint command then you should install a fake X Server and tell QGIS Server to use it. You can do that by running the following commands.

Install xvfb:

```
sudo apt-get install xvfb
```

#### Create the service file:

```
sudo sh -c \
"echo \
'[Unit]
Description=X Virtual Frame Buffer Service
After=network.target

[Service]
ExecStart=/usr/bin/Xvfb :99 -screen 0 1024x768x24 -ac +extension GLX +render -noreset

[Install]
WantedBy=multi-user.target' \
> /etc/systemd/system/xvfb.service"
```

Enable, start and check the status of the xvfb.service:

```
sudo systemctl enable xvfb.service
sudo systemctl start xvfb.service
sudo systemctl status xvfb.service
```

In the above configuration file there's a FcgidInitialEnv DISPLAY ":99" that tells QGIS Server instances to use display no. 99. If you're running the Server in Desktop then there's no need to install xvfb and you should simply comment with # this specific setting in the configuration file. More info at http://www.itopen.it/qgis-server-setup-notes/.

Now that Apache knows that he should answer requests to http://qgis.demo we also need to setup the client system so that it knows who qgis.demo is. We do that by adding 127.0.0.1 qgis.demo in the hosts file. We can do it with sudo sh -c "echo '127.0.0.1 qgis.demo' >> /etc/hosts". Replace 127.0.0.1 with the IP of your server.

Muista: Remember that both the myhost.conf and /etc/hosts files should be configured for our setup to work. You can also test the access to your QGIS Server from other clients on the network (e.g. Windows or Macos machines) by going to their /etc/hosts file and point the myhost name to whatever IP the server machine has on the network. You can be sure that that specific IP is not 127.0.0.1 as that's the local IP, only accessible from the local machine. On \*nix machines the hosts file is located in /etc, while on Windows it's under the C:\Windows\System32\drivers\etc directory. Under Windows you need to start your text editor with administrator privileges before opening the hosts file.

We can test one of the installed qgis servers with a http request from command line with curl http://qgis.demo/cgi-bin/qgis\_mapserv.fcgi which should output:

```
<ServiceExceptionReport version="1.3.0" xmlns="http://www.opengis.net/ogc">
<ServiceException code="Service configuration error">Service unknown or unsupported</ServiceExceptionReport>
```

Muista: curl can be installed with sudo apt-get install curl.

Apache is now configured.



### Follow Along: Create another virtual host

Let's create another Apache virtual host pointing to QGIS Server. You can choose whatever name you like (coco.bango, super.duper.training, example.com, etc.) but for simplicity sake we're going to use myhost.

- Let's set up the myhost name to point to the localhost IP by adding 127.0.0.1 x to the /etc/hosts with the following command: sudo sh -c "echo '127.0.0.1 myhost' >> /etc/hosts" or by manually editing the file with sudo gedit /etc/hosts.
- We can check that myhost points to the localhost by running in the terminal the ping myhost command which should output:

```
qgis@qgis:~$ ping myhost
PING myhost (127.0.0.1) 56(84) bytes of data.
64 bytes from localhost (127.0.0.1): icmp_seq=1 ttl=64 time=0.024 ms
64 bytes from localhost (127.0.0.1): icmp_seq=2 ttl=64 time=0.029 ms
```

• Let's try if we can access QGIS Server from the myhost site by doing: curl http://myhost/cgi-bin/qgis\_mapserv.fcgi or by accessing the url from your Debian box browser. You will probably get:

```
<!DOCTYPE HTML PUBLIC "-//IETF//DTD HTML 2.0//EN">
<html><head>
<title>404 Not Found</title>
</head><body>
<h1>Not Found</h1>
The requested URL /cgi-bin/qgis_mapserv.fcgi was not found on this server.
<hr>
<address>Apache/2.4.25 (Debian) Server at myhost Port 80</address>
</body></html>
```

- Apache doesn't know that he's supposed to answer requests pointing to the server named myhost. In order to setup the virtual host the simplest way would be to make a myhost.conf file in the /etc/apache/sites-available directory that has the same content as file:qgis.demo.conf except for the ServerName line that should be ServerName myhost. You could also change where the logs go as otherwise the logs for the two virtual hosts would be shared but this is optional.
- Let's now enable the virtual host with sudo apt-get a2ensite myhost.conf and then reload the Apache service with sudo systemctl reload apache2.
- If you try again to access the http://myhost/cgi-bin/qgis\_mapserv.fcgi url you'll notice everything is working now!

#### 12.1.5 In Conclusion

You learned how to install different QGIS Server versions from packages, how to configure Apache with QGIS Server, on Debian based Linux distros.

#### 12.1.6 What's Next?

Now that you've installed QGIS Server and it's accesible through the HTTP protocol, we need to learn how to access some of the services it can offer. The topic of the next lesson is to learn how to access QGIS Server WMS services.

## 12.2 Lesson: Serving WMS

Let's download the demo data and unzip the files in the qgis-server-tutorial-data subdirectory to any directory. We recommend that you simply create a /home/qgis/projects directory and put your files there in order to avoid possible permissions problems.

The demo data contains a QGIS project named world.qgs that is already prepared to be served with QGIS Server. If you want to use your own project or you want to learn how a project is prepared see the *Creatingwms-fromproject* section.

**Muista:** This module presents the URLs so that the audience can easily distinguish the parameters and parameters values. While the normal format is:

```
...&field1=value1&field2=value2&field3=value3
```

#### this tutorial uses:

```
&field1=value1
&field2=value2
&field3=value3
```

Pasting them into Mozilla Firefox works properly but other web browsers like Chrome may add unwanted spaces between the field:parameter pairs. So, if you encounter this issue you can either use Firefox or modify the URLs so that they're in one line format.

Let's make a WMS GetCapabilities request in the web browser or with curl:

```
http://qgisplatform.demo/cgi-bin/qgis_mapserv.fcgi
?SERVICE=WMS
&VERSION=1.3.0
&REQUEST=GetCapabilities
&map=/home/qgis/projects/world.qgs
```

In the Apache config from the previous lesson the QGIS\_PROJECT\_FILE variable sets the default project to /home/qgis/projects/world.qgs. However, in the above request we made use of the **map** parameter to be explicit and to show it can be used to point at any project. If you delete the **map** parameter from the above request QGIS Server will output the same response.

By pointing any WMS client to the GetCapabilities URL, the client gets in response an XML document with metadata of the Web Map Server's information, e.g. what layers does it serve, the geographical coverage, in what format, what version of WMS etc.

As QGIS is also a *ogc-wms* you can create a new WMS server connection with the help of the above GetCapabilities url. See the *Lesson: Web Mapping Services* or the *ogc-wms-servers* section on how to do it.

By adding the countries WMS layer to your QGIS project you should get an image like the one below:

**Muista:** QGIS Server serves layers that are defined in the world.qgs project. By opening the project with QGIS you can see there are multiple styles for the countries layer. QGIS Server is also aware of this and you can choose the style you want in your request. The classified\_by\_population style was chosen in the above image.

#### 12.2.1 Logging

When you're setting up a server, the logs are always important as they show you what's going on. We have setup in the \*.conf file the following logs:

- QGIS Server log at /logs/ggisserver.log
- qgisplatform.demo Apache access log at qgisplatform.demo.access.log
- qqisplatform.demo Apache error log at qqisplatform.demo.error.log

The log files are simply text files so you can use a text editor to check them out. You can also use the tail command in a terminal: sudo tail -f /logs/qgisserver.log.

This will continuously output in the terminal what's written in that log file. You can also have three terminals opened for each of the log files like so:

When you use QGIS Desktop to consume the QGIS Server WMS services you will see all the requests QGIS sends to the Server in the access log, the errors of QGIS Server in the QGIS Server log etc.

Muista:




Figure 12.1: QGIS Desktop consuming the QGIS Server countries layer WMS service

```
qgis@qgis: ~
File Edit View Search Terminal Help
qgis@qgis:~$ sudo tail -f /var/log/apache2/qgisplatform.demo.error.log
qgis@qgis:~$ sudo tail -f /var/log/apache2/qgisplatform.demo.error.log
                                      qgis@qgis: ~
File Edit View Search Terminal Help
200 11378 "-" "curl/7.52.1"
127.0.0.1 - - [17/Mar/2017:04:09:41 -0400] "GET /cgi-bin/qgis mapserv.fcgi?SERVICE=W
"MS&VERSION=1.3.0&REQUEST=GetCapabilities&map=/home/qgis/projects/world.qgs HTTP/1.1
200 11378 "-" "curl/7.52.1"
127.0.0.1 - - [17/Mar/2017:04:09:42 -0400] "GET /cgi-bin/qgis_mapserv.fcgi?SERVICE=W
"MS&VERSION=1.3.0&REQUEST=GetCapabilities&map=/home/qgis/projects/world.qgs HTTP/1.1
200 11378 "-" "curl/7.52.1"
                                      qgis@qgis: ~
                                                                                  101
File Edit View Search Terminal Help
[1732][04:09:42] Sent 1 blocks of 11205 bytes
[1732][04:09:42] Request finished in 3 ms
qgis@qgis:~$ sudo tail -f /logs/qgisserver.log
[1732][04:09:42] MAP:/home/qgis/projects/world.qgs
[1732][04:09:42] REQUEST:GetCapabilities
[1732][04:09:42] SERVICE:WMS
[1732][04:09:42] VERSION:1.3.0
[1732][04:09:42] Found capabilities document in cache
[1732][04:09:42] Checking byte array is ok to set...
[1732][04:09:42] Byte array looks good, setting response...
[1732][04:09:42] Sending HTTP response
[1732][04:09:42] Sent 1 blocks of 11205 bytes
[1732][04:09:42] Request finished in 3 ms
```

Figure 12.2: Using the tail command to visualise QGIS Server logs output

- If you look at the logs in the following sections you should get a better understanding on what's happening.
- By restarting Apache while looking in the QGIS Server log you can find some extra pointers on how things work.

#### 12.2.2 GetMap requests

In order to display the countries layer, QGIS Desktop, like any other WMS client, is using GetMap requests.

A simple request looks like:

```
http://qgisplatform.demo/cgi-bin/qgis_mapserv.fcgi
?MAP=/home/qgis/projects/world.qgs
&SERVICE=WMS
&VERSION=1.3.0
&REQUEST=GetMap
&BBOX=-432786,4372992,3358959,7513746
&SRS=EPSG:3857
&WIDTH=665
&HEIGHT=551
&LAYERS=countries
&FORMAT=image/jpeg
```

The above request should output the following image:

Figure: simple GetMap request to QGIS Server



## Try Yourself Change the Image and Layers parameters

Based on the request above, let's replace the countries layer with another.

In order to see what other layers are available you could open up the world.qgs project in QGIS and look at its contents. Keep in mind though that the WMS clients don't have access to the QGIS project, they just look at the capabilities document contents.

Also, there's a configuration option so that some of the layers existing in the QGIS project are ignored by QGIS when serving the WMS service.

So, you could look at the layer list when you point QGIS Desktop to the GetCapabilities URL or you could try yourself finding other layer names in the GetCapabilities XML response.

One of the layer names that you could find and works is countries\_shapeburst. You may find others but keep in mind some may not be visible at such a small scale so you could get a blank image as response.

You can also play around with others parameters from above, like changing the returned image type to image/png.

# 12.2.4

## Follow Along: Use Filter, Opacities and Filter parameters

Let's do another request that adds another layer, some of the *extra-getmap-parameters*, **FILTER** and **OPACITIES**, but also uses the standard STYLES parameter.

```
http://qgisplatform.demo/cgi-bin/qgis_mapserv.fcgi
?MAP=/home/qgis/projects/world.qgs
&SERVICE=WMS
&VERSION=1.3.0
&REQUEST=GetMap
&BBOX=-432786,4372992,3358959,7513746
&SRS=EPSG:3857
```




Figure 12.3: Qgis Server response after a simple GetMap request

```
&WIDTH=665

&HEIGHT=551

&FORMAT=image/jpeg

&LAYERS=countries,countries_shapeburst

&STYLES=classified_by_name,default

&OPACITIES=255,30

&FILTER=countries:"name" IN ( Germany', , 'Italy')
```

The above request should output the following image:




Figure 12.4: Response to a GetMap request with FILTER and OPACITIES parameters

As you can see from the above image, among other things, we told QGIS Server to render only **Germany** and **Italy** from the countries layer.

# 12.2.5 Follow Along: Use Redlining

Let's do another GetMap request that makes use of the *qgisserver-redlining* feature and of the **SELECTION** parameter detailed in the *extra-getmap-parameters* section:

```
http://qgisplatform.demo/cgi-bin/qgis_mapserv.fcgi
?MAP=/home/qgis/projects/world.qgs
&SERVICE=WMS
&VERSION=1.3.0
```

```
&REQUEST=GetMap
&BBOX=-432786,4372992,3358959,7513746
&SRS=EPSG:3857
&WIDTH=665
&HEIGHT=551
&LAYERS=countries,countries_shapeburst
&FORMAT=image/jpeg
&HIGHLIGHT_GEOM=POLYGON((590000 6900000, 590000 7363000, 2500000 7363000, 2500000 6900000, 590000
&HIGHLIGHT_SYMBOL=<StyledLayerDescriptor><UserStyle><Name>Highlight</Name><FeatureTypeStyle><Rule
&HIGHLIGHT_LABELSIZE=30
&HIGHLIGHT_LABELSIZE=30
&HIGHLIGHT_LABELSUFFERCOLOR=%23000000
&HIGHLIGHT_LABELBUFFERCOLOR=%23FFFFFF
&HIGHLIGHT_LABELBUFFERSIZE=3
&SELECTION=countries:171,65
```

Pasting the above request in your web browser should output the following image:



Figure 12.5: Response to a request with the REDLINING feature and SELECTION parameter

You can see from the above image that the countries with the 171 and 65 ids were highlighted in yellow (Romania and France) by using the **SELECTION** parameter and we used the **REDLINING** feature to overlay a rectangle with the **QGIS Tutorial** label.

#### 12.2.6 GetPrint requests

One very nice feature of QGIS Server is that it makes use of the QGIS Desktop print composers. You can learn about it in the *server\_getprint* section.

If you open the world.qgs project with QGIS Desktop you will find a print composer named Population distribution. A simplified GetPrint request that exemplifies this amazing feature is:

```
http://qgisplatform.demo/cgi-bin/qgis_mapserv.fcgi
?map=/home/qgis/projects/world.qgs
&SERVICE=WMS
&VERSION=1.3.0&
REQUEST=GetPrint
&FORMAT=pdf
&TRANSPARENT=true
&SRS=EPSG:3857
&DPI=300
&TEMPLATE=Population distribution
&map0:extent=-432786,4372992,3358959,7513746
&LAYERS=countries
```




Figure 12.6: Shows the pdf resulted from the above GetPrint request

Naturally, it's hard to write your  ${\tt GetMap}, {\tt GetPrint}$  etc. requests.

QGIS Web Client or QWC is a Web client project that can work alongside QGIS Server so that you can publish your projects on the Web or help you create QGIS Server requests for a better understanding about the possibilities.

You can install it like this:

- As user ggis go to the home directory with cd /home/ggis.
- Download the QWC project from here and unzip it.

- Make a symbolic link to the /var/www/html directory as it's the DocumentRoot that we've setup in the virtual host configuration. If you unzipped the archive under /home/qgis/Downloads/QGIS-Web-Client-master we can do that with sudo ln -s /home/qgis/Downloads/QGIS-Web-Client-master /var/www/html/.
- Access http://qgisplatform.demo/QGIS-Web-Client-master/site/qgiswebclient.html?map=/home/qgis/projects/world.qgs from your Web browser.

Now you should be able to see the Map as in the following figure:



Figure 12.7: QGIS Web Client consuming the world.qgs project

If you click the Print button in QWC you can interactively create GetPrint requests. You can also click the? icon in the QWC to access the available help so that you can better discover the QWC possibilities.

#### 12.2.7 In Conclusion

You learned how use QGIS Server to provide WMS Services.

### **12.2.8 What's Next?**

Next, you'll see how to use QGIS as a frontend for the famous GRASS GIS.

12.2. Lesson: Serving WMS

**Module: GRASS** 

GRASS (Geographic Resources Analysis Support System) is a well-known open source GIS with a wide array of useful GIS functions. It was first released in 1984, and has seen much improvement and additional functionality since then. QGIS allows you to make use of GRASS' powerful GIS tools directly.

### 13.1 Lesson: GRASS Setup


Using GRASS in QGIS requires you to think of the interface in a slightly different way. Remember that you're not working in QGIS directly, but working in GRASS *via* QGIS.

The goal for this lesson: To begin a GRASS project in QGIS.

# 13.1.1 Follow Along: Start a New GRASS Project

To launch GRASS from within QGIS, you need to activate it as with any other plugin. First, open a new QGIS project.

• In the *Plugin Manager*, enable *GRASS* in the list:



The GRASS toolbar will appear:




Before you can use GRASS, you need to create a **mapset**. GRASS always works in a database environment, which means that you need to import all the data you want to use into a GRASS database.

• Click on the *New mapset* button:



You'll see a dialog explaining the structure of a GRASS mapset.


- Create a new directory called grass\_db in exercise\_data.
- Set it as the directory that will be used by GRASS to set up its database:




• Click Next.

GRASS needs to create a "location", which describes the maximum extents of the geographic area you'll be working in.


• Call the new location South\_Africa:




- Click Next.
- $\bullet\,$  We'll be working with WGS  $\,$  84, so search for and select this CRS:



- Click Next.
- Now select the region *South Africa* from the dropdown and click *Set*:



- Click Next.
- Create a mapset, which is the map file that you'll be working with.



Once you're done, you'll see a dialog asking you to confirm that the settings it displays are correct.

- · Click Finish.
- Click OK on the success dialog.

# 13.1.2 Follow Along: Loading Vector Data into GRASS

You'll now have a blank map. To load data into GRASS, you need to follow a two-step process.


- Load data into QGIS as usual. Use the roads.shp dataset (found under exercise\_data/epsg4326/) for now.
- As soon as it's loaded, click on the *GRASS Tools* button:




- In the new dialog, select Modules list.
- Find the vector import tool by entering the term v.in.ogr.qgis in the *Filter* field.

The v stands for "vector", in means its a function to import data into the GRASS database, ogr is the software library used to read vector data, and qgis means that the tool will look for a vector from among the vectors already loaded into QGIS.

• Once you've found this tool, click on it to bring up the tool itself:



• Set the loaded layer to *roads* and its GRASS version's name to g\_roads to prevent confusion.



**Muista:** Note the extra import options provided under *Advanced Options*. These include the ability to add a WHERE clause for the SQL query used for importing the data.

- Click Run to begin the import.
- When it's done, click the *View output* button to see the newly imported GRASS layer in the map.
- Close first the import tool (click the *Close* button to the immediate right of *View output*), then close the *GRASS Tools* window.
- Remove the original *roads* layer.


Now you are left with only the imported GRASS layer as displayed in your QGIS map.

# 13.1.3 Follow Along: Loading Raster Data into GRASS

Recall that our DEM is in the Projected CRS UTM 33S / WGS 84, but our GRASS project is in the Geographic CRS WGS 84. So let's re-project the DEM first.

• Load the srtm\_41\_19.tif dataset (found under exercise\_data/raster/SRTM/) into the QGIS map as usual, using QGIS' *Add Raster Layer* tool.

• Re-project it using GDAL Warp tool (*Raster* → *Projections* → *Warp* (*Reproject*)), setting it up as shown:




• Save the raster under the same folder as the original, but with the file name DEM\_WGS84.tif. Once it appears in your map, remove the srtm\_41\_19.tif dataset from your Layers list.


Now that it's reprojected, you can load it into your GRASS database.

• Open the GRASS Tools dialog again.

- Click on the *Modules List* tab.
- Search for r.in.gdal.qgis and double click the tool to open the tool's dialog.
- Set it up so that the input layer is *DEM\_WGS84* and the output is g\_dem.



- Click Run.
- When the process is done, click *View output*.
- Close the current tab, and then Close the whole dialog.



• You may now remove the original *DEM\_WGS84* layer.

#### 13.1.4 In Conclusion

The GRASS workflow for ingesting data is somewhat different from the QGIS method because GRASS loads its data into a spatial database structure. However, by using QGIS as a frontend, you can make the setup of a GRASS mapset easier by using existing layers in QGIS as data sources for GRASS.

#### 13.1.5 What's Next?


Now that the data is imported into GRASS, we can look at the advanced analysis operations that GRASS offers.

#### 13.2 Lesson: GRASS Tools


In this lesson we will present a selection of tools to give you an idea of the capabilities of GRASS.

# 13.2.1 Follow Along: Set Raster Colors

- Open the GRASS Tools dialog.
- Look for the r.colors.table module by searching for it in the Filter field of the Modules List tab.
- Open the tool and set it up like this:



When you run the tool, it will recolor your raster:



# 13.2.2 Follow Along: Visualize Data in 3D


GRASS allows you to use a DEM to visualize your data in three dimensions. The tool you'll use for this operates on the GRASS Region, which at the moment is set to the whole extent of South Africa, as you set it up before.

• To redefine the extent to cover only our raster dataset, click this button:




When this tool is activated, your cursor will turn into a cross when over the QGIS map canvas.

- Using this tool, click and drag a rectangle around the edges of the GRASS raster.
- Click OK in the GRASS Region Settings dialog when done.
- Search for the nviz tool:




• Set it up as shown:



- Remember to enable both *Use region of this map* buttons to the right of the two raster selection dropdown menus. This will allow NVIZ to correctly assess the resolution of the rasters.
- Click the Run button.

NVIZ will set up a 3D environment using the raster and vector selected. This may take some time, depending on your hardware. When it's done, you will see the map rendered in 3D in a new window:



Experiment with the *height*, *z-exag*, and *View method* settings to change your view of the data. The navigation methods may take some getting used to.

After experimenting, close the NVIZ window.

# 13.2.3 Follow Along: The Mapcalc Tool

- Open the *GRASS Tools* dialog's *Modules List* tab and search for calc.
- From the list of modules, select *r.mapcalc* (not *r.mapcalculator*, which is more basic).
- Start the tool.

The Mapcalc dialog allows you to construct a sequence of analyses to be performed on a raster, or collection of rasters. You will use these tools to do so:




#### In order, they are:


- Add map: Add a raster file from your current GRASS mapset.
- Add constant value: Add a constant value to be used in functions.
- Add operator or function: Add an operator or function to be connected to inputs and outputs.
- Add connection: Connect elements. Using this tool, click and drag from the red dot on one item to the red dot on another item. Dots that are correctly connected to a connector line will turn gray. If the line or dot is red, it is not properly connected!
- Select item: Select an item and move selected items.
- Delete selected item: Removes the selected item from the current mapcalc sheet, but not from the mapset (if it is an existing raster).

Using these tools:


• Construct the following algorithm:



• When you click *Run*, your output should look like this:



• Click *View output* to see the output displayed in your map:



This shows all the areas where the terrain is lower than 500 meters or higher than 1000 meters.

#### 13.2.4 In Conclusion

In this lesson, we have covered only a few of the many tools GRASS offers. To explore the capabilities of GRASS for yourself, open the *GRASS Tools* dialog and scroll down the *Modules List*. Or for a more structured approach, look under the *Modules Tree* tab, which organizes tools by type.

Module: Assessment

Use your own data for this section. You will need:

- a point vector dataset of points of interest, with point names and multiple categories
- a line vector dataset of roads
- a polygon vector dataset of land use (using property boundaries)
- a visual-spectrum image (such as an aerial photograph)
- a DEM (downloadable from this URL if you don't have your own)

### 14.1 Create a base map

Before doing any data analysis, you will need a base map, which will provide your analysis result with context.


#### 14.1.1 Add the point layer

• Add in the point layer. Based on the level that you're doing the course at, do only what is listed in the appropriate section below:



- Label the points according to a unique attribute, such as place names. Use a small font and keep the labels inconspicuous. The information should be available, but shouldn't be a main feature of the map.
- Classify the points themselves into different colors based on a category. For example, categories could include "tourist destination", "police station", and "town center".





- Do the same as the
- · Classify the point size by importance: the more significant a feature, the larger its point. However, don't exceed the point size of 2.00.
- For features that aren't located at a single point (for example, provincial/regional names, or town names at a large scale), don't assign any point at all.



- Don't use point symbols to symbolize the layer at all. Instead, use labels centered over the points; the point symbols themselves should have no size.
- Use Data defined settings to style the labels into meaningful categories.
- Add appropriate columns to the attribute data if necessary. When doing so, don't create fictional data rather, use the Field Calculator to populate the new columns, based on appropriate existing values in the dataset.

#### 14.1.2 Add the line layer

• Add the road layer and then change its symbology. Don't label the roads.




• Change the road symbology to a light color with a broad line. Make it somewhat transparent as well.



- Create a symbol with multiple symbol layers. The resulting symbol should look like a real road. You can use a simple symbol for this; for example, a black line with a thin white solid line running down the center. It can be more elaborate as well, but the resulting map should not look too busy.
- If your dataset has a high density of roads at the scale you want to show the map at, you should have two road layers: the elaborate road-like symbol, and a simpler symbol at smaller scales. (Use scale-based visibility to make them switch out at appropriate scales.)
- All symbols should have multiple symbol layers. Use symbols to make them display correctly.







- In addition, roads should be classified. When using realistic road-like symbols, each type of road should have an appropriate symbol; for example, a highway should appear to have two lanes in either direction.

#### 14.1.3 Add the polygon layer

• Add the land use layer and change its symbology.



• Classify the layer according to land use. Use solid colors.



• Classify the layer according to land use. Where appropriate, incorporate symbol layers, different symbol types, etc. Keep the results looking subdued and uniform, however. Keep in mind that this will be part of a backdrop!



• Use rule-based classification to classify the land use into general categories, such as "urban", "rural", "nature reserve", etc.

#### 14.1.4 Create the raster backdrop

• Create a hillshade from the DEM, and use it as an overlay for a classified version of the DEM itself. You could also use the *Relief* plugin (as shown in the lesson on plugins).

#### 14.1.5 Finalize the base map

• Using the resources above, create a base map using some or all of the layers. This map should include all the basic information needed to orient the user, as well as being visually unified / "simple".

### 14.2 Analyze the data

- You are looking for a property that satisfies certain criteria.
- You can decide on your own criteria, which you must document.
- There are some guidelines for these criteria:
  - the target property should be of (a) certain type(s) of land use
  - it should be within a given distance from roads, or be crossed by a road
  - it should be within a given distance from some category of points, like a hospital for example





• Include raster analysis in your results. Consider at least one derived property of the raster, such as its aspect or slope.

## 14.3 Final Map

- Use the Map Composer to create a final map, which incorporates your analysis results.
- Include this map in a document along with your documented criteria. If the map has become too visually busy due to the added layer(s), deselect the layers which you feel are the least necessary.
- Your map must include a title and a legend.

#### Module: Metsänhoidon sovellus

Moduleissa 1 - 13 olet jo oppinut varsin paljon QGIS:sta ja kuinka työskennellä sillä. Jos olet kiinnostunut oppimaan joitain perussovelluksia metsänhoidosta käyttäen QGIS:ä tarjoaa tämä moduli Sinulle mahdollisuuden soveltaa jo oppimaasi sekä näyttää Sinulle eräitä uusia hyödyllisiä työkaluja.



Tämän modulin kehittämistä on sponsoroinut Euroopan Unioni.

#### 15.1 Lesson: Metsänhoitomodulin esittely

Tämän metsänhoitosovelluksen modulin seuraaminen edellyttää tietoja jotka olet oppinut tämän opetusmanuaalin moduleissa 1 - 11. Seuraavien oppituntien harjoitukset olettavat Sinun olevan jo kyvykäs tekemään useita perustoimenpiteitä QGIS:ssä ja siksi ainoastaan sellaiset työkalut esitellään yksityiskohtaisesti joita ei aiemmin ole käytetty.

Kuitenkin moduli noudattaa perustasoa oppitunneissa siten että jos Sinulla on aiempaa kokemusta QGIS:stä, voit oletettavasti seurata ohjeita ilman vaikeuksia.

Huomaa että Sinun tulee ladata tähän moduliin tarkoitettu esimerkki datan paketti.

#### 15.1.1 Metsänhoidon esimerkkidata

**Muista:** The sample data used in this module is part of the training manual data set and can be downloaded here. Download the zip file and extract the forestry\ folder into your exercise\_data\ folder.

The forestry related sample data (forestry map, forest data), has been provided by the EVO-HAMK forestry school. The datasets have been modified to adapt to the lessons needs.

The general sample data (aerial images, LiDAR data, basic maps) has been obtained from the National Land Survey of Finland open data service, and adapted for the purposes of the exercises. The open data file download service can be accessed in English here.

**Varoitus:** Kuten muullakin tässä opetusmanuaalissa, tämä moduli sisältää ohjeet lisätä, poistaa ja muuttaa GIS data-aineistoja. Olemme antaneet harjoitustietojoukot tätä varten. Ennen tässä kuvattujen tekniikoiden käyttöä omilla datoillasi varmista aina että Sinulla on käyttökelpoiset varmistukset!

#### 15.2 Lesson: Kartan georeferointi

Yleinen metsänhoidon tehtävä on päivittää metsäalueen tietoja. On mahdollista että edelliset tiedot alueesta ovat jo vuosien takaa ja ne oli kerätty analogisesti (siis paperille) tai ehkäpä ne oli digitoitu mutta jäljellä on ainoastaan paperinen versio tuosta inventointidatasta.

Todennäköisesti haluat käyttää myös tätä tietoa paikkatietojärjestelmässäsi, esimerkiksi vertailuun tuoreempien inventointien kanssa. Tämä tarkoittaa että Sinun on digitoitava käsillä oleva informaatio piakkatieto-ohjelmaasi, Mutta ennekuin aloitamme digitoinnin, on tehtävä tärkeä ensimmäinen askel, skannattava ja georeferoitava paperikarttasi.

Tämän oppitunnin tavoite: Oppia käyttämään Georeferointityökalua QGIS ohjelmassa.




Ensimmäinen toimenpide joka Sinun tulee suorittaa on skannata kartta. Jos kartta on liian suuri, voit skannata sen useampaan osaan mutta pidä mielessäsi että Sinun on toistettava alkutoimenpiteet ja georeferointi jokaiselle osalle erikseen. Joten jos mahdollista, skannaa karttaan niin vähiin osiin kuin mahdollista.

Jos aiot käyttää muuta kartaan kuin tämän oppaan ohessa saamaasi, käytä omaa skanneriasi skannataksesi kartan kuvatiedostoksi, resoluutiota 300 DPI on hyvä. Jos kartassasi on värejä, skannaa kuva värillisenä niin että voit myöhemmin käyttää noita värejä tietojen erottelemiseksi kartasta eri tasoille (esim. metsäkuviot, korkeuskäyrät, tiet ...).

Tässä esimerkissä käytät aiemmin skannattua karttaa, löydät sen nimellä rautjarvi\_map.tif datahakemistosta

# 15.2.2 Follow Along: Skannatun kartan georeferointi

Open QGIS and set the project's CRS to ETRS89 / ETRS-TM35FIN in  $Project \rightarrow Project \ Properties \rightarrow CRS$ , which is the currently used CRS in Finland. Make sure that *Enable 'on the fty' CRS transformation* is checked, since we will be working with old data that is another CRS.



Tallenna QGIS projekti nimellä map\_digitizing.qgs.


Tulet käyttämään georeferointi liitännäistä QGIS:ssä, liitännäinen on jo ladattu QGISiin. Aktivoi liitännäinen liitännäisten hallinnassa samoin kuin olet tehnyt aiemmissa moduleissa. Liitännäinen on nimeltään *Georeferointi GDAL*.

#### Kartan georeferointi:

- Avaa georeferointityökalu,  $Rasteri \rightarrow Georeferoija \rightarrow Georeferoija$ .
- Add the map image file, raut jarvi\_map.tif, as the image to georeferenciate,  $File \rightarrow Open \ raster$ .
- Kun kysytään etsi ja valitse KKJ / Finland zone 2 CRS. Tämä koordinaattijärjestelmä (CRS) oli käytössä Suomessa aiemmin vuonna 1994 kun tämä kartta luotiin.
- Klikkaa OK.

Seuraavaksi Sinun tulee määritellä muunnosasetukset kartan georeferoinnille:

- Avaa  $Asetukset \rightarrow Muunnos asetukset$ .
- Klikkaa ikonin Tulosrasteri laatikkoa, mene hakemistoon tai luo hakemisto exercise\_data\forestry\digitizing ja nimeä tiedostoksi rautjarvi\_georef.tif.
- Aseta loput parametrit kuten on näytetty alla.



#### • Klikkaa OK.

Kartta sisältää useita hiusviivaristikkoja merkaten koordinaatteja kartalla, tulemme käyttämään niitä georeferoitaessa karttaa. Voi käyttää zoomaus- ja siirtämis-työkaluja kuten tavallisestikin QGIS:ssä tutkiessasi kuvaa Georeferoija-ikkunassa.


- Zoom in to the left lower corner of the map and note that there is a cross-hair with a coordinate pair, x and y, that as mentioned before are in KKJ / Finland zone 2 CRS. You will use this point as the first ground control point for the georeferencing your map.
- Valitse *Lisää piste* työkalu ja klikkaa hiusristikon leikkauspisteessä (liikuta ja zoomaa tarvittaessa).
- Syötä karttakoordinaatit valintaikkunassa kirjoita koordinaatit kuten ne ovat kartalla
- Klikkaa OK.

Ensimmäinen koordinaatti georeferointia varten on nyt valmis.

Etsi muita mustia hiusviivaristikoita kuvassa, ne ovat erillään 1000 metrin päässä toisistaan sekä pohjois- että

itäsuunnissa. Sinun tulisi kyetä laskemaan noiden pisteiden koordinaatit suhteessa ensimmäiseen.

Zoom out in the image and move to the right until you find other cross-hair, and estimate how many kilometres you have moved. Try to get ground control points as far from each other as possible. Digitize at least three more ground control points in the same way you did the first one. You should end up with something similar to this:



Jo kolmen digitoidun maaston tarkistuspisteen jälkeen voit nähdä georeferointivirheiden tulevan punaisina viivoina pisteistä. Virheet pisteissä voidaan nähdä myös *GCP taulussa dX[pikseleihin]* ja *dY[pikseleihin]* sarakkeissa. Virhe pikseleissä ei tulisi olla suurempi kuin 10 pikseliä, jos on tulisi Sinun tarkistaa pisteet jotka olet digitoinut ja koordinaatit jotka olet anatanut löytääksesi mikä on ongelma. Voit käyttää alla olevaa kuvaa apuna.

Kun olet tyytyväinen tarkistuspisteisiisi tallenna maastotarkistuspisteet jos tarvitsisit niitä myöhemmin ja niin tulee olemaan:


- $Tiedosto \rightarrow Tallenna\ GCP\ pisteet\ nimell\"{a}....$
- In the folder exercise\_data\forestry\digitizing, name the file rautjarvi\_map.tif.points.

Lopuksi georeferoi karttasi:

- $Tiedosto \rightarrow Aloita georeferointi$ .
- Huomaa että nimesit tiedoston jo rautjarvi\_georef.tif nimellä kun muokkasit Georeferoinin asetuksia.

Nyt voit nähdä kartan QGIS projektissa georeferoituna rasterina. Huomaa että rasteri näyttää hieman kiertyneeltä mutta tämä johtuu ainoastaan siitä että tieto on KKJ / Finland zone 2 koordinaatistossa ja projektisi on

To check that your data is properly georeferenced you can open the aerial image in the exercise\_data\forestry folder, named rautjarvi\_aerial.tif. Your map and this image should match quite well. Set the map transparency to 50% and compare it to the aerial image.



Tallenna muutokset QGIS projektiin koska jatkat tästä pisteestä seuraavalla oppitunnilla.

#### 15.2.3 In Conclusion

Kuten olet huomannut, paperisen kartan georeferointi on verraten suoraviivainen toimenpide.

#### 15.2.4 What's Next?

In the next lesson, you will digitize the forest stands in your map as polygons and add the inventory data to them

#### 15.3 Lesson: Metsäkuvioiden digitointi

Unless you are going to use your georeferenced map as a simple background image, the next natural step is to digitize elements from it. You have already done so in the exercises about creating vector data in *Lesson: Creating a New Vector Dataset*, when you digitized the school fields. In this lesson, you are going to digitize the forest stands' borders that appear in the map as green lines but instead of doing it using an aerial image, you will use your georeferenced map.

**Tämän oppitunnin tavoite:** Oppia tekniikka helpottamaan digitointitoimenpidettä, digitoida metsäkuvioita ja lopuksi lisätä inventointitiedot niihin.

# 15.3.1 Follow Along: Metsäkuvioiden rajojen poimiminen


Avaa edellisellä oppitunnilla tallentamasi map\_digitizing.qqs projekti QGIS:ssä.

Kun olet skannanut ja georeferoinut karttasi voisit aloittaa digitoinnin samoin tein käyttämällä kuvaa oppaana. Tämä olisikin varmasti se tapa jos kuva olisi skannattu esimerkiksi ilmakuvasta.

If what you are using to digitize is a good map, as it is in our case, it is likely that the information is clearly displayed as lines with different colors for each type of element. Those colors can be relatively easy extracted as individual images using an image processing software like GIMP. Such separate images can be used to assist the digitizing, as you will see below.


Ensi askel on käyttää GIMP ohjelmaa tehdessä kuva joka sisältää ainoastaan metsäkuviot, tämä tarkoittaa, kaikki nuo vihertävät viivat jotka voit nähdä alkuperäisessä skannatussa kartassa:

- Avaa GIMP (jos et ole vielä asentanut sitä. lataa se internetistä tai kysy ohjaajaltasi).
- Avaa alkuperäinen karttakuva, *Tiedosto*  $\rightarrow$  *Avaa...*, rautjarvi\_map.tif hakemistossa exercise\_data/forestry. Huomaa että metsäkuviot on esitetty vihreinä viivoina (joissa kuvion numero myös vihreänä jokaisen monikulmion sisällä).




Now you can select the pixels in the image that are making up the forest stands' borders (the greenish pixels):

- Avaa työkalu  $Valitse \rightarrow V\ddot{a}rin\ mukaan$ .
- Kun työkalu on käytössä zoomaa kuvaa (*Ctrl + mouse wheel*) siten että metsäkuvion viivasta näkyvät yksittäiset pikselit jotka muodostavat viivan. Katso vasenta kuvaa alla.
- Klikkaa ja vedä hiiren osoitinta viivan keskellä siten että työkalu kerää lukuisia pikselin väriarvoja.
- Vapauta hiiren klikkaus ja odota joitakin sekunteja. Työkalun keräämät värejä vastaavat pikselit valitaan koko kuvasta.
- Zoomaa laajemmaksi nähdäksesi kuinka vihertävät pikselit on valittu koko kuvasta.
- Jos et ole tyytyväinen tulokseen, toista klikkaus- ja vetämistoimenpide.
- Your pixel selection should look something like the right image below.



Kun olet saanut valintasi valmiiksi tarvitsee Sinun kopioida valintasi uudeksi tasoksi ja tallentaa se erilliseksi kuvatiedostoksi:

- Kopioi (*Ctr+C*) valitut pikselit.
- Ja liitä pikselit suoraan (*Ctr+V*), GIMP näyttää liitetyt pikselit uutena väliaikaisena tasona *Tasot Siveltimet* panelissa *Kelluva Valinta* (*Liitetty Taso*) tasona.
- Klikkaa oikealla väliaikaista tasoa ja valitse *Uudeksi tasoksi*.
- Pasted Layer Klikkaa "silmää" alkuperäisen kuvatason vieressä piilottaaksesi sen niin että ainoastaan Liitetty Taso jää näkyväksi:



• Lopuksi valitse *Tiedosto*  $\rightarrow$  *Export...*, aseta *Valitse tiedoston tyyppi (Päätteestä)* arvoon *TIFF-kuva*, valitse digitizing hakemisto ja anna nimeksi rautjarvi\_map\_green.tif. Valitse Ei mitään pakkaukseksi kun kysytään.

Voit suorittaa saman prosessin muille elementeille kuvassa, esimerkiksi poimia mustat viivat jotka edustavat teitä tai ruskeat viivat jotka edustavat maaston korkeuskäyriä. Mutta meille metsäkuviot riittävät.

## 15.3.2 Try Yourself Georeferoi vihreiden pikselien kuva

Aivan kuten teit edellisellä oppitunnilla Sinun tulee georeferoida tämä uusi kuva jotta voit käyttää sitä muiden tietojesi kanssa,

Huomaa ettei Sinun tarvitse digitoida maaston tarkisuspisteitä änää koska tämä kuva on pohjimmiltaan sama kuva kuin alkuperäinen kartta, ainakin Georeferointi työkalun kannalta. Tässä on eräiä seikkoja jotka Sinun tulee muistaa:

- Tämä kuva on myös, tietenkin, KKJ / Finland zone 2 koordinaattijärjestelmässä.
- Sinun tulee käyttää maaston tarkistuspisteitä jotka talletit, *Tiedosto* → *Lataa GCP pisteet*.
- Remember to review the *Transformation settings*.
- Nimeä tulosrasteri raut jarvi\_green\_georef.tif hakemistoon digitizing.


Tarkista että uusi rasteri sopii hyvin yhteen alkuperäisen kartan kanssa.

# 15.3.3 Follow Along: Tukipisteiden luominen digitointiin

Having in mind the digitizing tools in QGIS, you might already be thinking that it would be helpful to snap to those green pixels while digitizing. That is precisely what you are going to do next create points from those pixels to use them later to help you follow the forest stands' borders when digitizing, by using the snapping tools available in QGIS.

- Käytä Rasteri → Muunnos → Monikulmioiksi (Rasteri Vektoriksi) työkalua muuntaaksesi vihreät viivat monikulmioiksi. Jos et muista kuinka voit palauttaa mieleen sen katsomalla
- Tallenna nimellä rautjarvi\_green\_polygon.shp hakemistoon digitizing.

Zoomaa ja katso miltä monikulmiot näyttävät. Saat jotain tämän kaltaista:



Seuraava toimenpide saada pisteet näistä monikulmioista on etsiä niiden keskiöt:

- Avaa  $Vektorr \rightarrow Geometriaty\"{o}kalut \rightarrow Monikulmioiden keski\"{o}t$ .
- Set the polygon layer you just got as the input file for the tool.
- Nimeä tulostiedosto green\_centroids.shp hakemistoon digitizing.
- Merkkaa Lisää tulokset karttapohjalle.
- Suorita työkalu monikulmioiden keskiöiden laskemiseksi.



Nyt voit poistaa rautjarvi\_green\_polygon tason Tasot panelista.


Muuta keskiötason symboleja seuraavasti:

- Avaa green\_centroids tason Ominaisuudet.
- Go to the Style tab.
- Aseta Yksikkö Karttayksiköksi.
- Aseta Koko arvoon 1.

Ei ole tarpeen erotella pisteitä toisistaan, tarvitset niiden vain olevan siellä kohdistustyökalun käyttöä varten. Voit nyt käyttää noita pisteitä seurataksesi alkuperäisiä viivoja paljon helpommin kuin ilman niitä.

# 15.3.4 Follow Along: Digitoi metsäkuviot

Olet nyt valmis aloittamaan todellisen digitointityön. Voisit aloittaa luomalla *monikulmio tyypin* vektoritiedoston, mutta tässä harjoituksessa on jo olemassa shapefile tiedosto jossa osa kiinnostuksen alueesta on jo digitoitu. Tulet vain viimeistelemään puolet metsäkuvioista jotka on jätetty pääteiden (leveät pinkit viivat) ja järven väliin:



- Siirry digitizing hakemistoon käyttäen Selain panelia (tiedoston hallinta).
- Vedä ja pudota forest\_stands.shp vektoritiedosto karttapohjallesi.


Muuta uuden tason tyyliä siten että on helpompi nähdä monikulmiot jotka on jo digitoitu:

- Monikulmioiden täyttö vihreäksi.
- Monikulmioiden rajojen leveys 1 mm.
- ja aseta läpinäkyvyys 50%.

Nyt, jos muistat aiemmista moduleista, meidän tulee asettaa ja ottaa käyttöön kohdistusvalinnat:

• Go to  $Settings \rightarrow Snapping \ options...$ 

- Activate the snapping the green\_centroids and the forest\_stands layers.
- Aseta niiden guilabel: Toleranssi arvoon 5 karttayksikköä.
- Merkkaa Vältä risteämiä laatikko forest\_stands tasolle.
- Merkkaa Mahdollista topologian muokkaus.
- Klikkaa



Näillä kohdistusasetuksilla, ainakun digitoit ja pääset tarpeeksi lähelle jotain pistetta keskiöiden tasolla tai jotain verteksiä digitoimissasi monikulmioissa, pinkki risti ilmestyy pisteelle johon kohdistetaan.

Lopuksi poista kaikkien muiden tason näkyminen paitsi forest\_stands ja rautjarvi\_georef. Varmista ettei karttakuvassa ole enää läpinäkyvyyttä.

Vielä pari tärkeää seikka ennenkuin aloitat digitoinnin:

- Älä yritä olla liian tarkka digitoidessasi rajoja.
- Jos raja on suora viiva, digitoi se vain kahdella pisteellä. Yleisesti ottaen digitoi niin vähin pistein kuin mahdollista.
- Zoomaa lähietäisyydelle vain kun Sinusta tuntuu että haluat olla tarkka, esimerkiksi, joissain kulmissa tai kun haluat monikulmion yhdistyvän toiseen monikulmioon tietyssä pisteessä.
- Käytä hiiren keskinäppäintä zoomaukseen lähelle ja kauas ja panoroi digitoidessasi.
- Digitoi ainoastaan yhtä monikulmiota kerrallaan.
- Jokaisen digitoimasi monikulmion jälkeen, kirjoita metsäkuvion identifiointitunnus jonka näet kartalta.

Nyt voit aloittaa digitoinnin:

- Paikanna metsäkuvio jonka numero on 357 karttaikkunassa.
- Ota käyttöön muokkaus forest\_stands.shp tasolle.
- Valitse Lisää kohde työkalu.
- Aloita kuvion 357 digitointi yhdistämällä joitakin pisteitä.
- Huomaa pinkit ristit jotka osoittavat kohdistusta.



- Kun olet saanut valmiiksi klikkaa oikealla päättääksesi tämän monikulmion digitoinnin.
- Anna metsäkuviolle id (tässä tapauksessa 357).
- Klikkaa OK.


Jos Sinulta ei kysytty monikulmion id tietoa kun lopetit monikulmion digitoinnin mene  $Asetukset \rightarrow Asetukset \rightarrow Digitointi$  ja varmista että :guilabel: Häivytä ominaisuustietojen pop-up ikkunat ominaisuuden luonnin jälkeen EI ole merkattu.

Digitoimasi monikulmio näyttää tältä:



Now for the second polygon, pick up the stand number 358. Make sure that the *Avoid int*. is checked for the forest\_stands layer. This option does not allow intersecting polygons at digitizing, so that if you digitize over an existing polygon, the new polygon will be trimmed to meet the border of the already existing polygons. You can use this characteristic to automatically obtain a common border.

- Aloita kuvion 358 digitointi yhdestä yhteisestä kulmasta kuvion 357 kanssa.
- Sitten jatka normaalisti kunnes pääset toiseen molemmille yhteiseen kulmaan.
- Finally, digitize a few points inside polygon 357 making sure that the common border is not intersected. See left image below.
- Klikkaa oikealla päättääksesi metsäkuvio 358 digitointi.
- Anna id arvoksi 358.
- Click *OK*, your new polygon should show a common border with the stand 357 as you can seen in the image on the right.



Monikulmion osa joka peitti olemassa olevaa monikulmiota on automaattisesti häivytetty pois ja jäljelle on jäänyt yhteinen raja kuten tarkoitus olikin.

# 15.3.5 Try Yourself Lopetellaan metsäkuvioiden digitoiinti

Nyt Sinulla on kaksi metsäkuviota valmiina. Ja hyvä ajatus kuinka jatkaa. Jatka digitointia itseksesi kunnes olet digitoinut kaikki metsäkuviot jotka rajautuvat pääteihin ja järveen.

Työ voi näyttää paljolta mutta pikaisesti tulee metsäkuvioiden digitointi tutuksi. Työ kestänee noin 15 minuuttia.

During the digitizing you might need to edit or delete nodes, split or merge polygons. You learned about the necessary tools in *Lesson: Feature Topology*, now is probably a good moment to go read about them again.

Muista että kun *Mahdollista topologian muokkaus* on aktivoitu Sinun on mahdollista siirtää kahden monikulmion yhteisiä solmupisteitä siten että yhteistä rajaa muokataan saman aikaisesti molemmille monikulmiolle.

Tuloksesi tulee näyttämään tältä:




# 15.3.6 Follow Along: Metsäkuviotietojen yhdistäminen

On mahdollista että karttasi metsän inventointitiedot ovat kirjoitettu paperille. Tässä tapauksessa tulee Sinun ensin kirjoittaa tiedot tekstitiedostoon tai laskentataulukkoon. Tässä harjoituksessa vuoden 1994 inventoinnin tiedot (sama inventointi kuin kartta) ovat jo pilkuin erotellussa tekstitiedostossa (csv).

Open the rautjarvi\_1994.csv file from the exercise\_data\forestry directory in a text editor and note that the inventory data file has an attribute called ID that has the numbers of the forest stands. Those numbers are the same as the forest stands ids you have entered for your polygons and can be used to link the data from the text file to your vector file. You can see the metadata for this inventory data in the file rautjarvi\_1994\_legend.txt in the same folder.

Avaa .csv QGIS:ssä käyttäen työkalua Tasot → Lisää erotinmerkkejä sisältävä tekstitiedosto.... Valintaikkunasssa aseta tiedot seuraavasti:



Lisää tiedot .csv tiedostosta:

- Avaa Ominaisuudet tasolle forest stands.
- Siirry Yhdistymät välilehdelle.
- Klikkaa plus-merkkiä valintaikkunan alalaidassa.
- Valitse raut jarvi\_1994.csv *Yhdistä taso* tietoon ja ID *Liittämiskenttä* tietoon.
- Varmista että Kohdekenttä tietoon on myös asetettu id.
- Klikkaa OK kahdesti.

Tiedot tekstitiedostosta tulisivat nyt olla yhdistettynä vektoritiedostoosi. Nähdäksesi mitä on tapahtunut avaa tason forest\_stands attribuuttitaulu. Voit nähdä että kaikki attribuutti inventointitiedot on nyt yhdistetty digitoimaasi vektoritasoon.


# 15.3.7 Try Yourself Attribuuttien uudelleen nimeäminen sekä alan ja ympärysmitan lisääminen

Tiedot .csv tiedostosta on vain linkattu vektoritiedostoosi. Tehdäksesi tämä yhdistämisen pysyväksi, siten että tiedot todellakin ovat aidosti talletettu vektoritiedostoon tulee Sinun tallentaa forest\_stands taso uutena vektoritiedostona. Sulje attribuuttitaulu ja klikkaa oikealla forest\_stands tasoa tallentaaksesi sen nimellä

Avaa uusi forest\_stands\_1994.shp kartallesi jottel jo tehnyt sitä. Avaa attribuuttitaulu. Huomaat että sarakkeiden nimet jotka juuri lisäsit eivät ole kovin käyttökelpoisia. Tämän ratkaisemiseksi:

• Lisää liitännäinen Table Manager kuten olet tehnyt muidenkin liitännäisten kanssa aiemmin.

- Varmista että liitännäinen on aktivoitu.
- Tasot panelissa valitse taso forest\_stands\_1994.shp.
- Then, go to  $Vector \rightarrow Table\ Manager \rightarrow Table\ manager$ .
- Käytä valintaikkunan laatikoita sarakkeiden nimien muokkauksessa vastaamaan .csv tiedostossa olevia.



- Klikkaa
- Valitse Yes säilyttääksesi tason tyylin.
- Sulje (close) Table Manager valintaikkuna.

Näihin metsäkuivioihin liittyvien tietojen keräämisen lopettelemiseksi voisit laskea kuvioiden alan ja ympärysmitan. Laskit monikulmioiden aloja harjoituksessa *Lesson: Supplementary Exercise*. Palaa tuolle oppitunnille jos tarpeen ja laske metsäkuvioiden alat, nimeä uusi attribuutti Area ja varmista että lasketut arvot ovat hehtaareina.

Nyt forest\_stands\_1994.shp tasosi on valmis ja pakattuna kaikella saatavilla olevilla tiedoilla.

Tallenna projekti säilyttääksesi nykyisen kartan esityksen siinä tapauksessa että Sinun tulee palata siihen myöhemmin.

#### 15.3.8 In Conclusion

Tähän on tarvittu mmutamia hiiren klikkauksia mutta nyt Sinulla on vanhemmat inventointitiedot digitaalisessa muodossa ja valmiina käytettäväksi QGIS:ssä.

#### 15.3.9 What's Next?

Voi olla että olisit kiinnostunut tekemään erilaista analyysia uudella tietojoukollasi, mutta saatat olla enemmän kiinnostuneempi tekemään analyysia nykyisemmällä tietojoukolla. Seuraavan oppitunnin aiheena on metsäkuvioiden luominen nykyisistä ilmavalokuvista ja jonkin merkityksellisen tiedon lisääminen tietojoukkoosi.

#### 15.4 Lesson: Metsäkuvioiden päivittäminen

Nyt kun olet digitoinut tiedot vanhemmasta inventointikartasta ja lisännyt vastaavat tiedot metsäkuvioihin, olisi seuraava askel luoda inventointi metsän nykyisestä tilasta.

You will digitize new forest stands from scratch following an aerial photo from that forest area. The forestry map you digitized in the previous lesson was created from an aerial Color Infrared (CIR) photograph. This type of imagery, where the infrared light is recorded instead of the blue light, are widely used to study vegetated areas. You will also use a CIR photograph in this lesson.

Kun olet digitoinut metsäkuviot, tulet lisäämään tietoja kuten suojelumääräysten antamia uusia rajoituksia.

**Tämän oppitunnin tavoite:** Digitoida uusi metsäkuvio joukko väri-infra ortokuvista sekä lisätä tietoja muista lähteistä.



### Vanhojen metsäkuvioiden vertailu nykyisiin ilmakuviin

The National Land Survey of Finland has an open data policy that allows you downloading a variety of geographical data like aerial imagery, traditional topographic maps, DEM, LiDAR data, etc. The service can be accessed also in English here. The aerial image used in this exercise has been created from two orthorectified CIR images downloaded from that service (M4134F\_21062012 and M4143E\_21062012).

- Open QGIS and set the project's CRS to ETRS89 / ETRS-TM35FIN in Project → Project Properties
   → CRS.
- Varmista että Aseta 'lennossa' CRS muunnokselle on merkattu.
- From the exercise\_data\forestry\ folder, add the CIR image rautjarvi\_aerial.tif that is containing the digitized lakes.
- Then save the QGIS project as digitizing\_2012.ggs.

The CIR images are from 2012. You can compare the stands that were created in 1994 with the situation almost 20 years later.

- Add your forest\_stands\_1994.shp layer.
- Set its styling so that you can see through your polygons.
- Review how the old forest stands follow (or not) what you might visually interpret as an homogeneous forest.

Zoom and pan around the area. You probably will notice that some of the old forest stands might be still corresponding with the image but others are not.

This is a normal situation, as some 20 years have passed by and different forest operations have been done (harvesting, thinning...). It is also possible that the forest stands looked homogeneous back in 1992 to the person who digitized them but as time has passed some forest has developed in different ways. Or simply the priorities for the forest inventory were different that they are today.


Next, you will create new forest stands for this image without using the old ones. Later you can compare them to see the differences.

### 15.4.2

### Interpreting the CIR Image

Let's digitize the same area that was covered by the old inventory, limited by the roads and the lake. You don't have to digitize the whole area, as in the previous exercise you can start with a vector file that already contains most of the forest stands.

- Remove the forest\_stands\_1994.shp layer.
- Add the forest\_stands\_2012.shp layer, located in the <code>exercise\_data\forestry\</code> folder.
- Set the styling of this layer so that the polygons have no fill and the borders are visible.




You can see that a region to the North of the inventory area is still missing. That will be your task, digitizing the missing forest stands.

But before you start, spend some time reviewing the forest stands already digitized and the corresponding forest in the image. Try to get an idea about how the stands borders are decided, it helps if you have some forestry knowledge.

Some ideas about what you could identify from the images:

- What forests are deciduous species (in Finland mostly birch forests) and which ones are conifers (in this region pine or spruce). In CIR images, deciduous species will often come as bright red color whereas conifers present dark green colors.
- When a forest stand age changes, by looking at the sizes of the tree crowns that can be identified in the imagery.
- The different forest stands' densities, for example forest stand were a thinning operation has recently been done would clearly show spaces between the tree crowns and should be easy to differentiate from other forest stands around it.
- Blueish areas indicate barren terrain, roads and urban areas, crops that have not started to grow etc.
- Don't use zooms too close to the image when trying to identify forest stands. A scale between 1:3 000 and 1: 5 000 should be enough for this imagery. See the image below (1: 4 000 scale):




### 15.4.3

### Try Yourself Digitizing Forest Stands from CIR Imagery

When digitizing the forest stands, you should try to get forest areas that are as homogeneous as possible in terms of tree species, forest age, stand density... Don't be too detailed though, or you will end up making hundreds of small forest stands that would not be useful at all. You should try to get stands that are meaningful in the context of forestry, not too small (at least 0.5 ha) but not too big either (no more than 3 ha).


With this indications in mind, you can now digitize the missing forest stands.

- Enable editing for forest\_stands\_2012.shp.
- Set up the snapping and topology options as in the image.
- Remember to click *Apply* or *OK*.



Start digitizing as you did in the previous lesson, with the only difference that you don't have any point layer that you are snapping to. For this area you should get around 14 new forest stands. While digitizing, fill in the Stand\_id field with numbers starting at 901.

When you are finished your layer should look something like:



Now you have a new set of polygons defining the different forest stands for the current situation as can interpreted from the CIR images. But you are obviously still missing the forest inventory data, right? For that you will still need to visit the forest and get some sample data that you will use to estimate the forest attributes for each of the forest stands. You will see how to do that in the next lesson.

For the moment, you still can improve your vector layer with some extra information that you have about conservation regulation that should be taken into account for this area.

# 15.4.4 Follow Along: Updating Forest Stands with Conservation Information

For the area you are working with, it has been researched that the following conservation regulations must be taken into account while doing the forest planning:

- Two locations of a protected species of Siberian flying squirrel (Pteromys volans) have been identified. According to the regulation, an area of 15 meters around the spots must be left untouched.
- A riparian forest of special interest growing along a stream in the area must be protected. In a visit to the field, it was found that 20 meters to both sides of the stream must be protected.


You have one vector file containing the information about the squirrel locations and another containing the digitized stream running in the North area towards the lake. From the <code>exercise\_data\forestry\</code> folder, add the vector files <code>squirrel.shp</code> and <code>stream.shp</code>.

For the protection of the squirrels locations, you are going to add a new attribute (column) to your new forest stands that will contain information about point locations that have to be protected. That information will later be available whenever a forest operation is planned, and the field team will be able to mark the area that has to be left untouched before the work starts.

- Open the attribute table for the squirrel layer.
- You can see that there are two locations that are defined as Siberian flying squirrel, and that the area to be protected is indicated by a distance of 15 meters from the locations.


To join the information about the squirrels to your forest stands, you can use the *Join attributes by location*:

- Open  $Vector \rightarrow Data\ Management\ Tools \rightarrow Join\ attributes\ by\ location.$
- Set the forest\_stands\_2012.shp layer as the *Target vector layer*.
- As Join vector layer select the squirrel.shp point layer.
- Name the output file as stands\_squirrel.shp.
- In *Output table* select *Keep all records (including non-matching target records)*. So that you keep all the forest stands in the layer instead of only keeping those that are spatially related to the squirrel locations.
- Click OK.
- Select *Yes* when prompted to add the layer to the TOC.
- Close the dialogue box.




Now you have a new forest stands layer, stands\_squirrel where there are new attributes corresponding to the protection information related to the Siberian flying squirrel.

Open the table of the new layer and order it so that the forest stands with information for the *Protection* attribute are on top. You should have now two forest stands where the squirrel has been located:




Although this information might be enough, look at what areas related to the squirrels should be protected. You know that you have to leave a buffer of 15 meters around the squirrels location:

- Open  $Vector \rightarrow Geoprocessing\ Tools \rightarrow Buffer$ .
- Make a buffer of 15 meters for the squirrel layer.
- Name the result squirrel\_15m.shp.




You will notice that if you zoom in to the location in the Northern part of the area, the buffer area extends to the neighbouring stand as well. This means that whenever a forest operation would take place in that stand, the protected location should also be taken into account.



From your previous analysis, you did not get that stand to register information about the protection status. To solve this problem:

- Run the Join attributes by location tool again.
- But this time use the squirrel\_15m layer as join layer.
- Name the output file as stands\_squirrel\_15m.shp.



Open the attribute table for the this new layer and note that now you have three forest stands that have the information about the protection locations. The information in the forest stands data will indicate to the forest manager that there are protection considerations to be taken into account. Then he or she can get the location from the squirrel dataset, and visit the area to mark the corresponding buffer around the location so that the operators in the field can avoid disturbing the squirrels environment.

# 15.4.5 Try Yourself Updating Forest Stands with Distance to the Stream

Following the same approach as indicated for the protected squirrel locations you can now update your forest stands with protection information related to the stream identified in the field:

• Remember that the buffer in this case is 20 meters around it.

- You want to have all the protection information in the same vector file, so use the stands\_squirrel\_15m layer as the target.
- Name your output as forest\_stands\_2012\_protect.shp.

Open the attributes table for the new vector layer and confirm that you now have all the protection information for the stands that are affected by the protection measures to protect the riparian forest associated with the stream.

Save your QGIS project.

#### 15.4.6 In Conclusion

You have seen how to interpret CIR images to digitize forest stands. Of course it would take some practice to make more accurate stands and usually using other information like soil maps would give better results, but you know now the basis for this type of task. And adding information from other datasets resulted to be quite a trivial task.

#### 15.4.7 What's Next?

The forest stands you digitized will be used for planning forestry operations in the future, but you still need to get more information about the forest. In the next lesson, you will see how to plan a set of sampling plots to inventory the forest area you just digitized, and get the overall estimate of forest parameters.

#### 15.5 Lesson: Järjestelmällinen näytteenottosuunnitelma

You have already digitized a set of polygons that represent the forest stands, but you don't have information about the forest just yet. For that purpose you can design a survey to inventory the whole forest area and then estimate its parameters. In this lesson you will create a systematic set of sampling plots.

When you start planning your forest inventory it is important to clearly define the objectives, the types of sample plots that will be used, and the data that will be collected to achieve the objectives. For each individual case, those will depend on the type of forest and the management purpose; and should be carefully planned by someone with forestry knowledge. In this lesson, you will implement a theoretical inventory based on a systematic sampling plot design.

The goal for this lesson: To create a systematic sampling plot design to survey the forest area.

#### 15.5.1 Metsän inventointi

There are several methods to inventory forests, each of them suiting different purposes and conditions. For example, one very accurate way to inventory a forest (if you consider only tree species) would be to visit the forest and make a list of every tree and their characteristics. As you can imagine this is not commonly applicable except for some small areas or some special situations.

The most common way to find out about a forest is by sampling it, that is, taking measurements in different locations at the forest and generalizing that information to the whole forest. These measurements are often made in *sample plots* that are smaller forest areas that can be easily measured. The sample plots can be of any size (for ex. 50 m2, 0.5 ha) and form (for ex. circular, rectangular, variable size), and can be located in the forest in different ways (for ex. randomly, systematically, along lines). The size, form and location of the sample plots are usually decided following statistical, economical and practical considerations. If you have no forestry knowledge, you might be interested in reading this Wikipedia article.



#### Follow Along: Implementing a Systematic Sampling Plot Design

For the forest you are working with, the manager has decided that a systematic sampling design is the most appropriate for this forest and has decided that a fixed distance of 80 meters between the sample plots and sampling lines will yield reliable results (for this case, +- 5% average error at a probability of 68%). Variable size plots has been decided to be the most effective method for this inventory, for growing and mature stands, but a 4 meters fixed radius plots will be used for seedling stands.

In practice, you simply need to represented the sample plots as points that will be used by the field teams later:


- Open your digitizing\_2012.qgs project from the previous lesson.
- Remove all the layers except for forest\_stands\_2012.
- Save your project now as forest\_inventory.ggs

Now you need to create a rectangular grid of points separated 80 meters from each other:

- Open  $Vector \rightarrow Research\ Tools \rightarrow Regular\ points$ .
- In the Area definitions select Input Boundary Layer.
- And as input layer set the forest\_stands\_2012 layer.
- In the *Grid Spacing* settings, select *Use this point spacing* and set it to 80.
- Save the output as  $systematic\_plots.shp$  in the forestry\sampling\ folder.
- Check Add result to canvas.
- Click OK.

**Muista:** The suggested *Regular points* creates the systematic points starting in the corner upper-left corner of the extent of the selected polygon layer. If you want to add some randomness to this regular points, you could use a randomly calculated number between 0 and 80 (80 is the distance between our points), and then write it as the *Initial inset from corner (LH side)* parameter in the tool's dialog.

You notice that the tool has used the whole extent of your stands layer to generate a rectangular grid of points. But you are only interested on those points that are actually inside your forest area (see the images below):



- Open  $Vector \rightarrow Geoprocessing\ Tools \rightarrow Clip$ .
- Select systematic\_plots as Input vector layer.
- Set forest stands 2012 as the Clip layer.
- Save the result as systematic\_plots\_clip.shp.
- Check Add result to canvas.
- Click OK.

You have now the points that the field teams will use to navigate to the designed sample plots locations. You can still prepare these points so that they are more useful for the field work. At the least you will have to add meaningful names for the points and export them to a format that can be used in their GPS devices.

Lets start with the naming of the sample plots. If you check the *Attribute table* for the plots inside the forest area, you can see that you have the default *id* field automatically generated by the *Regular points* tool. Label the points to see them in the map and consider if you could use those numbers as part of your sample plot naming:

- Open the *Layer Properties -> Labels* for your systematic\_plots\_clip.
- Check Label this layer with and select the field ID.
- Go to the *Buffer* options and check the *Draw text buffer*, set the *Size* to 1.
- Click OK.

Now look at the labels on your map. You can see that the points have been created and numbered first West to East and then North to South. If you look at the attribute table again, you will notice that the order in the table is following also that pattern. Unless you would have a reason to name the sample plots in a different way, naming them in a West-East/North-South fashion follows a logical order and is a good option.

**Muista:** If you would like to order or name them in a different way, you could use a spreadsheet to be able to order and combine rows and columns in any different way.

Nevertheless, the number values in the id field are not so good. It would be better if the naming would be something like  $p_1$ ,  $p_2$ ... You can create a new column for the systematic\_plots\_clip layer:

- $\bullet$   $\,Go\:to\:the\:Attribute\:table\:for\:systematic\_plots\_clip.$
- Enable the edit mode.
- Open the *Field calculator* and name the new column Plot\_id.
- Set the *Output field type* 'to :kbd: 'Text (string).
- In the *Expression* field, write, copy or construct this formula concat ('P\_', \$rownum'). Remember that you can also double click on the elements inside the *Function list*. The concat function can be found under *String* and the \$rownum parameter can be found under *Record*.
- Click OK.
- Disable the edit mode and save your changes.

Now you have a new column with plot names that are meaningful to you. For the <code>systematic\_plots\_clip</code> layer, change the field used for labeling to your new <code>Plot\_id</code> field.



# 15.5.3 Follow Along: Exporting Sample Plots as GPX format


The field teams will be probably using a GPS device to locate the sample plots you planned. The next step is to export the points you created to a format that your GPS can read. QGIS allows you to save your point and line vector data in GPS eXchange Format (GPX)<a href="http://en.wikipedia.org/wiki/GPS\_Exchange\_Format">http://en.wikipedia.org/wiki/GPS\_Exchange\_Format</a>, which is an standard GPS data format that can be read by most of the specialized software. You need to be careful with selecting the CRS when you save your data:

- Right click systematic\_plots\_clip and select Save as.
- In Format select GPS eXchange Format [GPX].

- Save the output as plots\_wgs84.gpx.
- In CRS select Selected CRS.
- Browse for WGS 84 (EPSG: 4326).

..note:: The GPX format accepts only this CRS, if you select a different one, QGIS will give no error but you will get an empty file.

- Click OK.
- In the dialog that opens, select only the waypoints layer (the rest of the layers are empty).



The inventory sample plots are now in a standard format that can be managed by most of the GPS software. The field teams can now upload the locations of the sample plots to their devices. That would be done by using the specific devices own software and the plots\_wgs84.gpx file you just saved. Other option would be to use the GPS Tools plugin but it would most likely involve setting the tool to work with your specific GPS device. If you are working with your own data and want to see how the tool works you can find out information about it in the section Working with GPS Data in the QGIS User Manual.

Save your QGIS project now.

#### 15.5.4 In Conclusion

You just saw how easily you can create a systematic sampling design to be used in a forest inventory. Creating other types of sampling designs will involve the use of different tools within QGIS, spreadsheets or scripting to calculate the coordinates of the sample plots, but the general idea remains the same.

#### 15.5.5 What's Next?

In the next lesson you will see how to use the Atlas capabilities in QGIS to automatically generate detailed maps that the field teams will be using to navigate to the sample plots assigned to them.

# 15.6 Lesson: Yksityiskohtaisten karttojen luominen Atlas työkalua käyttäen

The systematic sampling design is ready and the field teams have loaded the GPS coordinates in their navigation devices. They also have a field data form where they will collect the information measured at every sample plot. To easier find their way to every sample plot, they have requested a number of detail maps where some ground information can be clearly seen along with a smaller subset of sample plots and some information about the map area. You can use the Atlas tool to automatically generate a number of maps with a common format.

The goal for this lesson: Learn to use the Atlas tool in QGIS to generate detailed printable maps to assist in the field inventory work.



### Follow Along: Preparing the Map Composer

Before we can automate the detailed maps of the forest area and our sampling plots, we need to create a map template with all the elements we consider useful for the field work. Of course the most important will be a properly styled but, as you have seen before, you will also need to add lots of other elements that complete the printed map.

Open the QGIS project from the previous lesson forest\_inventory.qgs. You should have at least the following layers:

- forest\_stands\_2012 (with a 50% transparency, green fill and darker green border lines).
- systematic\_plots\_clip.
- rautjarvi\_aerial.

Save the project with a new name, map creation.ggs.

To create a printable map, remember that you use the Composer Manager:

- Open *Project* → *Composer Manager....*
- In the Composer manager dialog.
- Click the *Add* button and name your composer forest\_map.
- Klikkaa OK.
- Click the Show button.

Set up the printer options so that your maps will suit your paper and margins, for an A4 paper:

- Open menuselection: Composer -> Page Setup.
- *Size* is *A4* (217 x 297 mm).
- Orientation is Landscape.
- *Margins* (*milimeters*) are all set to 5.

In the *Print Composer* window, go to the *Composition* tab (on the right panel) and make sure that these settings for *Paper and quality* are the same you defined for the printer:

- *Size*: A4 (210x297mm).
- Orientation: Landscape.
- Quality: 300dpi.

Composing a map is easier if you make use of the canvas grid to position the different elements. Review the settings for the composer grid:


- In the *Composition* tab expand the *Grid* region.
- Check that *Spacing* is set to 10 mm.
- And that *Tolerance* is set to 2 mm.

Sinun tulee aktivoida ruudukon käyttö:

- Open the View menu.
- · Check Show grid.
- Check Snap to grid.
- Notice that options for using *guides* are checked by default, which allows you to see red guiding lines when you are moving elements in the composer.

Now you can start to add elements to your map canvas. Add first a map element so you can review how it looks as you will be making changes in the layers symbology:

- Click on the *Add New Map* button:
- Click and drag a box on the canvas so that the map occupies most of it.



Notice how the mouse cursor snaps to the canvas grid. Use this function when you add other elements. If you want to have more accuracy, change the grid *Spacing* setting. If for some reason you don't want to snap to the grid at some point, you can always check or uncheck it in the *View* menu.

## 15.6.2 🍑

### Follow Along: Taustakartan lisääminen

Leave the composer open but go back to the map. Lets add some background data and create some styling so that the map content is as clear as possible.

- Add the background raster basic\_map.tif that you can find in the exercise\_data\forestry\ folder.
- $\bullet$  When prompted select the ETRS89 / ETRS-TM35FIN CRS for the raster.

As you can see the background map is already styled. This type of ready to use cartography raster is very common. It is created from vector data, styled in a standard format and stored as a raster so that you don't have to bother styling several vector layers and worrying about getting a good result.

• Now zoom to your sample plots, so that you can see only about four or five lines of plots.

The current styling of the sample plots is not the best, but how does it look in the map composer?:



While during the last exercises, the white buffer was OK on top of the aerial image, now that the background image is mostly white you barely can see the labels. You can also check how it looks like on the composer:


- Go to the *Print Composer* window.
- Use the button to select the map element in the composer.
- Go to the *Item properties* tab.
- Under Extents click on Set to map canvas extent.
- If you need to refresh the element, under Main properties click on the Update preview.

Obviously this is not good enough, you want to make the plot numbers as clearly visible as possible for the field teams.



# Try Yourself Tasojen symboliikan muuttaminen

You have been working in *Module: Creating a Basic Map* with symbology and in *Module: Classifying Vector Data* with labeling. Go back to those modules if you need to refresh about some of the available options and tools. Your goal is to get the plots locations and their name to be as clearly visible as possible but always allowing to see the background map elements. You can take some guidance from this image:




You will use later the the green styling of the forest\_stands\_2012 layer. In order to keep it, and have a visualization of it that shows only the stand borders:

- Right click on forest\_stands\_2012 and select Duplicate
- you get a new layer named forest\_stands\_2012 copy that you can use to define a different style, for example with no filling and red borders.

Now you have two different visualizations of the forest stands and you can decide which one to display for your detail map.

Go back to the *Print composer* window often to see what the map would look like. For the purposes of creating detailed maps, you are looking for a symbology that looks good not at the scale of the whole forest area (left image below) but at a closer scale (right image below). Remember to use *Update preview* and *Set to map canvas extent* whenever you change the zoom in your map or the composer.




## 15.6.4 💞 Tr

## Try Yourself Luo kartan perusmalli

Once you have a symbology your happy with, you are ready to add some more information to your printed map. Add at least the following elements:

- Otsikko.
- · A scale bar.
- Grid frame for your map.
- Coordinates on the sides of the grid.

You have created a similar composition already in *Module: Creating Maps*. Go back to that module as you need. You can look at this example image for reference:



Export your map as an image and look at it.

- $Composer \rightarrow Export \ as \ Image.$
- Use for example the JPG format.

That is what it will look like when printed.

# 5.6.5


## Follow Along: Adding More Elements to the Composer

As you probably noticed in the suggested map template images, there are plenty of room on the right side of the canvas. Lets see what else could go in there. For the purposes of our map, a legend is not really necessary, but an overview map and some text boxes could add value to the map.

The overview map will help the field teams place the detail map inside the general forest area:

- Add another map element to the canvas, right under the title text.
- In the *Item properties* tab, open the *Overview* dropdown.

- Set the *Overview frame* to *Map 0*. This creates a shadowed rectangle over the smaller map representing the extent visible in the bigger map.
- Check also the *Frame* option with a black color and a *Thickness* of 0.30.



Notice that your overview map is not really giving an overview of the forest area which is what you want. You want this map to represent the whole forest area and you want it to show only the background map and the forest\_stands\_2012 layer, and not display the sample plots. And also you want to lock its view so it does not change anymore whenever you change the visibility or order of the layers.


- Go back to the map, but don't close the *Print composer*.
- Right click the forest\_stands\_2012 layer and click on Zoom to Layer Extent.
- Deactivate all layers except for basic\_map and forest\_stands\_2012.
- Go back to the Print composer.
- With the small map selected, click the *Set to map canvas extent* to set its extents to what you can see in the map window.
- Lock the view for the overview map by checking Lock layers for map item under Main properties.

Now your overview map is more what you expected and its view will not change anymore. But, of course, now your detail map is not showing anymore the stand borders nor the sample plots. Lets fix that:

- Go to the map window again and select the layers you want to be visible (systematic\_plots\_clip, forest\_stands\_2012 copy and Basic\_map).
- Zoom again to have only a few lines of sample plots visible.
- Go back to the *Print composer* window.
- Select the bigger map in your composer ( ).
- In *Item properties* click on *Update preview* and *Set to map canvas extent*.

Notice that only the bigger map is displaying the current map view, and the small overview map is keeping the same view you had when you locked it.

Note also that the overview is showing a shaded frame for the extent shown in the detail map.



Your template map is almost ready. Add now two text boxes below the map, one containing the text 'Detailed map zone: 'and the other one 'Remarks: '. Place them as you can see in the image above.


You can also add a North arrow to the overview map:

- Use the *Add image* tool, **\Bigsi**.
- Click at the upper right corner of the overview map.
- In *Item properties* open *Search directories* and browse for an arrow image.
- Under Image rotation, check the Sync with map and select Map 1 (the overview map).
- Uncheck Background.
- Resize the arrow image to a size that looks good on the small map.

The basic map composer is ready, now you want to make use of the Atlas tool to generate as many detail maps in this format as you consider necessary.


# 15.6.6 Follow Along: Creating an Atlas Coverage

The Atlas coverage is just a vector layer that will be used to generate the detail maps, one map for every feature in the coverage. To get an idea of what you will do next, here is a full set of detail maps for the forest area:



The coverage could be any existing layer, but usually it makes more sense to create one for the specific purpose. Let's create a grid of polygons covering the forest area:

- In the QGIS map view, open  $Vector \rightarrow Research\ Tools \rightarrow Vector\ grid$ .
- Set the tool as shown in this image:



- Save the output as atlas\_coverage.shp.
- Style the new atlas\_coverage layer so that the polygons have no filling.


The new polygons are covering the whole forest area and they give you an idea of what each map (created from each polygon) will contain.



# 15.6.7 Follow Along: Setting Up the Atlas Tool

The last step is to set up the Atlas tool:


- Go back to the *Print Composer*.
- In the panel on the right, go to the *Atlas generation* tab.
- Set the options as follows:



That tells the Atlas tool to use the features (polygons) inside atlas\_coverage as the focus for every detail map. It will output one map for every feature in the layer. The *Hidden coverage layer* tells the Atlas to not show the polygons in the output maps.

One more thing needs to be done. You need to tell the Atlas tool what map element is going to be updated for every output map. By now, you probably can guess that the map to be changed for every feature is the one you have prepared to contain detail views of the sample plots, that is the bigger map element in your canvas:

- Select the bigger map element.
- Go to the *Item properties* tab.
- In the list, check Controlled by atlas.
- And set the *Marging around feature* to 10%. The view extent will be 10% bigger than the polygons, which means that your detail maps will have a 10% overlap.



Now you can use the preview tool for Atlas maps to review what your maps will look like:

- Activate the Atlas previews using the button or if your Atlas toolbar is not visible, via Atlas → Preview Atlas.
- You can use the arrows in the Atlas tool bar or in the Atlas menu to move through maps that will be created.


Note that some of them cover areas that are not interesting. Lets do something about it and save some trees by not printing those useless maps.

# 15.6.8 Follow Along: Editing the Coverage Layer

Besides removing the polygons for those areas that are not interesting, you can also customize the text labels in your map to be generated with content from the *Attribute table* of your coverage layer:

- Go back to the map view.
- Enable editing for the atlas\_coverage layer.

- Select the polygons that are selected (in yellow) in the image below.
- Remove the selected polygons.
- Disable editing and save the edits.



You can go back to the *Print Composer* and check that the previews of the Atlas use only the polygons you left in the layer.

The coverage layer you are using does not yet have useful information that you could use to customize the content of the labels in your map. The first step is to create them, you can add for example a zone code for the polygon areas and a field with some remarks for the field teams to have into account:

- Open the Attribute table for the atlas\_coverage layer.
- Enable editing.
- Use the calculator to create and populate the following two fields.
- Create a field named Zone and type Whole number (integer).
- In the *Expression* box write/copy/construct \$rownum.
- Create another field named Remarks, of type Text (string) and a width of 255.

• In the Expression box write 'No remarks.'. This will set all the default value for all the polygons.

The forest manager will have some information about the area that might be useful when visiting the area. For example, the existence of a bridge, a swamp or the location of a protected species. The atlas\_coverage layer is probably in edit mode still, add the following text in the Remarks field to the corresponding polygons (double click the cell to edit it):


- For the Zone 2: Bridge to the North of plot 19. Siberian squirrel between  $p_13$  and  $p_14...$
- ullet For the Zone 6: Difficult to transit in swamp to the North of the lake..
- For the Zone 7: Siberian squirrel to the South East of p\_94..
- Disable editing and save your edits.

Almost ready, now you have to tell the Atlas tool that you want some of the text labels to use the information from the atlas\_coverage layer's attribute table.

- Go back to the Print Composer.
- Select the text label containing Detailed map....
- Set the *Font* size to 12.
- Set the cursor at the end of the text in the label.
- In the *Item properties* tab, inside the *Main properties* click on *Insert an expression*.
- In the Function list double click on the field Zone under Field and Values.
- Klikkaa OK.
- The text inside the box in the *Item properties* should show Detail map inventory zone: [% "Zone" %]. Note that the [% "Zone" %] will be substituted by the value of the field Zone for the corresponding feature from the layer atlas\_coverage.

Test the contents of the label by looking at the different Atlas preview maps.

Do the same for the labels with the text Remarks: using the field with the zone information. You can leave a break line before you enter the expression. You can see the result for the preview of zone 2 in the image below:



Use the Atlas preview to browse through all the maps you will be creating soon and enjoy!




Last but not least, printing or exporting your maps to image files or PDF files. You can use the  $Atlas \rightarrow Export$   $Atlas \ as \ Images...$  or  $Atlas \rightarrow Export \ Atlas \ as \ PDF...$ . Currently the SVG export format is not working properly and will give a poor result.

Lets print the maps as a single PDF that you can send to the field office for printing:

- Go to the *Atlas generation* tab on the right panel.
- Under the *Output* check the *Single file export when possible*. This will put all the maps together into a PDF file, if this option is not checked you will get one file for every map.
- Open *Composer* → *Export as PDF....*
- Save the PDF file as inventory\_2012\_maps.pdf in your exercise\_data\forestry\samplig\map\_creation\folder.

Open the PDF file to check that everything went as expected.

You could just as easily create separate images for every map (remember to uncheck the single file creation), here you can see the thumbnails of the images that would be created:



In the *Print Composer*, save your map as a composer template as forestry\_atlas.qpt in your exercise\_data\forestry\map\_creation\ folder. Use  $Composer \rightarrow Save$  as Template. You will be able to use this template again and again.

Close the Print Composer and save your QGIS project.

#### 15.6.10 In Conclusion

You have managed to create a template map that can be used to automatically generate detail maps to be used in the field to help navigate to the different plots. As you noticed, this was not an easy task but the benefit will come when you need to create similar maps for other regions and you can use the template you just saved.

#### 15.6.11 What's Next?

In the next lesson, you will see how you can use LiDAR data to create a DEM and then use it to your enhance your data and maps visibility.

### 15.7 Lesson: Metsän parametrien laskenta

Estimating the parameters of the forest is the goal of the forest inventory. Continuing the example from previous lesson, you will use the inventory information gathered in the field to calculate the forest parameters, for the whole forest first, and then for the stands you digitized before.

The goal for this lesson: Calculate forest parameters at general and stand level.

# 15.7.1 Follow Along: Inventointitulosten lisääminen

The field teams visited the forest and with the help of the information you provided, gathered information about the forest at every sample plot.

Most often the information will be collected into paper forms in the field, then typed to a spreadsheet. The sample plots information has been condensed into a .csv file that can be easily open in QGIS.

Continue with the QGIS project from the lesson about designing the inventory, you probably named it forest\_inventory.qgs.

First, add the sample plots measurements to your QGIS project:

• Go to Layer  $\rightarrow$  Add Delimited Text Layer....

- Browse to the file systematic\_inventory\_results.csv located in exercise\_data\forestry\results\.
- Make sure that the *Point coordinates* option is checked.
- Set the fields for the coordinates to the X and Y fields.
- Click OK.
- When prompted, select ETRS89 / ETRS-TM35FIN as the CRS.
- Open the new layer's *Attribute table* and have a look at the data.

You can read the type of data that is contained in the sample plots measurements in the text file legend\_2012\_inventorydata.txt located in the exercise\_data\forestry\results\ folder.

The systematic\_inventory\_results layer you just added is actually just a virtual representation of the text information in the .csv file. Before you continue, convert the inventory results to a real shapefile:

- Right click on the systematic\_inventory\_results layer.
- Browse to exercise\_data\forestry\results\ folder.
- Name the file sample\_plots\_results.shp.
- Check Add saved file to map.
- Remove the systematic\_inventory\_results layer from your project.

## 15.7.2

### Follow Along: Whole Forest Parameters Estimation


You can calculate the averages for this whole forest area from the inventory results for the some interesting parameters, like the volume and the number of stems per hectare. Since the systematic sample plots represent equal areas, you can directly calculate the averages of the volumes and number of stems per hectare from the sample\_plots\_results layer.

You can calculate the average of a field in a vector layer using the Basic statistics tool:

- Open  $Vector \rightarrow Analysis\ Tools \rightarrow Basic\ statistics$ .
- Select the sample\_plots\_results as the *Input Vector Layer*.
- Select Vol as Target field.
- Click OK.

The average volume in the forest is 135.2 m3/ha.

You can calculate the average for the number of stems in the same way, 2745 stems/ha.



## 15.7.3


### Follow Along: Estimating Stand Parameters

You can make use of those same systematic sample plots to calculate estimates for the different forest stands you digitized previously. Some of the forest stands did not get any sample plot and for those you will not get information. You could have planned some extra sample plots when you planned the systematic inventory, so that the field teams would have measured a few extra sample plots for this purpose. Or you could send a field team later to get estimates of the missing forest stands to complete the stand inventory. Nevertheless, you will get information for a good number of stands just using the planned plots.

What you need is to get the averages of the sample plots that are falling within each of the forest stands. When you want to combine information based on their relative locations, you perform a spatial join:

- Open the  $Vector \rightarrow Data\ Management \rightarrow Join\ attributes\ by\ location\ tool.$
- Set forest\_stands\_2012 as the *Target vector layer*. The layer you want the results for.
- Set sample\_plots\_results as the *Join vector layer*. The layer you want to calculate estimates from.
- Check Take summary of intersecting features.
- Check to calculate only the Mean.
- Name the result as forest\_stands\_2012\_results.shp and save it in the exercise\_data\forestry\results\folder.
- Finally select *Keep all records...*, so you can check later what stands did not get information.
- Click OK.
- Accept adding the new layer to your project when prompted.
- Close the *Join attributes by location* tool.

Open the *Attribute table* for forest\_stands\_2012\_results and review the results you got. Note that a number of forest stands have NULL as the value for the calculations, those are the ones having no sample plots. Select them all review them in the map, they are some of the smaller stands:



Lets calculate now the same averages for the whole forest as you did before, only this time you will use the averages you got for the stands as the bases for the calculation. Remember that in the previous situation, each sample plot represented a theoretical stand of  $80\times80~$  m. Now you have to consider the area of each of the stands individually instead. That way, again, the average values of the parameters that are in, for example, m3/ha for the volumes are converted to total volumes for the stands.

You need to first calculate the areas for the stands and then calculate total volumes and stem numbers for each of them:

- In the *Attribute table* enable editing.
- Open the Field calculator.
- Create a new field called area.


- Leave the Output field type to Decimal number (real).
- Set the *Precision* to 2.
- In the Expression box, write \$area / 10000. This will calculate the area of the forest stands in ha.
- Click OK.

Now calculate a field with the total volumes and number of stems estimated for every stand:

- Name the fields s\_vol and s\_stem.
- The fields can be integer numbers or you can use real numbers also.
- Use the expressions "area" \* "MEANVol" and "area" \* "MEANStems" for total volumes and total stems respectively.
- Save the edits when you are finished.
- Disable editing.

In the previous situation, the areas represented by every sample plot were the same, so it was enough to calculate the average of the sample plots. Now to calculate the estimates, you need to divide the sum of the stands volumes or number of stems by the sum of the areas of the stands containing information.

- In the *Attribute table* for the forest\_stands\_2012\_results layer, select all the stands containing information.
- Open  $Vector \rightarrow Analysis\ Tools \rightarrow Basic\ statistics$ .
- Select the forest\_stands\_2012\_results as the *Input Vector Layer*.
- Select area as Target field.
- Check the Use only selected features
- Click OK.



As you can see, the total sum of the stands' areas is 66.04 ha. Note that the area of the missing forest stands is only about 7 ha.

In the same way, you can calculate that the total volume for these stands is 8908 m3/ha and the total number of stems is 179594 stems.

Using the information from the forest stands, instead of directly using that from the sample plots, gives the following average estimates:

- 184.9 m3/ha and
- 2719 stems/ha.

Save your QGIS project, forest\_inventory.qgs.

#### 15.7.4 In Conclusion

You managed to calculate forest estimates for the whole forest using the information from your systematic sample plots, first without considering the forest characteristics and also using the interpretation of the aerial image into forest stands. And you also got some valuable information about the particular stands, which could be used to plan the management of the forest in the coming years.

#### 15.7.5 What's Next?

In the following lesson, you will first create a hillshade background from a LiDAR dataset which you will use to prepare a map presentation with the forest results you just calculated.

### 15.8 Lesson: DEM from LiDAR Data

You can improve the look of your maps by using different background images. You could use the basic map or the aerial image you have been using before, but a hillshade raster of the terrain will look nicer in some situations.

You will use LAStools to extract a DEM from a LiDAR dataset and then create a hillshade raster to use in your map presentation later.

The goal for this lesson: Install LAStools and calculate a DEM from LiDAR data and a hillshade raster.


## 15.8.1 Follow Along: Lastools asennus

Managing LiDAR data within QGIS is possible using the Processing framework and the algorithms provided by LAStools.

You can obtain a digital elevation model (DEM) from a LiDAR point cloud and then create a hillshade raster that is visually more intuitive for presentation purposes. First you will have to set up the *Processing* framework settings to properly work with LAStools:

- Sulje QGIS, jos olet jo käynnistänyt sen.
- An old lidar plugin might be installed by default in your system in the folder C:/Program Files/QGIS Valmiera/apps/qgis/python/plugins/processing/.
- If you have a folder named lidar, delete it. This is valid for some installations of QGIS 2.2 and 2.4.

15.8. Lesson: DEM from LiDAR Data



- Go to the exercise\_data\forestry\lidar\ folder, there you can find the file QGIS\_2\_2\_toolbox.zip. Open it and extract the lidar folder to replace the one you just deleted.
- If you are using a different QGIS version, you can see more installation instructions in this tutorial.

Now you need to install the LAStools to your computer. Get the newest lastools version here and extract the content of the lastools. zip file into a folder in your system, for example, c:\lastools\. The path to the lastools folder cannot have spaces or special characters.


**Muista:** Read the LICENSE.txt file inside the lastools folder. Some of the LAStools are open source and other are closed source and require licensing for most commercial and governmental use. For education and evaluation purposes you can use and test LAStools as much as you need to.

The plugin and the actual algorithms are now installed in your computer and almost ready to use, you just need to set up the Processing framework to start using them:

- Open a new project in QGIS.
- Set the project's CRS to ETRS89 / ETRS-TM35FIN.
- Save the project as forest\_lidar.qgs.

To setup the LAStools in QGIS:


- Go to *Processing*  $\rightarrow$  *Options and configuration*.
- In the *Processing options* dialog, go to *Providers* and then to *Tools for LiDAR data*.
- Check Activate.
- For *LAStools folder* set c:\lastools\ (or the folder you extracted LAStools to).




# 15.8.2 Follow Along: Calculating a DEM with LAStools

You have already used the *Processing* toolbox in *Lesson: Spatial Statistics* to run some SAGA algorithms. Now you are going to use it to run LAStools programs:

- Open  $Processing \rightarrow Toolbox$ .
- In the dropdown menu at the bottom, select *Advanced interface*.
- You should see the *Tools for LiDAR data* category.




- Expand it to see the tools available, and expand also the *LAStools* category (the number of algorithms may vary).
- Scroll down until you find the *lasview* algorithm, double click it to open.
- At  $Input\ LAS/LAZ\ file,$  browse to exercise\_data\forestry\lidar\ and select the rautjarvi\_lidar.laz file.



· Click Run.

Now you can see the LiDAR data in the just a little LAS and LAZ viewer dialog window:



There are many things you can do within this viewer, but for now you can just click and drag on the viewer to pan the LiDAR point cloud to see what it looks like.


Muista: If you want to know further details on how the LAStools work, you can read the README text files

about each of the tools, in the C:\lastools\bin\ folder. Tutorials and other materials are available at the Rapidlasso webpage.

• Close the viewer when you are ready.


Creating a DEM with LAStools can be done in two steps, first one to classify the point cloud into ground and no ground points and then calculating a DEM using only the ground points.

- Go back to the *Processing Toolbox*.
- Note the Search... box, write lasground.
- Double click to open the *lasground* tool and set it as shown in this image:




• The output file is saved to the same folder where the rautjarvi\_lidar.laz is located and it is named rautjarvi\_lidar\_1.las.

You can open it with lasview if you want to check it.



The brown points are the points classified as ground and the gray ones are the rest, you can click the letter g to visualize only the ground points or the letter u to see only the unclassified points. Click the letter a to see all the points again. Check the <code>lasview\_README.txt</code> file for more commands. If you are interested, also this tutorial about editing LiDAR points manually will show you different operations within the viewer.

- Close the viewer again.
- In the *Processing Toolbox*, search for las2dem.
- Open the *las2dem* tool and set it as shown in this image:



The result DEM is added to your map with the generic name Output raster file.


**Muista:** The *lasground* and *las2dem* tools require licensing. You can use the unlicensed tool as indicated in the license file, but you get the diagonals you can appreciate in the image results.

# 15.8.3

## .3 Follow Along: Creating a Terrain Hillshade


For visualization purposes, a hillshade generated from a DEM gives a better visualization of the terrain:

- Open  $Raster \rightarrow Terrain \ analysis \rightarrow Hillshade$ .
- As the  $Output\ layer,$  browse to exercise\_data\forestry\lidar\ and name the file hillshade.tif.
- Leave the rest of parameters with the default settings.



• Select ETRS89  $\,/\,$  ETRS-TM35FIN as the CRS when prompted.

Despite the diagonal lines remaining in the hillshade raster result, you can clearly see an accurate relief of the area. You can even see the different soil drains that have been dug in the forests.



#### 15.8.4 In Conclusion

Using LiDAR data to get a DEM, specially in forested areas, gives good results with not much effort. You could also use ready LiDAR derived DEMs or other sources like the SRTM 9m resolution DEMs. Either way, you can use them to create a hillshade raster to use in your map presentations.

#### 15.8.5 What's Next?

In the next, and final step in this module, lesson you will use the hillshade raster and the forest inventory results to create a map presentation of the results.

### 15.9 Lesson: Karttaesitys

In the previous lessons you have imported an old forest inventor as a GIS project, updated it to the current situation, designed a forest inventory, created maps for the field work and calculated forest parameters from the field measurements.

It is often important to create maps with the results of a GIS project. A map presenting the results of the forest inventory will make it easier for anyone to have a good idea of what the results are in a quick glance, without looking at the specific numbers.

The goal for this lesson: Create a map to present the inventory results using a hillshade raster as background.

## 15.9.1

### Follow Along: Preparing the Map Data

Open the QGIS project from the parameters calculations lesson, forest\_inventory.qgs. Keep at least the following layers:

- forest\_stands\_2012\_results.
- basic\_map.
- rautjarvi\_aerial.
- lakes (if you don't have it, add it from the exercise\_data\forestry\ folder).


You are going to present the average volumes of your forest stands in a map. If you open the *Attribute table* for the forest\_stands\_2012\_results layer, you can see the NULL values for the stands without information. To be able to get also those stands into your styling you should change the NULL values to, for example, -999, knowing that those negative numbers mean there is no data for those polygons.

For the forest\_stands\_2012\_results layer:


- Open the Attribute table and enable editing.
- Select the polygons with NULL values.
- Use the calculator to update the values of the MEANVol field to -999 only for the selected features.
- Disable editing and save the changes.

Now you can use a saved style for this layer:

- Go to the Style tab.
- Click on Load Style.
- Select the forest\_stands\_2012\_results.qml from the exercise\_data\forestry\results\ folder.
- Click OK.




Your map will look something like this:





The style you loaded:




is using the Hard light mode for the *Layer blending mode*. Note that the different modes apply different filters combining the underlying and overlying layers, in this case the hillshade raster and your forest stands are used. You can read about these modes in the User Guide.

Try with different modes and see the differences in your map. Then choose the one you like better for your final map.


# 15.9.3 Try Yourself Using a Composer Template to Create the Map result

Use a template prepared in advanced to present the results. The template forest\_map.qpt is located in the exercise\_data\forestry\results\ folder. Load it using the  $Project \rightarrow Composer\ Manager...$  dialog.



Open the map composer and edit the final map to get a result you are happy with.

The map template you are using will give a map similar to this one:



Save your QGIS project for future references.

### 15.9.4 In Conclusion

Through this module you have seen how a basic forest inventory can be planned and presented with QGIS. Many more forest analysis are possible with the variety of tools that you can access, but hopefully this manual has given you a good starting point to explore how you could achieve the specific results you need.

15.9. Lesson: Karttaesitys 393

## Module: Database Concepts with PostgreSQL

Relational Databases are an important part of any GIS system. In this module, you'll learn about Relational Database Management System (RDBMS) concepts and you will use PostgreSQL to create a new database to store data, as well as learning about other typical RDBMS functions.

#### 16.1 Lesson: Introduction to Databases

Before using PostgreSQL, let's make sure of our ground by covering general database theory. You will not need to enter any of the example code; it's only there for illustration purposes.

The goal for this lesson: To understand fundamental database concepts.

#### 16.1.1 What is a Database?

A database consists of an organized collection of data for one or more uses, typically in digital form. - Wikipedia

A database management system (DBMS) consists of software that operates databases, providing storage, access, security, backup and other facilities. - *Wikipedia* 

#### **16.1.2 Tables**

In relational databases and flat file databases, a table is a set of data elements (values) that is organized using a model of vertical columns (which are identified by their name) and horizontal rows. A table has a specified number of columns, but can have any number of rows. Each row is identified by the values appearing in a particular column subset which has been identified as a candidate key. - *Wikipedia* 

In SQL databases a table is also known as a relation.

#### 16.1.3 Columns / Fields

A column is a set of data values of a particular simple type, one for each row of the table. The columns provide the structure according to which the rows are composed. The term field is often used interchangeably with column, although many consider it more correct to use field (or field value) to refer specifically to the single item that exists at the intersection between one row and one column. - *Wikipedia* 

A column:

```
name
| Tim |
| Horst |
```

#### A field:

```
| Horst |
```

#### 16.1.4 Records

A record is the information stored in a table row. Each record will have a field for each of the columns in the table.

```
2 | Horst | 88 <-- one record
```

#### 16.1.5 Datatypes

Datatypes restrict the kind of information that can be stored in a column. - Tim and Horst

There are many kinds of datatypes. Let's focus on the most common:

- String to store free-form text data
- Integer to store whole numbers
- Real to store decimal numbers
- Date to store Horst's birthday so no one forgets
- Boolean to store simple true/false values

You can tell the database to allow you to also store nothing in a field. If there is nothing in a field, then the field content is referred to as a 'null' value:

```
insert into person (age) values (40);
select * from person;
Result:
id | name | age
1 | Tim | 20
2 | Horst | 88
         | 40 <-- null for name
(3 rows)
```

There are many more datatypes you can use - check the PostgreSQL manual!

#### 16.1.6 Modelling an Address Database

Let's use a simple case study to see how a database is constructed. We want to create an address database.



Write down the properties which make up a simple address and which we would want to store in our database.

Check your results

#### **Address Structure**

The properties that describe an address are the columns. The type of information stored in each column is its datatype. In the next section we will analyse our conceptual address table to see how we can make it better!

#### 16.1.7 Database Theory

The process of creating a database involves creating a model of the real world; taking real world concepts and representing them in the database as entities.

#### 16.1.8 Normalisation

One of the main ideas in a database is to avoid data duplication / redundancy. The process of removing redundancy from a database is called Normalisation.

Normalization is a systematic way of ensuring that a database structure is suitable for general-purpose querying and free of certain undesirable characteristics - insertion, update, and deletion anomalies - that could lead to a loss of data integrity. - *Wikipedia* 

There are different kinds of normalisation 'forms'.

Let's take a look at a simple example:

Table "public.people"

| Column    | Туре   | Modifiers  |
|-----------|--|--|
| id        | integer  | not null default<br>  nextval('people_id_seq'::regclass) |
| address   | character varying(50)<br>character varying(200)<br>character varying | not null   |
| "people_p | key" <b>PRIMARY KEY,</b> btree (i                                    | id)  |

#### select \* from people;

| id | '     | name   |   |   | address   |  | pho | one_n | 0 |
|----|-------|--------|---|---|---|--|-----|-------|---|
|    | Tim   | Sutton | ĺ | 3 | Buirski Plein, Swellendam<br>Avenue du Roix, Geneva |  |     |       |   |
| (2 | rows) |        |   |   |   |  |     |       |   |

Imagine you have many friends with the same street name or city. Every time this data is duplicated, it consumes space. Worse still, if a city name changes, you have to do a lot of work to update your database.

# 16.1.9 Try Yourself

Redesign the theoretical *people* table above to reduce duplication and to normalise the data structure.

You can read more about database normalisation here

Check your results

#### 16.1.10 Indexes

A database index is a data structure that improves the speed of data retrieval operations on a database table. - Wikipedia

Imagine you are reading a textbook and looking for the explanation of a concept - and the textbook has no index! You will have to start reading at one cover and work your way through the entire book until you find the information you need. The index at the back of a book helps you to jump quickly to the page with the relevant information:

```
create index person_name_idx on people (name);
```

Now searches on name will be faster:

```
Table "public.people"
```

| Column   | <b>Type</b>   | Modifiers  |
|----------|---|--|
| id       | integer   | not null default<br>  nextval('people_id_seq'::regclass) |
|          | <pre>  character varying(50)   character varying(200)   character varying</pre> | <br>  not null<br>                                       |
| Indexes: |   |  |
| 1 1 —1   | key" <b>PRIMARY KEY,</b> btree (ame_idx" btree (name)                           | id)  |

### 16.1.11 Sequences

A sequence is a unique number generator. It is normally used to create a unique identifier for a column in a table. In this example, id is a sequence - the number is incremented each time a record is added to the table:

#### 16.1.12 Entity Relationship Diagramming

In a normalised database, you typically have many relations (tables). The entity-relationship diagram (ER Diagram) is used to design the logical dependencies between the relations. Consider our non-normalised *people* table from earlier in the lesson:

```
select * from people;
```

With a little work we can split it into two tables, removing the need to repeat the street name for individuals who live in the same street:

```
select * from streets;

id | name
---+----
1 | Plein Street
(1 row)
```

and:

```
select * from people;
```

We can then link the two tables using the 'keys' streets.id and people.streets\_id.

If we draw an ER Diagram for these two tables it would look something like this:



The ER Diagram helps us to express 'one to many' relationships. In this case the arrow symbol show that one street can have many people living on it.



Our *people* model still has some normalisation issues - try to see if you can normalise it further and show your thoughts by means of an ER Diagram.

Check your results

#### 16.1.13 Constraints, Primary Keys and Foreign Keys

A database constraint is used to ensure that data in a relation matches the modeller's view of how that data should be stored. For example a constraint on your postal code could ensure that the number falls between 1000 and

A Primary key is one or more field values that make a record unique. Usually the primary key is called id and is a sequence.

A Foreign key is used to refer to a unique record on another table (using that other table's primary key).

In ER Diagramming, the linkage between tables is normally based on Foreign keys linking to Primary keys.

If we look at our people example, the table definition shows that the street column is a foreign key that references the primary key on the streets table:

Table "public.people"

| Column                   | Туре                           | Modifiers  |  |  |  |
|--------------------------|--------------------------------|--|--|--|--|
|                          | integer                        | not null default<br>  nextval('people_id_seq'::regclass) |  |  |  |
| name                     | character varying(50)          |  |  |  |  |
| house_no                 | integer                        | not null   |  |  |  |
| street_id                | integer                        | not null   |  |  |  |
| phone_no                 | character varying              |  |  |  |  |
| Indexes:                 |                                |  |  |  |  |
| "people_pkey             | " <b>PRIMARY KEY,</b> btree (i | d)   |  |  |  |
| Foreign-key constraints: |                                |  |  |  |  |
| "people_stre             | eet_id_fkey" FOREIGN KEY       | (street_id) REFERENCES streets(id)                       |  |  |  |

#### 16.1.14 Transactions

When adding, changing, or deleting data in a database, it is always important that the database is left in a good state if something goes wrong. Most databases provide a feature called transaction support. Transactions allow you to create a rollback position that you can return to if your modifications to the database did not run as planned.

Take a scenario where you have an accounting system. You need to transfer funds from one account and add them to another. The sequence of steps would go like this:

- remove R20 from Joe
- · add R20 to Anne

If something goes wrong during the process (e.g. power failure), the transaction will be rolled back.

#### 16.1.15 In Conclusion

Databases allow you to manage data in a structured way using simple code structures.

#### 16.1.16 What's Next?

Now that we've looked at how databases work in theory, let's create a new database to implement the theory we've covered.

## 16.2 Lesson: Implementing the Data Model

Now that we've covered all the theory, let's create a new database. This database will be used for our exercises for the lessons that will follow afterwards.

The goal for this lesson: To install the required software and use it to implement our example database.

#### 16.2.1 Install PostgreSQL

**Muista:** Although outside the scope of this document, Mac users can install PostgreSQL using Homebrew. Windows users can use the graphical installer located here: http://www.postgresql.org/download/windows/. Please note that the documentation will assume users are running QGIS under Ubuntu.

#### Under Ubuntu:

```
sudo apt-get install postgresql-9.1
```

#### You should get a message like this:

```
[sudo] password for qgis:
Reading package lists... Done
Building dependency tree
Reading state information... Done
The following extra packages will be installed:
postgresql-client-9.1 postgresql-client-common postgresql-common
Suggested packages:
oidentd ident-server postgresql-doc-9.1
The following NEW packages will be installed:
postgresql-9.1 postgresql-client-9.1 postgresql-client-common postgresql-common
0 upgraded, 4 newly installed, 0 to remove and 5 not upgraded.
Need to get 5,012kB of archives.
After this operation, 19.0MB of additional disk space will be used.
Do you want to continue [Y/n]?
```

Press Y and Enter and wait for the download and installation to finish.

#### 16.2.2 Help

PostgreSQL has very good online documentation.

#### 16.2.3 Create a database user

Under Ubuntu:

After the installation is complete, run this command to become the postgres user and then create a new database user:

```
sudo su - postgres
```

Type in your normal log in password when prompted (you need to have sudo rights).

Now, at the postgres user's bash prompt, create the database user. Make sure the user name matches your unix login name: it will make your life much easier, as postgres will automatically authenticate you when you are logged in as that user:

```
createuser -d -E -i -l -P -r -s qgis
```

Enter a password when prompted. You should use a different password to your login password.

What do those options mean?

Now you should leave the postgres user's bash shell environment by typing:

exit

#### 16.2.4 Verify the new account

```
psql -1
```

Should return something like this:

|           |   |          |    |      |    | Collation  |    |            | 1  |
|-----------|---|----------|----|------|----|------------|----|------------|----|
|           | + |          | +- |      | +- |            | +- |            | -+ |
| postgres  |   | postgres |    | UTF8 |    | en_ZA.utf8 |    | en_ZA.utf8 |    |
| template0 |   | postgres |    | UTF8 |    | en_ZA.utf8 |    | en_ZA.utf8 |    |
| template1 |   | postgres |    | UTF8 |    | en_ZA.utf8 |    | en_ZA.utf8 |    |
| (3 rows)  |   |          |    |      |    |            |    |            |    |

Type q to exit.

#### 16.2.5 Create a database

The createdb command is used to create a new database. It should be run from the bash shell prompt:

```
createdb address -0 qgis
```

You can verify the existence of your new database by using this command:

```
psql -1
```

Which should return something like this:

| Name      | Owner                | Encoding | Collation  | Ctype      | Access privileges                  |
|-----------|----------------------|----------|------------|------------|------------------------------------|
| address   | qgis<br>postares     | UTF8     | _          | en_ZA.utf8 | ,                                  |
| template0 | postgres<br>postgres | UTF8     | _          | en_ZA.utf8 |                                    |
| (4 rows)  | posegres             | 0110     | en_ZA.ucio | en_ZA.ucio | -c/postgles. postgles-cit/postgles |

Type q to exit.

#### 16.2.6 Starting a database shell session

You can connect to your database easily like this:

```
psql address
```

To exit out of the psql database shell, type:

/q

For help in using the shell, type:

\?

For help in using sql commands, type:

\help

To get help on a specific command, type (for example):

```
\help create table
```

See also the Psql cheat sheet - available online here.

#### 16.2.7 Make Tables in SQL

Let's start making some tables! We will use our ER Diagram as a guide. First, connect to the address db:

```
psql address
```

Then create a streets table:

```
create table streets (id serial not null primary key, name varchar(50));
```

serial and varchar are **data types**. serial tells PostgreSQL to start an integer sequence (auto-number) to populate the id automatically for every new record. varchar (50) tells PostgreSQL to create a character field of 50 characters in length.

You will notice that the command ends with a ; - all SQL commands should be terminated this way. When you press Enter, psql will report something like this:

```
NOTICE: CREATE TABLE will create implicit sequence "streets_id_seq" for serial column "streets.id"

NOTICE: CREATE TABLE / PRIMARY KEY will create implicit index "streets_pkey" for table "streets"

CREATE TABLE
```

That means your table was created successfully, with a primary key streets\_pkey using streets.id.

Note: If you hit return without entering a ;, then you will get a prompt like this: address-#. This is because PG is expecting you to enter more. Enter; to run your command.

To view your table schema, you can do this:

\d streets

Which should show something like this:

To view your table contents, you can do this:

```
select * from streets;
```

Which should show something like this:

```
id | name ---+----(0 rows)
```

As you can see, our table is currently empty.



Use the approach shown above to make a table called people:

Add fields such as phone number, home address, name, etc. (these aren't all valid names: change them to make them valid). Make sure you give the table an ID column with the same data-type as above.

Check your results

#### 16.2.8 Create Keys in SQL

The problem with our solution above is that the database doesn't know that people and streets have a logical relationship. To express this relationship, we have to define a foreign key that points to the primary key of the streets table.



There are two ways to do this:

- Add the key after the table has been created
- · Define the key at time of table creation

Our table has already been created, so let's do it the first way:

```
alter table people
add constraint people_streets_fk foreign key (street_id) references streets(id);
```

That tells the people table that its street\_id fields must match a valid street id from the streets table.

The more usual way to create a constraint is to do it when you create the table:

After adding the constraint, our table schema looks like this now:

```
Table "public.people"
```

| Column      | Туре                           | Modifiers  |
|-------------|--------------------------------|--|
|             | integer                        | not null default<br>  nextval('people_id_seq'::regclass) |
| name        | character varying(50)          |  |
| house_no    | integer                        | not null   |
| street_id   | integer                        | not null   |
| phone_no    | character varying              |  |
| Indexes:    |                                |  |
| "people_pk  | ey" <b>PRIMARY KEY</b> , btree | (id)   |
| Foreign-key | constraints:                   |  |
| "people_st  | reets_fk" FOREIGN KEY (        | id) <b>REFERENCES</b> streets(id)                        |

#### 16.2.9 Create Indexes in SQL

We want lightning fast searches on peoples names. To provide for this, we can create an index on the name column of our people table:

```
create index people_name_idx on people(name);
\d people
```

Which results in:

Table "public.people"

```
Column
                  Type
                              Modifiers
 id | integer
                              | not null default nextval
                              ('people_id_seg'::regclass)
name | character varying (50) |
house_no | integer
                              | not null
 street_id | integer
                              | not null
phone_no | character varying
Indexes:
 "people_pkey" PRIMARY KEY, btree (id)
 "people_name_idx" btree (name) <-- new index added!
Foreign-key constraints:
 "people_streets_fk" FOREIGN KEY (id) REFERENCES streets(id)
```

#### 16.2.10 Dropping Tables in SQL

If you want to get rid of a table you can use the drop command:

```
drop table streets;
```

Muista: In our current example, the above command would not work. Why not? See why

If you used the same drop table command on the *people* table, it would be successful:

```
drop table people;
```

**Muista:** If you actually did enter that command and dropped the people table, now would be a good time to rebuild it, as you will need it in the next exercises.

#### 16.2.11 A word on pgAdmin III

We are showing you the SQL commands from the *psql* prompt because it's a very useful way to learn about databases. However, there are quicker and easier ways to do a lot of what we are showing you. Install pgAdmin III and you can create, drop, alter etc tables using 'point and click' operations in a GUI.

Under Ubuntu, you can install it like this:

```
sudo apt-get install pgadmin3
```

pgAdmin III will be covered in more detail in another module.

#### 16.2.12 In Conclusion

You have now seen how to create a brand new database, starting completely from scratch.

#### 16.2.13 What's Next?

Next you'll learn how to use the DBMS to add new data.

## 16.3 Lesson: Adding Data to the Model

The models we've created will now need to be populated with the data they're intended to contain.

The goal for this lesson: To learn how to insert new data into the database models.

#### 16.3.1 Insert statement

How do you add data to a table? The sql INSERT statement provides the functionality for this:

```
insert into streets (name) values ('High street');
```

A couple of things to note:

- After the table name (streets), you list the column names that you will be populating (in this case only the name column).
- After the values keyword, place the list of field values.
- Strings should be quoted using single quotes.
- Note that we did not insert a value for the id column; this is because it is a sequence and will be autogenerated.
- If you do manually set the id, you may cause serious problems with the integrity of your database.

You should see INSERT 0 1 if it is successful.

You can see the result of your insert action by selecting all the data in the table:



Use the INSERT command to add a new street to the streets table.

Check your results

#### 16.3.2 Sequencing Data Addition According to Constraints

# 16.3.3 Try Yourself

Try to add a person object to the people table with the following details:

Name: Joe Smith House Number: 55 Street: Main Street Phone: 072 882 33 21

Muista: Recall that in this example, we defined phone numbers as strings, not integers.

At this point, you should have an error report if you try to do this without first creating a record for Main Street in the streets table.

You should have also noticed that:

- You can't add the street using its name
- You can't add a street using a street id before first creating the street record on the streets table

Remember that our two tables are linked via a Primary/Foreign Key pair. This means that no valid person can be created without there also being a valid corresponding street record.

Using the above knowledge, add the new person to the database.

Check your results

#### 16.3.4 Select data

We have already shown you the syntax for selecting records. Let's look at a few more examples:

```
select name from streets;
select * from streets;
select * from streets where name='Main Road';
```

In later sessions we will go into more detail on how to select and filter data.

#### 16.3.5 Update data

What if you want to make a change to some existing data? For example, a street name is changed:

```
update streets set name='New Main Road' where name='Main Road';
```

Be very careful using such update statements - if more than one record matches your WHERE clause, they will all be updated!

A better solution is to use the primary key of the table to reference the record to be changed:

```
update streets set name='New Main Road' where id=2;
It should return UPDATE 1.
```

Muista: the WHERE statement criteria are case sensitive Main Road is not the same as Main road

#### 16.3.6 Delete Data

In order to delete an object from a table, use the DELETE command:

## 16.3.7 Try Yourself

Use the skills you have learned to add some new friends to your database:

| name         | 1  | house_no |   | street_i | d |   | ph  | none_ | _no |    |
|--------------|----|----------|---|----------|---|---|-----|-------|-----|----|
|              | -+ |          | + |          |   | - |     |       |     |    |
| Joe Bloggs   |    | 3        |   |          | 2 |   | 072 | 887   | 23  | 45 |
| Jane Smith   |    | 55       |   |          | 3 |   | 072 | 837   | 33  | 35 |
| Roger Jones  |    | 33       |   |          | 1 |   | 072 | 832   | 31  | 38 |
| Sally Norman |    | 83       |   |          | 1 |   | 072 | 932   | 31  | 32 |

#### 16.3.8 In Conclusion

Now you know how to add new data to the existing models you created previously. Remember that if you want to add new kinds of data, you may want to modify and/or create new models to contain that data.

#### **16.3.9 What's Next?**

Now that you've added some data, you'll learn how to use queries to access this data in various ways.

#### 16.4 Lesson: Queries

When you write a SELECT ... command it is commonly known as a query - you are interrogating the database for information.

16.4. Lesson: Queries 407

**The goal of this lesson:** To learn how to create queries that will return useful information.

**Muista:** If you did not do so in the previous lesson, add the following people objects to your people table. If you receive any errors related to foreign key constraints, you will need to add the 'Main Road' object to your streets table first

#### 16.4.1 Ordering Results

Let's retrieve a list of people ordered by their house numbers:

```
select name, house_no from people order by house_no;
```

#### Result:

| name         |  | house_no |
|--------------|--|----------|
| Joe Bloggs   |  | 3        |
| Roger Jones  |  | 33       |
| Jane Smith   |  | 55       |
| Sally Norman |  | 83       |
| (4 rows)     |  |          |

You can sort the results by the values of more than one column:

```
select name, house_no from people order by name, house_no;
```

#### Result:

| name         |  | house_no |
|--------------|--|----------|
| Jane Smith   |  | 55       |
| Joe Bloggs   |  | 3        |
| Roger Jones  |  | 33       |
| Sally Norman |  | 83       |
| (4 rows)     |  |          |

#### 16.4.2 Filtering

Often you won't want to see every single record in the database - especially if there are thousands of records and you are only interested in seeing one or two.

Here is an example of a numerical filter which only returns objects whose house\_no is less than 50:

```
select name, house_no from people where house_no < 50;</pre>
```

```
name | house_no
------
Joe Bloggs | 3
Roger Jones | 33
(2 rows)
```

You can combine filters (defined using the WHERE clause) with sorting (defined using the ORDER BY clause):

select name, house\_no from people where house\_no < 50 order by house\_no;</pre>

You can also filter based on text data:

```
select name, house_no from people where name like '%s%';
```

Here we used the LIKE clause to find all names with an s in them. You'll notice that this query is case-sensitive, so the Sally Norman entry has not been returned.

If you want to search for a string of letters regardless of case, you can do a case in-sensitive search using the ILIKE clause:

```
select name, house_no from people where name ilike '%r%';
```

| name         |  | house_no |
|--------------|--|----------|
| Roger Jones  |  | 33       |
| Sally Norman |  | 83       |
| (2 rows)     |  |          |

That query returned every **people** object with an r or R in their name.

#### 16.4.3 Liitokset

What if you want to see the person's details and their street's name instead of the ID? In order to do that, you need to join the two tables together in a single query. Lets look at an example:

```
select people.name, house_no, streets.name
from people, streets
where people.street_id=streets.id;
```

**Muista:** With joins, you will always state the two tables the information is coming from, in this case people and streets. You also need to specify which two keys must match (foreign key & primary key). If you don't specify that, you will get a list of all possible combinations of people and streets, but no way to know who actually lives on which street!

Here is what the correct output will look like:

We will revisit joins as we create more complex queries later. Just remember they provide a simple way to combine the information from two or more tables.

#### 16.4.4 Sub-Select

Sub-selections allow you to select objects from one table based on the data from another table which is linked via a foreign key relationship. In our case, we want to find people who live on a specific street.

First, let's do a little tweaking of our data:

```
insert into streets (name) values('QGIS Road');
insert into streets (name) values('OGR Corner');
insert into streets (name) values('Goodle Square');
update people set street_id = 2 where id=2;
update people set street_id = 3 where id=3;
```

Let's take a quick look at our data after those changes: we can reuse our query from the previous section:

```
select people.name, house_no, streets.name
from people, streets
where people.street_id=streets.id;
```

#### Result:

Now let's show you a sub-selection on this data. We want to show only people who live in  $street_id$  number 1.

Although this is a very simple example and unnecessary with our small data-sets, it illustrates how useful and important sub-selections can be when querying large and complex data-sets.

#### 16.4.5 Aggregate Queries

One of the powerful features of a database is its ability to summarise the data in its tables. These summaries are called aggregate queries. Here is a typical example which tells us how many people objects are in our people table:

```
select count(*) from people;
Result:
   count
-----
```

(2 rows)

```
4
(1 row)
```

If we want the counts to be summarised by street name we can do this:

```
select count(name), street_id
from people
group by street_id;
```

#### Result:

| count   | street_id  |  |
|---------|------------|--|
| 2.      | <i>†</i> 1 |  |
| 1       | 3          |  |
| 1       | 2          |  |
| (3 rows | )          |  |

Muista: Because we have not used an ORDER BY clause, the order of your results may not match what is shown here



Summarise the people by street name and show the actual street names instead of the street\_ids.

Check your results

#### 16.4.6 In Conclusion

You've seen how to use queries to return the data in your database in a way that allows you to extract useful information from it.

#### 16.4.7 What's Next?

Next you'll see how to create views from the queries that you've written.

#### 16.5 Lesson: Views

When you write a query, you need to spend a lot of time and effort formulating it. With views, you can save the definition of an SQL query in a reusable 'virtual table'.

The goal for this lesson: To save a query as a view.

#### 16.5.1 Creating a View

You can treat a view just like a table, but its data is sourced from a query. Let's make a simple view based on the above:

```
create view roads_count_v as
    select count(people.name), streets.name
    from people, streets where people.street_id=streets.id
    group by people.street_id, streets.name;
```

16.5. Lesson: Views 411

As you can see the only change is the create view roads\_count\_v as part at the beginning. We can now select data from that view:

#### 16.5.2 Modifying a View

A view is not fixed, and it contains no 'real data'. This means you can easily change it without impacting on any data in your database:

```
CREATE OR REPLACE VIEW roads_count_v AS
   SELECT count(people.name), streets.name
   FROM people, streets WHERE people.street_id=streets.id
   GROUP BY people.street_id, streets.name
   ORDER BY streets.name;
```

(This example also shows the best practice convention of using UPPER CASE for all SQL keywords.)

You will see that we have added an ORDER BY clause so that our view rows are nicely sorted:

### 16.5.3 Dropping a View

If you no longer need a view, you can delete it like this:

```
drop view roads_count_v;
```

#### 16.5.4 In Conclusion

Using views, you can save a query and access its results as if it were a table.

#### **16.5.5 What's Next?**

Sometimes, when changing data, you want your changes to have effects elsewhere in the database. The next lesson will show you how to do this.

#### 16.6 Lesson: Rules

Rules allow the "query tree" of an incoming query to be rewritten. One common usage is to implement views, including updatable view. - Wikipedia

The goal for this lesson: To learn how to create new rules for the database.

#### 16.6.1 Materialised Views (Rule based views)

Say you want to log every change of phone\_no in your people table in to a people\_log table. So you set up a new table:

```
create table people_log (name text, time timestamp default NOW());
```

In the next step, create a rule that logs every change of a phone\_no in the people table into the people\_log table:

```
create rule people_log as on update to people
  where NEW.phone_no <> OLD.phone_no
  do insert into people_log values (OLD.name);
```

To test that the rule works, let's modify a phone number:

```
update people set phone_no = '082 555 1234' where id = 2;
```

Check that the people table was updated correctly:

Now, thanks to the rule we created, the people\_log table will look like this:

**Muista:** The value of the time field will depend on the current date and time.

#### 16.6.2 In Conclusion

Rules allow you to automatically add or change data in your database to reflect changes in other parts of the database.

#### 16.6.3 What's Next?

The next module will introduce you to Spatial Database using PostGIS, which takes these database concepts and applies them to GIS data.

16.6. Lesson: Rules 413

## Module: Spatial Database Concepts with PostGIS

Spatial Databases allow the storage of the geometries of records inside a Database as well as providing functionality for querying and retrieving the records using these Geometries. In this module we will use PostGIS, an extension to PostgreSQL, to learn how to setup a spatial database, import data from shapefiles into the database and make use of the geographic functions that PostGIS offers.

While working through this section, you may want to keep a copy of the **PostGIS cheat sheet** available from Boston GIS user group. Another useful resource is the online PostGIS documentation.

There are also some more extensive tutorials on PostGIS and Spatial Databases available from Boundless Geo:

- Introduction to PostGIS
- Spatial Database Tips and Tricks

See also PostGIS online.

## 17.1 Lesson: PostGIS Setup

Setting up PostGIS functions will allow you to access spatial functions from within PostgreSQL.

The goal for this lesson: To install spatial functions and briefly demo their effects.

**Muista:** We will assume the use of PostGIS version 2.1 in this exercise. The installation and database configuration are different for older versions, but the rest of this material in this module will still work. Consult the documentation for your platform for help with installation and database configuration.

#### 17.1.1 Installing under Ubuntu

Postgis is easily installed from apt.

```
$ sudo apt-get install postgis
$ sudo apt-get install postgresql-9.1-postgis
```

Really, it's that easy...

**Muista:** Depending on which version of Ubuntu you are using, and which repositories you have configured, these commands will install PostGIS 1.5, or 2.x. You can find the version installed by issuing a select PostGIS\_full\_version(); query with psql or another tool.

To install the absolute latest version of PostGIS, you can use the following commands.

```
$ sudo apt-add-repository ppa:sharpie/for-science
$ sudo apt-add-repository ppa:sharpie/postgis-nightly
```

```
$ sudo apt-get update
$ sudo apt-get install postgresql-9.1-postgis-nightly
```

#### 17.1.2 Installing under Windows

Installing on Windows is a little more complicated, but still not hard. Note that you need to be online to install the postgis stack.

First Visit the download page.

Then follow this guide.

More information about installing on Windows can be found on the PostGIS website.

#### 17.1.3 Installing on Other Platforms

The PostGIS website download has information about installing on other platforms including macOS and on other linux distributions

#### 17.1.4 Configuring Databases to use PostGIS

Once PostGIS is installed, you will need to configure your database to use the extensions. If you have installed PostGIS version > 2.0, this is as simple as issuing the following command with psql using the address database from our previous exercise.

```
$ psql -d address -c "CREATE EXTENSION postgis;"
```

**Muista:** If you are using PostGIS 1.5 and a version of PostgreSQL lower than 9.1, you will need to follow a different set of steps in order to install the postgis extensions for your database. Please consult the PostGIS Documentation for instructions on how to do this. There are also some instructions in the previous version of this manual.

#### 17.1.5 Looking at the installed PostGIS functions

PostGIS can be thought of as a collection of in-database functions that extend the core capabilities of PostgreSQL so that it can deal with spatial data. By 'deal with', we mean store, retrieve, query and manipulate. In order to do this, a number of functions are installed into the database.

Our PostgreSQL address database is now geospatially enabled, thanks to PostGIS. We are going to delve a lot deeper into this in the coming sections, but let's give you a quick little taster. Let's say we want to create a point from text. First we use the psql command to find functions relating to point. If you are not already connected to the address database, do so now. Then run:

```
\df *point*
```

This is the command we're looking for: st\_pointfromtext. To page through the list, use the down arrow, then press q to quit back to the psql shell.

Try running this command:

Three things to note:

- We defined a point at position 1,1 (EPSG:4326 is assumed) using POINT (1 1),
- We ran an sql statement, but not on any table, just on data entered from the SQL prompt,
- The resulting row does not make much sense.

The resulting row is in the OGC format called 'Well Known Binary' (WKB). We will look at this format in detail in the next section.

To get the results back as text, we can do a quick scan through the function list for something that returns text:

```
\df *text
```

The query we're looking for now is st\_astext. Let's combine it with the previous query:

```
\textbf{select} \  \, \texttt{st\_astext} \, (\texttt{st\_pointfromtext} \, ('\, \texttt{POINT} \, (1\ 1)\, '\,)\,) \, ; \\
```

#### Result:

```
st_astext
POINT(1 1)
(1 row)
```

Here, we entered the string POINT(1,1), turned it into a point using st\_pointfromtext(), and turned it back into a human-readable form with st\_astext(), which gave us back our original string.

One last example before we really get into the detail of using PostGIS:

```
select st_astext(st_buffer(st_pointfromtext('POINT(1 1)'),1.0));
```

What did that do? It created a buffer of 1 degree around our point, and returned the result as text.

#### 17.1.6 Spatial Reference Systems

In addition to the PostGIS functions, the extension contains a collection of spatial reference system (SRS) definitions as defined by the European Petroleum Survey Group (EPSG). These are used during operations such as coordinate reference system (CRS) conversions.

| Modifiers

We can inspect these SRS definitions in our database as they are stored in normal database tables.

First, let's look at the schema of the table by entering the following command in the psql prompt:

```
\d spatial_ref_sys
```

The result should be this:

"spatial\_ref\_sys\_pkey" PRIMARY KEY, btree (srid)

You can use standard SQL queries (as we have learned from our introductory sections), to view and manipulate this table - though its not a good idea to update or delete any records unless you know what you are doing.

One SRID you may be interested in is EPSG:4326 - the geographic / lat lon reference system using the WGS 84 ellipsoid. Let's take a look at it:

```
select * from spatial_ref_sys where srid=4326;
```

#### Result:

The srtext is the projection definition in well known text (you may recognise this from .prj files in your shapefile collection).

#### 17.1.7 In Conclusion

You now have PostGIS functions installed in your copy of PostgreSQL. With this you'll be able to make use of PostGIS' extensive spatial functions.

#### 17.1.8 What's Next?

Next you'll learn how spatial features are represented in a database.

## 17.2 Lesson: Simple Feature Model

How can we store and represent geographic features in a database? In this lesson we'll cover one approach, the Simple Feature Model as defined by the OGC.


The goal for this lesson: To learn what the SFS Model is and how to use it.

#### 17.2.1 What is OGC

The Open Geospatial Consortium (OGC), an international voluntary consensus standards organization, originated in 1994. In the OGC, more than 370+ commercial, governmental, nonprofit and research organizations worldwide collaborate in an open consensus process encouraging development and implementation of standards for geospatial content and services, GIS data processing and data sharing. - *Wikipedia* 

#### 17.2.2 What is the SFS Model

The Simple Feature for SQL (SFS) Model is a *non-topological* way to store geospatial data in a database and defines functions for accessing, operating, and constructing these data.



The model defines geospatial data from Point, Linestring, and Polygon types (and aggregations of them to Multi objects).

For further information, have a look at the OGC Simple Feature for SQL standard.

#### 17.2.3 Add a geometry field to table

Let's add a point field to our people table:

```
alter table people add column the geom geometry;
```

#### 17.2.4 Add a constraint based on geometry type

You will notice that the geometry field type does not implicitly specify what *type* of geometry for the field - for that we need a constraint:

This adds a constraint to the table so that it will only accept a point geometry or a null value.

# 17.2.5 Try Yourself

Create a new table called cities and give it some appropriate columns, including a geometry field for storing polygons (the city boundaries). Make sure it has a constraint enforcing geometries to be polygons.

Check your results

#### 17.2.6 Populate geometry columns table

At this point you should also add an entry into the geometry\_columns table:

```
insert into geometry_columns values
('','public','people','the_geom',2,4326,'POINT');
```

Why? geometry\_columns is used by certain applications to be aware of which tables in the database contain geometry data.

Muista: If the above INSERT statement causes an error, run this query first:

```
select * from geometry_columns;
```

If the column f\_table\_name contains the value people, then this table has already been registered and you don't need to do anything more.

The value 2 refers to the number of dimensions; in this case, two: **x** and **y**.

The value 4326 refers to the projection we are using; in this case, WGS 84, which is referred to by the number 4326 (refer to the earlier discussion about the EPSG).



Add an appropriate *geometry\_columns* entry for your new cities layer

Check your results

#### 17.2.7 Add geometry record to table using SQL

Now that our tables are geo-enabled, we can store geometries in them:

**Muista:** In the new entry above, you will need to specify which projection (SRID) you want to use. This is because you entered the geometry of the new point using a plain string of text, which does not automatically add the correct projection information. Obviously, the new point needs to use the same SRID as the data-set it is being added to, so you need to specify it.


If at this point you were using a graphical interface, for example, specifying the projection for each point would be automatic. In other words, you usually won't need to worry about using the correct projection for every point you want to add if you've already specified it for that data-set, as we did earlier.

Now is probably a good time to open QGIS and try to view your people table. Also, we should try editing / adding / deleting records and then performing select queries in the database to see how the data has changed.


To load a PostGIS layer in QGIS, use the  $Layer \rightarrow Add$  PostGIS Layers menu option or toolbar button:



This will open the dialog:



Click on the *New* button to open this dialog:



## Then define a new connection, e.g.:

Name: myPG
Service:

Host: localhost Port: 5432 Database: address

User: Password:

To see whether QGIS has found the address database and that your username and password are correct, click *Test Connect*. If it works, check the boxes next to *Save Username* and *Save Password*. Then click *OK* to create this connection.

Back in the Add PostGIS Layers dialog, click Connect and add layers to your project as usual.



Formulate a query that shows a person's name, street name and position (from the the\_geom column) as plain text.

Check your results

#### 17.2.8 In Conclusion

You have seen how to add spatial objects to your database and view them in GIS software.

#### 17.2.9 What's Next?

Next you'll see how to import data into, and export data from, your database.

## 17.3 Lesson: Import and Export

Of course, a database with no easy way to migrate data into it and out of it would not be of much use. Fortunately, there are a number of tools that will let you easily move data into and out of PostGIS.

#### 17.3.1 shp2pgsql

shp2pgsql is a commandline tool to import ESRI shapefiles to the database. Under Unix, you can use the following command for importing a new PostGIS table:

```
shp2pgsql -s <SRID> -c -D -I <path to shapefile> <schema>. | \
   psql -d <databasename> -h <hostname> -U <username>
```

Under Windows, you have to perform the import process in two steps:

```
shp2pgsql -s <SRID> -c -D -I <path to shapefile> <schema>.  > import.sql \\psql psql -d <databasename> -h <hostname> -U <username> -f import.sql
```

You may encounter this error:

```
ERROR: operator class "gist_geometry_ops" does not exist for access method
"gist"
```

This is a known issue regarding the creation *in situ* of a spatial index for the data you're importing. To avoid the error, exclude the -I parameter. This will mean that no spatial index is being created directly, and you'll need to create it in the database after the data have been imported. (The creation of a spatial index will be covered in the next lesson.)

#### 17.3.2 pgsql2shp

pgsql2shp is a commandline tool to export PostGIS Tables, Views or SQL select queries. To do this under Unix:

```
pgsql2shp -f <path to new shapefile> -g <geometry column name> \
   -h <hostname> -U <username> <databasename>
```

To export the data using a query:

```
pgsql2shp -f <path to new shapefile> -g <geometry column name> \
    -h <hostname> -U <username> "<query>"
```

#### 17.3.3 ogr2ogr

ogr2ogr is a very powerful tool to convert data into and from postgis to many data formats. ogr2ogr is part of the GDAL/OGR Software and has to be installed separately. To export a table from PostGIS to GML, you can use this command:

```
ogr2ogr -f GML export.gml PG:'dbname=<databasename> user=<username>
    host=<hostname>' <Name of PostGIS-Table>
```

#### 17.3.4 Tietokannan hallinta

You may have noticed another option in the *Database* menu labeled *DB Manager*. This is a tool that provides a unified interface for interacting with spatial databases including PostGIS. It also allows you to import and export from databases to other formats. Since the next module is largely devoted to using this tool, we will only briefly mention it here.

#### 17.3.5 In Conclusion

Importing and exporting data to and from the database can be done in many various ways. Especially when using disparate data sources, you will probably use these functions (or others like them) on a regular basis.

#### 17.3.6 What's Next?

Next we'll look at how to query the data we've created before.

## 17.4 Lesson: Spatial Queries

Spatial queries are no different from other database queries. You can use the geometry column like any other database column. With the installation of PostGIS in our database, we have additional functions to query our database.

The goal for this lesson: To see how spatial functions are implemented similarly to "normal" non-spatial functions.

#### 17.4.1 Spatial Operators

When you want to know which points are within a distance of 2 degrees to a point(X,Y) you can do this with:

**Muista:** the geom value above was truncated for space on this page. If you want to see the point in human-readable coordinates, try something similar to what you did in the section "View a point as WKT", above.

How do we know that the query above returns all the points within 2 degrees? Why not 2 meters? Or any other unit, for that matter?

Check your results

#### 17.4.2 Spatial Indexes

We also can define spatial indexes. A spatial index makes your spatial queries much faster. To create a spatial index on the geometry column use:

```
CREATE INDEX people_geo_idx
  ON people
  USING gist
  (the_geom);
```

#### Result:

```
Table "public.people"
```

```
Column
                     Type
                                                    Modifiers
 id
           | integer
                                    | not null default
                                    | nextval('people_id_seq'::regclass)
 name
           | character varying(50) |
 house_no | integer
                                    | not null
 street_id | integer
                                    | not null
 phone_no | character varying
 the_geom | geometry
Indexes:
  "people_pkey" PRIMARY KEY, btree (id)
  "people_geo_idx" gist (the_geom) <-- new spatial key added
  "people_name_idx" btree (name)
Check constraints:
 "people_geom_point_chk" CHECK (st_geometrytype(the_geom) = 'ST_Point'::text
 OR the_geom IS NULL)
Foreign-key constraints:
  "people_street_id_fkey" FOREIGN KEY (street_id) REFERENCES streets(id)
```

## 17.4.3 Try Yourself

Modify the cities table so its geometry column is spatially indexed.

Check your results

#### 17.4.4 PostGIS Spatial Functions Demo

In order to demo PostGIS spatial functions, we'll create a new database containing some (fictional) data.

To start, create a new database (exit the psql shell first):

```
createdb postgis_demo
```

Remember to install the postgis extensions:

```
psql -d postgis_demo -c "CREATE EXTENSION postgis;"
```

Next, import the data provided in the <code>exercise\_data/postgis/</code> directory. Refer back to the previous lesson for instructions, but remember that you'll need to create a new PostGIS connection to the new database. You can import from the terminal or via DB Manager. Import the files into the following database tables:

- points.shp into building
- lines.shp into road
- polygons.shp into region

Load these three database layers into QGIS via the *Add PostGIS Layers* dialog, as usual. When you open their attribute tables, you'll note that they have both an id field and a gid field created by the PostGIS import.

Now that the tables are imported, we can use PostGIS to query the data. Go back to your terminal (command line) and enter the psql prompt by running:

```
psql postgis_demo
```

We'll demo some of these select statements by creating views from them, so that you can open them in QGIS and see the results.

#### Select by location

Get all the buildings in the KwaZulu region:

```
SELECT a.id, a.name, st_astext(a.the_geom) as point
FROM building a, region b
WHERE st_within(a.the_geom, b.the_geom)
AND b.name = 'KwaZulu';
```


#### Result:

| id   name | point                  |                   |
|-----------|------------------------|-------------------|
| +         | +                      |                   |
| 30   York | POINT(1622345.23785063 | 6940490.65844485) |
| 33   York | POINT(1622495.65620524 | 6940403.87862489) |
| 35   York | POINT(1622403.09106394 | 6940212.96302097) |
| 36   York | POINT(1622287.38463732 | 6940357.59605424) |
| 40   York | POINT(1621888.19746548 | 6940508.01440885) |
| (5 rows)  |                        |                   |

Or, if we create a view from it:

```
CREATE VIEW vw_select_location AS
SELECT a.gid, a.name, a.the_geom
FROM building a, region b
WHERE st_within(a.the_geom, b.the_geom)
AND b.name = 'KwaZulu';
```

Add the view as a layer and view it in QGIS:




### Select neighbors

Show a list of all the names of regions adjoining the Hokkaido region:

WHERE TOUCHES (a.the\_geom, b.the\_geom)

AND a.name = 'Hokkaido';

In QGIS:




Note the missing region (Queensland). This may be due to a topology error. Artifacts such as this can alert us to potential problems in the data. To solve this enigma without getting caught up in the anomalies the data may have, we could use a buffer intersect instead:

```
CREATE VIEW vw_hokkaido_buffer AS
SELECT gid, ST_BUFFER(the_geom, 100) as the_geom
FROM region
WHERE name = 'Hokkaido';
```

This creates a buffer of 100 meters around the region Hokkaido.

The darker area is the buffer:




Select using the buffer:

```
CREATE VIEW vw_hokkaido_buffer_select AS
SELECT b.gid, b.name, b.the_geom
FROM
(
    SELECT * FROM
    vw_hokkaido_buffer
) a,
    region b
WHERE ST_INTERSECTS(a.the_geom, b.the_geom)
AND b.name != 'Hokkaido';
```

In this query, the original buffer view is used as any other table would be. It is given the alias a, and its geometry field, a.the\_geom, is used to select any polygon in the region table (alias b) that intersects it. However, Hokkaido itself is excluded from this select statement, because we don't want it; we only want the regions adjoining it.


In QGIS:



It is also possible to select all objects within a given distance, without the extra step of creating a buffer:

```
CREATE VIEW vw_hokkaido_distance_select AS
SELECT b.gid, b.name, b.the_geom
FROM region a, region b
WHERE ST_DISTANCE (a.the_geom, b.the_geom) < 100
AND a.name = 'Hokkaido'
AND b.name != 'Hokkaido';</pre>
```

This achieves the same result, without need for the interim buffer step:



#### Select unique values

Show a list of unique town names for all buildings in the Queensland region:

```
SELECT DISTINCT a.name
 FROM building a, region b
    WHERE st_within(a.the_geom, b.the_geom)
    AND b.name = 'Queensland';
Result:
 name
Beijing
Berlin
Atlanta
(3 rows)
Further examples ...
CREATE VIEW vw_shortestline AS
  SELECT b.gid AS gid,
        ST_ASTEXT(ST_SHORTESTLINE(a.the_geom, b.the_geom)) as text,
        ST_SHORTESTLINE(a.the_geom, b.the_geom) AS the_geom
    FROM road a, building b
      WHERE a.id=5 AND b.id=22;
CREATE VIEW vw_longestline AS
  SELECT b.gid AS gid,
         ST_ASTEXT(ST_LONGESTLINE(a.the_geom, b.the_geom)) as text,
         ST_LONGESTLINE(a.the_geom, b.the_geom) AS the_geom
    FROM road a, building b
      WHERE a.id=5 AND b.id=22;
CREATE VIEW vw_road_centroid AS
 SELECT a.gid as gid, ST_CENTROID(a.the_geom) as the_geom
   FROM road a
      WHERE a.id = 1;
CREATE VIEW vw_region_centroid AS
 SELECT a.gid as gid, ST_CENTROID(a.the_geom) as the_geom
   FROM region a
     WHERE a.name = 'Saskatchewan';
SELECT ST_PERIMETER(a.the_geom)
 FROM region a
   WHERE a.name='Queensland';
SELECT ST_AREA(a.the_geom)
 FROM region a
   WHERE a.name='Queensland';
CREATE VIEW vw_simplify AS
 SELECT gid, ST_Simplify(the_geom, 20) AS the_geom
   FROM road;
CREATE VIEW vw_simplify_more AS
  SELECT gid, ST_Simplify(the_geom, 50) AS the_geom
   FROM road;
CREATE VIEW vw_convex_hull AS
  SELECT
```

```
ROW_NUMBER() over (order by a.name) as id,
a.name as town,
ST_CONVEXHULL(ST_COLLECT(a.the_geom)) AS the_geom
FROM building a
GROUP BY a.name;
```

#### 17.4.5 In Conclusion

You have seen how to query spatial objects using the new database functions from PostGIS.

#### 17.4.6 What's Next?

Next we're going to investigate the structures of more complex geometries and how to create them using PostGIS.

# 17.5 Lesson: Geometry Construction

In this section we are going to delve a little deeper into how simple geometries are constructed in SQL. In reality, you will probably use a GIS like QGIS to create complex geometries using their digitising tools; however, understanding how they are formulated can be handy for writing queries and understanding how the database is assembled.

The goal of this lesson: To better understand how to create spatial entities directly in PostgreSQL/PostGIS.

## 17.5.1 Creating Linestrings

Going back to our address database, let's get our streets table matching the others; i.e., having a constraint on the geometry, an index and an entry in the geometry\_columns table.

# 17.5.2 Try Yourself

- Modify the streets table so that it has a geometry column of type ST\_LineString.
- Don't forget to do the accompanying update to the geometry columns table!
- Also add a constraint to prevent any geometries being added that are not LINESTRINGS or null.
- · Create a spatial index on the new geometry column

#### Check your results

Now let's insert a linestring into our streets table. In this case we will update an existing street record:

```
update streets
set the_geom = 'SRID=4326;LINESTRING(20 -33, 21 -34, 24 -33)'
where streets.id=2;
```

Take a look at the results in QGIS. (You may need to right-click on the streets layer in the 'Layers' panel, and choose 'Zoom to layer extent'.)

Now create some more streets entries - some in QGIS and some from the command line.

## 17.5.3 Creating Polygons

Creating polygons is just as easy. One thing to remember is that by definition, polygons have at least four vertices, with the last and first being co-located:

```
insert into cities (name, the_geom)
values ('Tokyo', 'SRID=4326;POLYGON((10 -10, 5 -32, 30 -27, 10 -10))');
```

**Muista:** A polygon requires double brackets around its coordinate list; this is to allow you to add complex polygons with multiple unconnected areas. For instance

If you followed this step, you can check what it did by loading the cities dataset into QGIS, opening its attribute table, and selecting the new entry. Note how the two new polygons behave like one polygon.

## 17.5.4 Exercise: Linking Cities to People

For this exercise you should do the following:

- Delete all data from your people table.
- Add a foreign key column to people that references the primary key of the cities table.
- Use QGIS to capture some cities.
- Use SQL to insert some new people records, ensuring that each has an associated street and city.

Your updated people schema should look something like this:


```
\d people
```

```
Table "public.people"
  Column | Type |
                                                         Modifiers
 id | integer
                                  | not null
                                  | default nextval('people_id_seq'::regclass)
 name | character varying(50) | house_no | integer | street_id | integer |
                                  | not null
                                 | not null
 phone_no | character varying |
 the_geom | geometry
 city id | integer
                                 | not null
  "people_pkey" PRIMARY KEY, btree (id)
  "people_name_idx" btree (name)
Check constraints:
  "people_geom_point_chk" CHECK (st_geometrytype(the_geom) =
                      'ST_Point'::text OR the_geom IS NULL)
Foreign-key constraints:
  "people_city_id_fkey" FOREIGN KEY (city_id) REFERENCES cities(id)
  "people_street_id_fkey" FOREIGN KEY (street_id) REFERENCES streets(id)
```

Check your results

#### 17.5.5 Looking at Our Schema

By now our schema should be looking like this:



# 17.5.6 Try Yourself

Create city boundaries by computing the minimum convex hull of all addresses for that city and computing a buffer around that area.

# 17.5.7 Access Sub-Objects

With the SFS-Model functions, you have a wide variety of options to access sub-objects of SFS Geometries. When you want to select the first vertex point of every polygon geometry in the table myPolygonTable, you have to do this in this way:

• Transform the polygon boundary to a linestring:

```
select st_boundary(geometry) from myPolygonTable;
```

• Select the first vertex point of the resultant linestring:

```
select st_startpoint(myGeometry)
from (
    select st_boundary(geometry) as myGeometry
    from myPolygonTable) as foo;
```


# 17.5.8 Data Processing

PostGIS supports all OGC SFS/MM standard conform functions. All these functions start with ST\_.


# 17.5.9 Clipping

To clip a subpart of your data you can use the ST\_INTERSECT () function. To avoid empty geometries, use:

```
where not st_isempty(st_intersection(a.the_geom, b.the_geom))
```




select st\_intersection(a.the\_geom, b.the\_geom), b.\*
from clip as a, road\_lines as b
where not st\_isempty(st\_intersection(st\_setsrid(a.the\_geom, 32734),
 b.the\_geom));



# 17.5.10 Building Geometries from Other Geometries


From a given point table, you want to generate a linestring. The order of the points is defined by their id. Another ordering method could be a timestamp, such as the one you get when you capture waypoints with a GPS receiver.



To create a linestring from a new point layer called 'points', you can run the following command:

```
select ST_LineFromMultiPoint(st_collect(the_geom)), 1 as id
from (
   select the_geom
   from points
   order by id
) as foo;
```

To see how it works without creating a new layer, you could also run this command on the 'people' layer, although of course it would make little real-world sense to do this.



# 17.5.11 Geometry Cleaning

You can get more information for this topic in this blog entry.

#### 17.5.12 Differences between tables

To detect the difference between two tables with the same structure, you can use the PostgreSQL keyword EXCEPT:

```
select * from table_a
except
select * from table_b;
```

As the result, you will get all records from table\_a which are not stored in table\_b.

# 17.5.13 Tablespaces

You can define where postgres should store its data on disk by creating tablespaces:

```
CREATE TABLESPACE homespace LOCATION '/home/pg';
```

When you create a database, you can then specify which tablespace to use e.g.:

createdb --tablespace=homespace t4a

# 17.5.14 In Conclusion

You've learned how to create more complex geometries using PostGIS statements. Keep in mind that this is mostly to improve your tacit knowledge when working with geo-enabled databases through a GIS frontend. You usually won't need to actually enter these statements manually, but having a general idea of their structure will help you when using a GIS, especially if you encounter errors that would otherwise seem cryptic.

# The QGIS processing guide

This module contributed by Victor Olaya and Paolo Cavallini.

Contents:

#### 18.1 Introduction

This guide describes how to use QGIS processing framework. It assumes no previous knowledge of the processign framework or any of the applications that it relies on. It assumes basic knowledge of QGIS. The chapters about scripting assume you have some basic knowledge of Python and maybe the QGIS Python API.

This guide is designed for self-study or to be used for running a processing workshop.

Examples in this guide use QGIS 2.0, with partial upgrades to 2.10. They might not work or not be available in versions other than that ones.

This guide is comprised of a set of small exercises of progressive complexity. If you have never used the processing framework, you should start from the very beginning. If you have some previous experience, feel free to skip lessons. They are more or less independent from each other, and each one introduces some new concept or some new element, which is indicated in the chapter title and the short introduction at the beginning of each chapter. That should make it easy to locate lessons dealing with a particular topic.

For a more systematic description of all the framework components and their usage, it is recommended to check the corresponding chapter in the QGIS manual. Use it as a support text along with this guide.

All the exercises in this guide use free data set that can be downloaded from the QGIS website. The zip file to download contains several folders corresponding to each one of the lessons in this guide. In each of them you will find a QGIS project file. Just open it and you will be ready to start the lesson.


Enjoy!

# 18.2 An important warning before starting

Just like the manual of a word processor doesn't teach you how to write a novel or a poem, or a CAD tutorial doesn't show you how to calculate the size of a beam for a building, this guide will not teach you spatial analysis. Instead, it will show you how to use the QGIS processing framework, a powerful tool for performing spatial analysis, but it is up to you to learn the required concepts that are needed to understand that type of analysis. Without them, there is no point on using the framework and its algorithms, although you might be tempted to try.

Let's show this more clearly with an example.

Given a set of points and a value of a given variable value at each point, you can calculate a raster layer from them using the *Kriging* geoalgorithm. The parameters dialog for that module is like the following one.



#### It look complex, right?

By reading this manual, you will learn things such as how to use that module, how to run it in a batch process to create raster layers from hundreds of points layers in a single run, or what happens if the input layer has some points selected. However, the parameters themselves are not explained. A seasoned analyst with a good knowledge of geostatistics will have no problem understanding those parameters. If you are not one of them and *sill*, *range*, or *nugget* are not familiar concepts to you, then you should not use the *Kriging* module. More than that, you are far from being ready to use the *Kriging* module, since it requires learning about concepts such as spatial autocorrelation or semivariograms, which probably you also haven't heard before, or at least haven't studied long enough. You should first study and understand them, and then come back to QGIS to actually run it and perform the analysis. Ignoring this will result in wrong results and poor (and most likely useless) analysis.

Although not all algorithms are as complex as kriging (but some of them are even more complex!), almost all of them require understanding the fundamental analysis ideas that they are based on. Without that knowledge, using them will most likely lead to poor results.

Using geoalgorithms without having a good foundation of spatial analysis is like trying to write a novel without

knowing anything about grammar or syntax, and having no knowledge about storytelling. You might get a result, but it is likely to have no value at all. Please, don't fool yourself and think that after reading this guide you are already capable of performing spatial analysis and get sound results. You need to study spatial analysis as well.

Here is a good reference that you can read to learn more about spatial data analysis.

*Geospatial Analysis (3rd Edition)*: A Comprehensive Guide to Principles, Techniques and Software Tools Michael John De Smith, Michael F. Goodchild, Paul A. Longley


It is available online here

# 18.3 Setting-up the processing framework


The first thing to do before using the processing framework is to configure it. There is not much to set-up, so this is an easy task.

Later on we will show how to configure the external applications that are used for extending the list of available algorithms, but for now we are just going to work with the framework itself.


The processing framework is a core QGIS plugin, which means that, if you are running QGIS 2.0 or later, it should already be installed in your system, since it is included with QGIS. In case it is active, you should see a menu called *Processing* in your menu bar. There you will find an access to all the framework components.



If you cannot find that menu, you have to enable the plugin by going to the plugin manager and activating it.



The main element that we are going to work with is the toolbox. Click on the corresponding menu entry and you will see the toolbox docked at the right side of the QGIS window.



The toolbox contains a list of all the available algorithms, divided in groups so called *Providers*. Providers can be (de)activated in the settings dialog. A label in the bottom part of the toolbox will remind you of that whenever there are inactive providers. Use the link in the label to open the settings window and set up providers. We will discuss the settings dialog later in this manual.

By default, only providers that do not rely on third-party applications (that is, those that only require QGIS elements to be run) are active. Algorithms requiring external applications might need additional configuration. Configuring providers is explained in a later chapter in this manual.


If you have reached this point, now you are ready to use geoalgorithms. There is no need to configure anything else by now. We can already run our first algorithm, which we will do in the next lesson.

# 18.4 Running our first algorithm. The toolbox

Muista: In this lesson we will run our first algorithm, and get our first result from it.


As we have already mentioned, the processing framework can run algorithms from other applications, but it also contains native algorithms that need no external software to be run. To start exploring the processing framework, we are going to run one of those native algorithms. In particular, we are going to calculate the centroids of set of polygons.

First, open the QGIS project corresponding to this lesson. It contains just a single layer with two polygons




Now go to the text box at the top of the toolbox. That is the search box, and if you type text in it, it will filter the list of algorithms so just those ones containing the entered text are shown. If there are algorithms that match your search but belong to a provider that is not active, an additional label will be shown in the lower part of the toolbox.


Type centroids and you should see something like this.



The search box is a very practical way of finding the algorithm you are looking for. At the bottom of the dialog, an additional label shows that there are algorithms that match your search but belong to a provider that is not active. If you click on the link in that label, the list of algorithms will also include results from those inactive providers, which will be shown in light gray. A link to activate each inactive provider is also shown. We'll see later how to activate other providers.



To execute an algorithm, you just have to double-click on its name in the toolbox. When you double-click on the *Polygon centroids* algorithm, you will see the following dialog.



All algorithms have a similar interface, which basically contains input parameters that you have to fill, and outputs that you have to select where to store. In this case, the only input we have is a vector layer with polygons.

Select the *Polygons* layer as input. The algorithm has a single output, which is the centroids layer. There are two options to define where a data output is saved: enter a filepath or save it to a temporary filename


In case you want to set a destination and not save the result in a temporary file, the format of the output is defined by the filename extension. To select a format, just select the corresponding file extension (or add it if you are directly typing the filepath instead). If the extension of the filepath you entered does not match any of the supported ones, a default extension (usually .dbf for tables, .tif for raster layers and .shp for vector ones) will be appended to the filepath and the file format corresponding to that extension will be used to save the layer or table.

In all the exercises in this guide, we will be saving results to a temporary file, since there is no need to save them for a later use. Feel free to save them to a permanent location if you want to.

**Varoitus:** Temporary files are deleted once you close QGIS. If you create a project with an output that was saved as a temporary output, QGIS will complain when you try to open back the project later, since that output file will not exist.

Once you have configured the algorithm dialog, press [Run] to run the algorithm.

You will get the following output.



The output has the same CRS as the input. Geoalgorithms assumes all input layers share the same CRS and do not perform any reprojection. Except in the case of some special algorithms (for instance, reprojection ones), the outputs will also have that same CRS. We will see more about this soon.

Try yourself saving it using different file formats (use, for instance, shp and geojson as extensions). Also, if you do not want the layer to be loaded in QGIS after it is generated, you can check off the checkbox that is found below the output path box.

# 18.5 More algorithms and data types

**Muista:** In this lesson we will run three more algorithms, learn how to use other input types, and configure outputs to be saved to a given folder automatically.


For this lessons we will need a table and a polygons layer. We are going to create a points layer based on coordinates in the table, and then count the number of points in each polygon. If you open the QGIS project corresponding to this lesson, you will find a table with X and Y coordinates, but you will find no polygons layer. Don't worry, we will create it using a processing geoalgorithm.

The first thing we are going to do is to create a points layer from the coordinates in the table, using the *Points layer from table* algorithm. You now know how to use the search box, so it should not be hard for you to find it. Double–click on it to run it and get to its following dialog.


This algorithm, like the one from the previous lesson, just generates a single output, and it has three inputs:

- Table: the table with the coordinates. You should select here the table from the lesson data.
- *X and Y fields*: these two parameters are linked to the first one. The corresponding selector will show the name of those fields that are available in the selected table. Select the *XCOORD* field for the *X* parameter, and the *YYCOORD* field for the *Y* parameter.
- *CRS*: Since this algorithm takes no input layers, it cannot assign a CRS to the output layer based on them. Instead, it asks you to manually select the CRS that the coordinates in the table use. Click on the button on the left–hand side to open the QGIS CRS selector, and select EPSG:4326 as the output CRS. We are using this CRS because the coordinates in the table are in that CRS.


Your dialog should look like this.



Now press the *Run* button to get the following layer (you may need to zoom full to reenter the map around the newly created points):




The next thing we need is the polygon layer. We are going to create a regular grid of polygons using the *Create grid* algorithm, which has the following parameters dialog.



**Varoitus:** The options are simpler in recent versions of QGIS; you just need to enter min and max for X and Y (suggested values: -5.696226,-5.695122,40.24742,40.248171)

The inputs required to create the grid are all numbers. When you have to enter a numerical value, you have two options: typing it directly on the corresponding box or clicking the button on the right—hand side to get to a dialog like the one shown next.




The dialog contains a simple calculator, so you can type expressions such as  $11 \times 34.7 + 4.6$ , and the result will be computed and put in the corresponding text box in the parameters dialog. Also, it contains constants that you can use, and values from other layers available.

In this case, we want to create a grid that covers the extent of the input points layer, so we should use its coordinates to calculate the center coordinate of the grid and its width and height, since those are the parameters that the algorithm takes to create the grid. With a little bit of math, try to do that yourself using the calculator dialog and the constants from the input points layer.

Select Rectangles (polygons) in the Type field.


As in the case of the last algorithm, we have to enter the CRS here as well. Select EPSG:4326 as the target CRS, as we did before.

In the end, you should have a parameters dialog like this:




(Better add one spacing on the width and height: Horizontal spacing: 0.0001, Vertical spacing: 0.0001, Width: 0.001004, Height: 0.000651, Center X: -5.695674, Center Y: 40.2477955) The case of X center is a bit tricky, see: -5.696126+((-5.695222+5.696126)/2)

Press Run and you will get the graticule layer.




The last step is to count the points in each one of the rectangles of that graticule. We will use the *Count points in polygons* algorithm.




Now we have the result we were looking for.

Before finishing this lesson, here is a quick tip to make your life easier in case you want to persistently save your data. If you want all your output files to be saved in a given folder, you do not have to type the folder name each time. Instead, go to the processing menu and select the *Options and configuration* item. It will open the

configuration dialog.



In the Output folder entry that you will find in the General group, type the path to your destination folder.



Now when you run an algorithm, just use the filename instead of the full path. For instance, with the configuration shown above, if you enter <code>graticule.shp</code> as the output path for the algorithm that we have just used, the result will be saved in <code>D:\processing\_output\graticule.shp</code>. You can still enter a full path in case you want a result to be saved in a different folder.


Try yourself the Create grid algorithm with different grid sizes, and also with different types of grids.

# 18.6 CRSs. Reprojecting

**Muista:** In this lesson we will discuss how Processing uses CRSs. We will also see a very useful algorithm: reprojecting.


CRS's are a great source of confusion for QGIS Processing users, so here are some general rules about how they are handled by geoalgorithms when creating a new layer.

• If there are input layers, it will use the CRS of the first layer. This is assumed to be the CRS of all input layers, since they should have the same one. If you use layers with unmatching CRS's, QGIS will warn you about it. Notice that the CRS of input layers is shown along with its name in the parameters dialog.



• If there are no input layer, it will use the project CRS, unless the algorithm contains a specific CRS field (as it happenend in the last lesson with the graticule algorithm)

Open the project corresponding to this lesson and you will see two layers named 23030 and 4326. They both contain the same points, but in different CRSs (EPSG:23030 and EPSG:4326). They appear in the same place because QGIS is reprojecting on the fly to the project CRS (EPSG:4326), but they are not actually the same layer.



Open the Export/Add geometry columns algorithm.

This algorithm add new columns to the attributes table of a vector layer. The content of the columns depend on the type of geometry of the layer. In the case of points, it adds new columns with the X and Y coordinates of each point.

In the list of available layers that you will find in the input layer field, you will see each one with its corresponding CRS. That means that, although they appear in the same place in your canvas, they will be treated differently. Select the 4326 layer.

The other parameter of the algorithm allows to set how the algorithm uses coordinates to calculate the new value that it will add to the resulting layers. Most algorithms do not have an option like that, and just use the coordinates directly. Select the *Layer CRS* option to just use coordinates as they are. This is how almost all geoalgorithms work.

You should get a new layer with exactly the same points as the other two layers. If you right click on the name of the layer and open its properties, you will see that it shares the same CRS of the input layer, that is, EPSG:4326. When the layer is loaded into QGIS, you will not be asked to enter the CRS of the layer, since QGIS already knows about it.

If you open the attributes table of the new layer you will see that it contains two new fields with the X and Y coordinates of each point.

|    | ID 🗸 | PT_NUM_A  | PT_ST_A | xcoord    | ycoord    |
|----|------|-----------|---------|-----------|-----------|
| 0  | 1    | 1.100000  | a       | -5.695426 | 40.248071 |
| 1  | 2    | 2.200000  | b       | -5.695885 | 40.247622 |
| 2  | 3    | 3.300000  | С       | -5.695406 | 40.247520 |
| 3  | 4    | 4.400000  | a       | -5.695222 | 40.247694 |
| 4  | 5    | 5.500000  | b       | -5.695642 | 40.248030 |
| 5  | 6    | 6.600000  | a       | -5.695855 | 40.248067 |
| 6  | 7    | 7.700000  | b       | -5.696049 | 40.248028 |
| 7  | 8    | 8.800000  | С       | -5.696126 | 40.247629 |
| 8  | 9    | 9.900000  | a       | -5.695961 | 40.247786 |
| 9  | 10   | 11.000000 | b       | -5.695353 | 40.247929 |
| 10 | 11   | 12.100000 | a       | -5.695595 | 40.247739 |
| 11 | 12   | 13.200000 | b       | -5.695779 | 40.247896 |

Those coordinate values are given in the layer CRS, since we chose that option. However, even if you choose another option, the output CRS of the layer would have been the same, since the input CRS is used to set the CRS of the output layer. Choosing another option will cause the values to be different, but not the resulting point to change or the CRS of the output layer to be different to the CRS of the input one.

Now do the same calculation using the other layer. You should find the resulting layer rendered exactly in the same place as the other ones, and it will have the EPSG:23030 CRS, since that was the one of the input layer.

If you go to its attribute table, you will see values that are different to the ones in the first layer that we created.

|    | ID 🗸 | PT_NUM_A  | PT_ST_A | xcoord        | ycoord          |
|----|------|-----------|---------|---------------|-----------------|
| 0  | 1    | 1.100000  | a       | 270839.655869 | 4458983, 162670 |
| 1  | 2    | 2.200000  | b       | 270799.116425 | 4458934.552874  |
| 2  | 3    | 3.300000  | С       | 270839.468187 | 4458921.978139  |
| 3  | 4    | 4.400000  | a       | 270855.745301 | 4458940.799487  |
| 4  | 5    | 5.500000  | b       | 270821.164389 | 4458979.173980  |
| 5  | 6    | 6.600000  | a       | 270803.157564 | 4458983.848803  |
| 6  | 7    | 7.700000  | b       | 270786.542791 | 4458980.047841  |
| 7  | 8    | 8.800000  | С       | 270778.601980 | 4458935.968837  |
| 8  | 9    | 9.900000  | a       | 270793.142411 | 4458952.931700  |
| 9  | 10   | 11.000000 | b       | 270845.414756 | 4458967.311298  |
| 10 | 11   | 12.100000 | a       | 270824.166376 | 4458946.784250  |
| 11 | 12   | 13.200000 | b       | 270809.035643 | 4458964.649799  |


This is because the original data is different (it uses a different CRS), and those coordinates are taken from it.

What should you learn from this? The main idea behind these examples is that geoalgorithms use the layer as it is in its original data source, and completely ignore the reprojections that QGIS might be doing before rendering. In other words, do not trust what you see in the canvas, but always have in mind that the original data will be used. That is not so important in this case, since we are just using one single layer at a time, but in an algorithm that needs several of them (such as a clip algorithm), layers that appear to match or overlay might be very far one from each other, since they might have different CRSs.

Algorithms performs no reprojection (except in the reprojection algorithm that we will see next), so it is up to you to make sure that layers have matching CRS's.

An interesting module that deals with CRS's is the reprojection one. It represents a particular case, since it has an input layer (the one to reproject), but it will not use its CRS for the output one.

Open the Reproject layer algorithm.



Select any of the layers as input, and select EPSG:23029 as the destination CRS. Run the algorithm and you will get a new layer, identical to the input one, but with a different CRS. It will appear on the same region of the canvas, like the other ones, since QGIS will reproject it on the fly, but its original coordinates are different. You can see that by running the *Export/Add geometry columns* algorithm using this new layer as input, and veryfing that the added coordinates are different to the ones in the attribute tables of both of the two layers that we had computed before.

# 18.7 Selection

**Muista:** In this lesson we will see how processing algorithms handle selections in vector layers that are used as inputs, and how to create a selection using a particular type of algorithm.

Unlike other analysis plugins in QGIS, you will not find in processing geoalgorithms any "Use only selected features" checkbox or similar. The behaviour regarding selection is set for the whole plugin and all its algorithms, and not for each algorithm execution. Algorithms follow the following simple rules when using a vector layer.


- If the layer has a selection, only selected features are used.
- If there is no selection, all features are used.

Please note that you can change this behaviour by unselecting the relevant option in the  $Processing \rightarrow Options \rightarrow General$  menu.


You can test that yourself by selecting a few points in any of the layers that we used in the last chapter, and running the reprojection algorithm on them. The reprojected layer that you will obtain will contain only those points that were selected, unless there was no selection, which will cause the resulting layer to contain all points from the original layer.

To make a selection, you can use any of the available methods and tools in QGIS. However, you can also use a geoalgorithm to do so. Algorithms for creating a selection are found in the toolbox under *Vector/Selection* 


18.7. Selection 455



Open the Random selection algorithm.



Leaving the default values, it will select 10 points from the current layer.



You will notice that this algorithm does not produce any output, but modifies the input layer (not the layer itself, but its selection). This is an uncommon behaviour, since all the other algorithms will produce new layers and not alter the input layers.

Since the selection is not part of the data itself, but something that only exist within QGIS, these selection algorithms only must be used selecting a layer that is open in QGIS, and not with the file selection option that you can find in the corresponding parameter value box.

The selection we have just made, like most of the ones created by the rest of the selection algorithms, can also be done manually from QGIS, so you might be wondering what is the point on using an algorithm for that. Although now this might not make much sense to you, we will later see how to create models and scripts. If you want to make a selection in the middle of a model (which defines a processing workflow), only a geoalgorithm can be added to a model, and other QGIS elements and operations cannot be added. That is the reason why some processing algorithms duplicate functionality that is also available in other QGIS elements.

By now, just remember that selections can be made using processing geoalgorithms, and that algorithms will only use the selected features if a selection exists, or all features otherwise.


# 18.8 Running an external algorithm

**Muista:** In this lesson we will see how to use algorithms that depend on a third-party application, particularly SAGA, which is one of the main algorithm providers.

All the algorithms that we have run so far are part of processing framework. That is, they are *native* algorithms implemented in the plugin and run by QGIS just like the plugin itself is run. However, one of the greatest features of the processing framework is that it can use algorithms from external applications and extend the possibilites of those applications. Such algorithms are wrapped and included in the toolbox, so you can easily use them from QGIS, and use QGIS data to run them.

Some of the algorithms that you see in the simplified view require third party applications to be installed in your system. One algorithm provider of special interest is SAGA (System for Automated Geospatial Analysis). First, we need to configure everything so QGIS can correctly call SAGA. This is not difficult, but it's important to understand how it works. Each external application has its own configuration, and later in this same manual we will talk about some of the other ones, but SAGA is going to be our main backend, so we will discuss it here.


If you are on Windows, the best way to work with external algorithms is to install QGIS using the standalone installer. It will take care of installing all the needed dependencies, including SAGA, so if you have used it, there is nothing else to do. You can open the settings dialog and go to the *Providers/SAGA* group.



The SAGA path should already be configured and pointing to the folder where SAGA is installed.

If you have installed QGIS not using the standalone installer, then you must enter the path to your SAGA installation (which you must have installed separately) there. The required version is SAGA 2.1 [this is changing according to the releases of SAGA].

In case you are using Linux, you do not have to set the path to your SAGA installation in the processing configuration. Instead, you must install SAGA and make sure that the SAGA folder is in PATH, so it can be called from the console (just open a console and type <code>saga\_cmd</code> to check it). Under Linux, the target version for SAGA is also 2.1, but in some installations (such as the OSGeo Live DVD) you might have just 2.0.8 available. There are some 2.1 packages available, but they are not commonly installed and might have some issues, so if you prefer to use the more common and stable 2.0.8, you can do it by enabling 2.0.8 compatibility in the configuration dialog, under the *SAGA* group.




Once SAGA is installed, you can launch a SAGA algorithm double clicking on its name, as with any other algorithm. Since we are using the simplified interface, you do not know which algorithms are based on SAGA or in another external application, but if you happen to double—click on one of them and the corresponding application is not installed, you will see something like this.




In our case, and assuming that SAGA is correctly installed and configured, you should not see this window, and you will get to the parameters dialog instead.

Let's try with a SAGA-based algorithm, the one called *Split shapes layer randomly*.




Use the points layer in the project corresponding to this lesson as input, and the default parameter values, and you will get something like this (the split is random, so your result might be different).




The input layer has been split in two layers, each one with the same number of points. This result has been computed by SAGA, and later taken by QGIS and added to the QGIS project.

If all goes fine, you will not notice any difference between this SAGA-based algorithm and one of the others that we have previously run. However, SAGA might, for some reason, not be able to produce a result and not generate the file that QGIS is expecting. In that case, there will be problems adding the result to the QGIS project, and an error message like this will be shown.



This kind of problems might happen, even if SAGA (or any other application that we are calling from the processing framework) is correctly installed, and it is important to know how to deal with them. Let's produce one of those error messages.

Open the Create graticule algorithm and use the following values.



We are using width and height values that is larger than the specified extent, so SAGA cannot produce any output.

In other words, the parameter values are wrong, but they are not checked until SAGA gets them and tries to create the graticule. Since it cannot create it, it will not produce the expected layer, and you will see the error message shown above.

**Muista:** In SAGA >= 2.2.3, the command will adjust automatically wrong input data, so you'll not get an error. To provoke an error, use negative values for division.

Understanding this kind of problems will help you solve them and find an explanation to what is happening. As you can see in the error message, a test is performed to check that the connection with SAGA is working correctly, indicating you that there might be a problem in how the algorithm was executed. This applies not only to SAGA, but also to other external applications as well.

In the next lesson we will introduce the processing log, where information about commands run by geoalgorithms is kept, and you will see how to get more detail when issues like this appear.

# 18.9 The processing log

**Muista:** This lesson describes the processing log.


All the analysis performed with the processing framework is logged in QGIS logging system. This allows you to know more about what has been done with the processing tools, to solve problems when they happen, and also to re–run previous operations, since the logging system also implements some interactivity.

To open the log, click on the balloon at the bottom right, on the QGIS status bar. Some algorithms might leave here information about their execution. For instance, those algorithms that call an external application usually log the console output of that application to this entry. If you have a look at it, you will see that the output of the SAGA algorithm that we just run (and that fail to execute because input data was not correct) is stored here.

This is helpful to understand what is going on. Advanced users will be able to analyze that output to find out why the algorithm failed. If you are not an advanced user, this will be useful for others to help you diagnose the problem you are having, which might be a problem in the installation of the external software or an issue with the data you provided.

Even if the algorithm could be executed, some algorithms might leave warnings in case the result might not be right. For instance, when executing an interpolation algorithm with a very small amount of points, the algorithm can run and will produce a result, but it is likely that it will not be correct, since more points should be used. It's a good idea to regularly check for this type of warnings if you are not sure about some aspect of a given algorithm.

From the *Processing* menu, under the *History* section, you'll find *Algorithms*. All algorithms that are executed, even if they are executed from the GUI and not from the console (which will be explained later in this manual) are stored in this section as a console call. That means that everytime you run an algorithm, a console command is added to the log, and you have the full history of your working session. Here is how that history looks like:



This can be very useful when starting working with the console, to learn about the syntax of algorithms. We will use it when we discuss how to run analysis commands from the console.

The history is also interactive, and you can re–run any previous algorithm just by double–clicking on its entry. This is an easy way of replicating the work we already did before.

For instance, try the following. Open the data corresponding to the first chapter of this manual and run the algorithm explained there. Now go to the log dialog and locate the last algorithm in the list, which corresponds to the algorithm you have just run. Double—click on it an a new result should be produced, just like when you run it using the normal dialog and calling it from the toolbox.



You can also modify the algorithm. Just copy it, open the  $Plugins \rightarrow Python\ console$ , click on  $Import\ class \rightarrow Import\ Processing\ class$ , then paste it to re-run the analysis; change the text at will. To display the resulting file, type iface.addVectorLayer('/path/filename.shp', 'Layer name in legend', 'ogr'). Otherwise, you can use processing.runandload.

### 18.10 The raster calculator. No-data values


**Muista:** In this lesson we will see how to use the raster calculator to perform some operations on raster layers. We will also explain what are no–data values and how the calculator and other algorithms deal with them

The raster calculator is one of the most powerful algorithms that you will find. It's a very flexible and versatile algorithm that can be used for many different calculations, and one that will soon become an important part of your toolbox.

In this lesson we will be performing some calculation with the raster calculator, most of them rather simple. This will let us see how it is used and how it deals with some particular situations that it might find. Understanding that is important to later get the expected results when using the calculator, and also to understand certain techniques that are commonly applied with it.

Open the QGIS project corresponding to this lesson and you will see that it contains several raster layers.

Now open the toolbox and open the dialog corresponding to the raster calculator.



Muista: The interface is different in recent versions.

The dialog contains 2 parameters.

- The layers to use for the analysis. This is a multiple input, that meaning that you can select as many layers as you want. Click on the button on the right—hand side and then select the layers that you want to use in the dialog that will appear.
- The formula to apply. The formula uses the layers selected in the above parameter, which are named using alphabet letters (a, b, c...) or g1, g2, g3... as variable names. That is, the formula a + 2 \* b is the same as g1 + 2 \* g2 and will compute the sum of the value in the first layer plus two times the value in the second layer. The ordering of the layers is the same ordering that you see in the selection dialog.

Varoitus: The calculator is case sensitive.

To start with, we will change the units of the DEM from meters to feet. The formula we need is the following one:

h' = h \* 3.28084

Select the DEM in the layers field and type a  $\,\star\,$  3.28084 in the formula field.

Varoitus: For non English users: use always ".", not ",".

Click *Run* to run the algorithm. You will get a layer that has the same appearance of the input layer, but with different values. The input layer that we used has valid values in all its cells, so the last parameter has no effect at all.


Let's now perform another calculation, this time on the *accflow* layer. This layer contains values of accumulated flow, a hydrological parameter. It contains those values only within the area of a given watershed, with no—data values outside of it. As you can see, the rendering is not very informative, due to the way values are distributed. Using the logarithm of that flow accumulation will yield a much more informative representation. We can calculate that using the raster calculator.

Open the algorithm dialog again, select the *accflow* layer as the only input layer, and enter the following formula: log(a).

Here is the layer that you will get.



If you select the *Identify* tool to know the value of a layer at a given point, select the layer that we have just created, and click on a point outside of the basin, you will see that it contains a no–data value.



For the next exercise we are going to use two layers instead of one, and we are going to get a DEM with valid elevation values only within the basin defined in the second layer. Open the calculator dialog and select both layers of the project in the input layers field. Enter the following formula in the corresponding field:

$$a/a * b$$

a refers to the accumulated flow layer (since it is the first one to appear in the list) and b refers to the DEM. What we are doing in the first part of the formula here is to divide the accumulated flow layer by itself, which will result in a value of 1 inside the basin, and a no-data value outside. Then we multiply by the DEM, to get the elevation value in those cells inside the basin (DEM  $\star$  1 = DEM) and the no-data value outside (DEM  $\star$  no\_data = no\_data)

Here is the resulting layer.



This technique is used frequently to *mask* values in a raster layer, and is useful whenever you want to perform calculations for a region other that the arbitrary rectangular region that is used by raster layer. For instance, an elevation histogram of a raster layer doesn't have much meaning. If it is instead computed using only values corresponding to a basin (as in he case above), the result that we obtain is a meaningful one that actually gives

information about the configuration of the basin.

There are other interesting things about this algorithm that we have just run, apart from the no-data values and how they are handled. If you have a look at the extents of the layers that we have multiplied (you can do it double-clicking on their names of the layer in the table of contents and looking at their properties), you will see that they are not the same, since the extent covered by the flow accumulation layer is smaller that the extent of the full DEM.

That means that those layers do not match, and that they cannot be multiplied directly without homogenizing those sizes and extents by resampling one or both layers. However, we did not do anything. QGIS takes care of this situation and automatically resamples input layers when needed. The output extent is the minimum covering extent calculated from the input layers, and the minimum cell size of their cellsizes.

In this case (and in most cases), this produces the desired results, but you should always be aware of the additional operations that are taking place, since they might affect the result. In cases when this behaviour might not be the desired, manual resampling should be applied in advance. In later chapters, we will see more about the behaviour of algorithms when using multiple raster layers.

Let's finish this lesson with another masking exercise. We are going to calculate the slope in all areas with an elevation between 1000 and 1500 meters.

In this case, we do not have a layer to use as a mask, but we can create it using the calculator.

Run the calculator using the DEM as only input layer and the following formula

```
ifelse(abs(a-1250) < 250, 1, 0/0)
```

As you can see, we can use the calculator not only to do simple algebraic operations, but also to run more complex calculation involving conditional sentences, like the one above.

The result has a value of 1 inside the range we want to work with, and no-data in cells outside of it.



The no-data value comes from the 0/0 expression. Since that is an undetermined value, SAGA will add a NaN (Not a Number) value, which is actually handled as a no-data value. With this little trick you can set a no-data value without needing to know what the no-data value of the cell is.


Now you just have to multiply it by the slope layer included in the project, and you will get the desired result.

All that can be done in a single operation with the calculator. We leave that as an exercise for the reader.

### 18.11 Vector calculator

**Muista:** In this lesson we will see how to add new attributes to a vector layer based on a mathematical expression, using the vector calculator.

We already know how to use the raster calculator to create new raster layers using mathematical expressions. A similar algorithm is available for vector layers, and generates a new layer with the same attributes of the input layer, plus an additional one with the result of the expression entered. The algorithm is called *Field calculator* and has the following parameters dialog.



**Muista:** In newer versions of Processing the interface has changed considerably, it's more powerful and easier to use.

Here are a few examples of using that algorithm.

First, let's calculate the population density of white people in each polygon, which represents a census. We have two fields in the attributes table that we can use for that, namely <code>WHITE</code> and <code>SHAPE\_AREA</code>. We just have to divide them and multiply by one million (to have density per square km), so we can use the following formula in the corresponding field


```
( "WHITE" / "SHAPE_AREA" ) * 1000000
```

The parameters dialog should be filled as shown below.

This will generate a new field named WHITE\_DENS


Now let's calculate the ratio between the MALES and FEMALES fields to create a new one that indicates if male population is numerically predominant over female population.

Enter the following formula



"MALES" / "FEMALES"

This time the parameters window should look like this before pressing the OK button.




In earlier version, since both fields are of type integer, the result would be truncated to an integer. In this case the formula should be:  $1.0 \star \text{"MALES"}$  / "FEMALES", to indicate that we want floating point number a result.


We can use conditional functions to have a new field with male or female text strings instead of those ratio value, using the following formula:

```
CASE WHEN "MALES" > "FEMALES" THEN 'male' ELSE 'female' END
```

The parameters window should look like this.



A python field calculator is available in the Advanced Python field calculator, which will not be detailed here




## 18.12 Defining extents

**Muista:** In this lesson we will see how to define extents, which are needed by some algorithms, especially raster ones.

Some algorithms require an extent to define the area to be covered by the analysis they perform, and usually to define the extent of the resulting layer.

When an extent is required, it can be defined manually by entering the four values that define it (min X, min Y, max X, max Y), but there are other more practical and more interesting ways of doing it as well. We will see all of them in this lesson.

First, let's open an algorithm that requires an extent to be defined. Open the *Rasterize* algorithm, which creates a raster layer from a vector layer.




All the parameters, except for the last two ones, are used to define which layer is to be rasterized, and configure how the rasterization process should work. The two last parameters, on the other hand, define the characteristics of the output layer. That means that they define the area that is covered (which is not necessarily the same area covered by the input vector layer), and the resolution/cellsize (which cannot be infered from the vector layer, since vector layers do not have a cellsize).

The first thing you can do is to type the 4 defining values explained before, separated by commas.




That doesn't need any extra explanation. While this is the most flexible option, it is also the less practical in some cases, and that's why other options are implemented. To access them, you have to click on the button on the right-hand side of the extent text box.




Let's see what each one of them does.

The first option is *Use layer/canvas extent*, which will show the selection dialog shown below.



Here you can select the extent of the canvas (the extent covered by the current zoom), or the extension any of the available layers. Select it and click on OK, and the text box will be automatically filled with the corresponding values.

The second option is *Select extent on canvas*. In this case, the algorithm dialog disappears and you can click and drag on the QGIS canvas to define the desired extent.




Once you release the mouse button, the dialog will reappear and the text box will already have the values corresponding to the defined extent.

The last option is *Use min covering extent from input layers*, which is the default option. This will compute the min covering extent of all layers used to run the algorithm, and there is no need to enter any value in the text box. In the case of a single input layer, as in the algorithm we are running, the same extent can be obtained by selecting that same input layer in the *Use layer/canvas extent* that we already saw. However, when there are several input layers, the min covering extent does not correspond to any of the input layer extent, since it is computed from all of them together.


We will use this last method to execute our rasterization algorithm.

Fill the parameters dialog as shown next, and press *OK*.



**Muista:** In this case, better use an *Integer (1 byte)* instead of a *Floating point (4 byte)*, since the *NAME* is an integer with maximum value=64. This will result in a smaller file size and faster computations.

You will get a rasterized layer that covers exactly the area covered by the original vector layer.



In some cases, the last option, *Use min covering extent from input layers*, might not be available. This will happen in those algorithm that do not have input layers, but just parameters of other types. In that case, you will have to enter the value manually or use any of the other options.

Notice that, when a selection exist, the extent of the layer is that of the whole set of features, and the selection is not used to compute the extent, even though the rasterization is executed on the selected items only. In that case, you might want to actually create a new layer from the selection, and then use it as input.


### 18.13 HTML outputs

**Muista:** In this lesson we learn how QGIS handles outputs in HTML format, which are used to produce text outputs and graphs.

All the outputs we have produced so far were layers (whether raster or vector). However, some algorithms generate outputs in the form of text and graphics. All this outputs are wrapped in HTML files and displayed in the so—called *Results viewer*, which is another element of the processing framework.


Let's see one of those algorithms to understand how they work.

Open the project with the data to be used in this lesson and then open the Basic statistics for numeric fields algorithm.



The algorithm is rather simple, and you just have to select the layer to use and one of its field (a numeric one). The output is of type HTML, but the corresponding box works exactly like the one that you can find in the case of a raster or vector output. You can enter a filepath or leave it blank to save to a temporary file. In this case, however, only the html and htm extensions are allowed, so there is no way of altering the output format by using a different one.

Run the algorithm selecting the only layer in the project as input, and the *POP2000* field, and a new dialog like the one shown next will appear once the algorithm is executed and the parameters dialog is closed.



This is the *Results viewer*. It keeps all the HTML result generated during the current session, easily accessible, so you can check them quickly whenever you need it. As it happens with layers, if you have saved the output to a temporary file, it will be deleted once you close QGIS. If you have saved to a non-temporary path, the file will remain, but it will not appear in the *Results viewer* the next time you open QGIS.

Some algorithms generate text that cannot be divided into other more detailed outputs. That is the case if, for instance, the algorithm captures the text output from an external process. In other cases, the output is presented as text, but internally is divided into several smaller outputs, usually in the form of numeric values. The algorithm that we have just executed is one of them. Each one of those values is handled as a single output, and stored in a variable. This has no importance at all now, but once we move to the graphical modeler, you will see that it will allow us to use those values as numeric inputs for other algorithms.

# 18.14 First analysis example

**Muista:** In this lesson we will perform some real analysis using just the toolbox, so you can get more familiar with the processing framework elements.

Now that everything is configured and we can use external algorithms, we have a very powerful tool to perform spatial analysis. It is time to work out a larger exercise with some real–world data.


We will be using the well-known dataset that John Snow used in 1854, in his groundbreaking work (http://en.wikipedia.org/wiki/John\_Snow\_%28physician%29), and we will get some interesting results. The analysis of this dataset is pretty obvious and there is no need for sofisticated GIS techniques to end up with good

results and conclusions, but it is a good way of showing how these spatial problems can be analyzed and solved by using different processing tools.


The dataset contains shapefiles with cholera deaths and pump locations, and an OSM rendered map in TIFF format. Open the corresponding QGIS project for this lesson.



The first thing to do is to calculting the Voronoi diagram (a.k.a. Thyessen polygons) of the pumps layer, to get the influence zone of each pump. The *Voronoi Diagram* algorithm can be used for that.




Pretty easy, but it will already give us interesting information.




Clearly, most cases are within one of the polygons


To get a more quantitative result, we can count the number of deaths in each polygon. Since each point represents a building where deaths occured, and the number of deaths is stored in an attribute, we cannot just count the points. We need a weighted count, so we will use the *Count points in polygon (weighted)* tool.




The new field will be called *DEATHS*, and we use the *COUNT* field as weighting field. The resulting table clearly reflects that the number of deaths in the polygon corresponding to the first pump is much larger than the other ones



Another good way of visualizing the dependence of each point in the Cholera\_deaths layer with a point in the Pumps layer is to draw a line to the closest one. This can be done with the *Distance to nearest hub* tool, and using the configuration shown next.




The result looks like this:




Although the number of lines is larger in the case of the central pump, do not forget that this does not represent the number of deaths, but the number of locations where cholera cases were found. It is a representative parameter, but it is not considering that some locations might have more cases than other.

A density layer will also give us a very clear view of what is happening. We can create it with the *Kernel density* algorithm. Using the *Cholera\_deaths* layer, its *COUNT* field as weight field, with a radius of 100, the extent and cellsize of the streets raster layer, we get something like this.



Remember that, to get the output extent, you do not have to type it. Click on the button on the right-hand side and select *Use layer/canvas extent*.




Select the streets raster layer and its extent will be automatically added to the text field. You must do the same with the cellsize, selecting the cellsize of that layer as well.

Combining with the pumps layer, we see that there is one pump clearly in the hotspot where the maximum density of death cases is found.

## 18.15 Clipping and merging raster layers

**Muista:** In this lesson we will see another example of spatial data preparation, to continue using geoalgorithms in real-world scenarios.

For this lesson, we are going to calculate a slope layer for an area surrounding a city area, which is given in a vector layer with a single polygon. The base DEM is divided in two raster layers that, together, cover an area much larger than that around the city that we want to work with. If you open the project corresponding to this lesson, you will see something like this.




These layers have two problems:

- They cover an area that is too large for what we want (we are interested in a smaller region around the city center)
- They are in two different files (the city limits fall into just one single raster layer, but, as it's been said, we want some extra area around it).


Both of them are easily solvable with the appropriate geoalgorithms.

First, we create a rectangle defining the area that we want. To do it, we create a layer containing the bounding box of the layer with the limits of the city area, and then we buffer it, so as to have a raster layer that covers a bit more that the strictly necessary.

To calculate the bounding box, we can use the Polygon from layer extent algorithm




To buffer it, we use the Fixed distance buffer algorithm, with the following parameter values.




Varoitus: Syntax changed in recent versions; set both Distance and Arc vertex to .25


Here is the resulting bounding box obtained using the parameters shown above



It is a rounded box, but we can easily get the equivalent box with square angles, by running the *Polygon from layer extent* algorithm on it. We could have buffered the city limits first, and then calculate the extent rectangle, saving one step.




You will notice that the rasters has a different projection from the vector. We should therefore reproject them before proceeding further, using the *Warp (reproject)* tool.




Muista: Recent versions have a more complex interface. Make sure at least one compression method is selected.

With this layer that contains the bounding box of the raster layer that we want to obtain, we can crop both of the raster layers, using the *Clip raster with polygon* algorithm.




Once the layers have been cropped, they can be merged using the GDAL Merge algorithm.



**Muista:** You can save time merging first and then cropping, and you will avoid calling the clipping algorithm twice. However, if there are several layers to merge and they have a rather big size, you will end up with a large layer than it can later be difficult to process. In that case, you might have to call the clipping algorithm several times, which might be time consuming, but don't worry, we will soon see that there are some additional tools to automate that operation. In this example, we just have two layers, so you shouldn't worry about that now.


With that, we get the final DEM we want.




Now it is time to compute the slope layer.

A slope layer can be computed with the *Slope, Aspect, Curvature* algorithm, but the DEM obtained in the last step is not suitable as input, since elevation values are in meters but cellsize is not expressed in meters (the layer uses a CRS with geographic coordinates). A reprojection is needed. To reproject a raster layer, the *Warp (reproject)* algorithm can be used again. We reproject into a CRS with meters as units (e.g. 3857), so we can then correctly calculate the slope, with either SAGA or GDAL.


With the new DEM, slope can now be computed.



And here is the resulting slope layer.



The slope produced by the *Slope, Aspect, Curvature* algorithm can be expressed in degrees or radians; degrees are a more practical and common unit. In case you calculated it in radians, the *Metric conversions* algorithm will help us to do the conversion (but in case you didn't know that algorithm existed, you could use the raster calculator that we have already used).



Reprojecting the converted slope layer back with the Reproject raster layer, we get the final layer we wanted.

Varoitus: todo: Add image


The reprojection processes might have caused the final layer to contain data outside the bounding box that we calculated in one of the first steps. This can be solved by clipping it again, as we did to obtain the base DEM.

# 18.16 Hydrological analysis

**Muista:** In this lesson we will perform some hydrological analysis. This analysis will be used in some of the following lessons, as it constitutes a very good example of an analysis workflow, and we will use it to demonstrate some advanced features.


In this lesson, we are going to do some hydrological analysis. Starting with a DEM, we are going to extract a channel network, delineate watersheds and calculate some statistics.

The first thing is to load the project with the lesson data, which just contains a DEM.



The first module to execute is *Catchment area* (in some SAGA versions it is called *Flow accumulation (Top Down)*). You can use anyone of the others named *Catchment area*. They have different algorithms underneath, but the results are basically the same.


Select the DEM in the *Elevation* field, and leave the default values for the rest of parameters.




Some algorithms calculate many layers, but the Catchment Area one is the only one we will be using.

You can get rid of the other ones if you want.


The rendering of the layer is not very informative.



To know why, you can have a look at the histogram and you will see that values are not evenly distributed (there are a few cells with very high value, those corresponding to the channel network). Calculating the logarithm of the catchment area value yields a layer that conveys much more information (you can do it using the raster calculator).




The catchment area (also known as flow accumulation), can be used to set a threshold for channel initiation. This can be done using the *Channel network* algorithm. Here is how you have to set it up (note the *Initiation threshold Greater than* 10.000.000).




Use the original catchment area layer, not the logarithm one. That one was just for rendering purposes.

If you increase the *Initiation threshold* value, you will get a more sparse channel network. If you decrease it, you will get a denser one. With the proposed value, this is what you get.




The image above shows just the resulting vector layer and the DEM, but there should be also a raster one with the same channel network. That raster one will be, in fact, the one we will be using.


Now, we will use the *Watersheds basins* algorithm to delineate the subbasins corresponding to that channel network, using as outlet points all the junctions in it. Here is how you have to set the corresponding parameters dialog.




And this is what you will get.



This is a raster result. You can vectorise it using the *Vectorising grid classes* algorithm.







Now, let's try to compute statistics about the elevation values in one of the subbasins. The idea is to have a layer that just represents the elevation within that subbasin and then pass it to the module that calculates those statistics.

First, let's clip the original DEM with the polygon representing a subbasin. We will use the *Clip raster with polygon* algorithm. If we select a single subbasin polygon and then call the clipping algorithm, we can clip the DEM to the area covered by that polygon, since the algorithm is aware of the selection.

Select a polygon,




and call the clipping algorithm with the following parameters:




The element selected in the input field is, or course, the DEM we want to clip.


You will get something like this.



This layer is ready to be used in the Raster layer statistics algorithm.



The resulting statistics are the following ones.



We will use both the basin calculations procedure and the statistics calculation in other lessons, to find out how other elements can help us automate both of them and work more effectively.


## 18.17 Starting with the graphical modeler

**Muista:** In this lesson we will use the graphical modeler, a powerful component that we can use to define a workflow and run a chain of algorithms.

A normal session with the processing tools includes more than running a single algorithm. Usually several of them are run to obtain a result, and the outputs of some of those algorithms are used as input for some of the other ones.

Using the graphical modeler, that workflow can be put into a model, which will run all the necessary algorithms in a single run, thus simplifying the whole process and automating it.

To start this lesson, we are going to calculate a parameter named Topographic Wetness Index. The algorithm that computes it is called *Topographic wetness index (twi)* 





As you can see, there are two mandatory inputs: *Slope* and *Catchment area*. There is also an optional input, but we will not be using it, so we can ignore it.

The data for this lesson contains just a DEM, so we do not have any of the required inputs. However, we know how to calculate both of them from that DEM, since we have already seen the algorithms to compute slope and catchment area. So we can first compute those layers and then use them for the TWI algorithm.


Here are the parameter dialogs that you should use to calculate the 2 intermediate layers.

**Muista:** Slope must be calculated in radians, not in degrees.






And this is how you have to set the parameters dialog of the TWI algorithm.




This is the result that you will obtain (the default singleband pseudocolor inverted palette has been used for rendering). You can use the twi.qml style provided.



What we will try to do now is to create an algorithm that calculates the TWI from a DEM in just one single step. That will save us work in case we later have to compute a TWI layer from another DEM, since we will need just

one single step to do it instead of the 3 ones above. All the processes that we need are found in the toolbox, so what we have to do is to define the workflow to wrap them. This is where the graphical modeler comes in.


Open the modeler by selecting its menu entry in the processing menu.



Two things are needed to create a model: setting the inputs that it will need, and defining the algorithm that it contains. Both of them are done by adding elements from the two tabs in the left–hand side of the modeler window: *Inputs* and *Algorithms* 


Let's start with the inputs. In this case we do not have much to add. We just need a raster layer with the DEM, and that will be our only input data.

Double click on the Raster layer input and you will see the following dialog.




Here we will have to define the input we want. Since we expect this raster layer to be a DEM, we will call it *DEM*. That's the name that the user of the model will see when running it. Since we need that layer to work, we will define it as a mandatory layer.


Here is how the dialog should be configured.



Click on *OK* and the input will appear in the modeler canvas.



Now let's move to the *Algorithms* tab. The first algorithm we have to run is the *Slope, aspect, curvature* algorithm. Locate it in the algorithm list, double–click on it and you will see the dialog shown below.




This dialog is very similar to the one that you can find when running the algorithm from the toolbox, but the element that you can use as parameter values are not taken from the current QGIS project, but from the model itself. That means that, in this case, we will not have all the raster layers of our project available for the *Elevation* field, but just the ones defined in our model. Since we have added just one single raster input named *DEM*, that will be the only raster layer that we will see in the list corresponding to the *Elevation* parameter.


Output generated by an algorithm are handled a bit differently when the algorithm is used as a part of a model. Instead of selecting the filepath where you want to save each output, you just have to specify if that ouput is an intermediate layer (and you do not want it to be preserved after the model has been executed), or it is a final one. In this case, all layers produced by this algorithm are intermediate. We will only use one of them (the slope layer), but we do not want to keep it, since we just need it to calculate the TWI layer, which is the final result that we want to obtain.

When layers are not a final result, you should just leave the corresponding field. Otherwise, you have to enter a name that will be used to identify the layer in the parameters dialog that will be shown when you run the model later.


There is not much to select in this first dialog, since we do not have but just one layer in or model (The DEM input that we created). Actually, the default configuration of the dialog is the correct one in this case, so you just have to press *OK*. This is what you will now have in the modeler canvas.




The second algorithm we have to add to our model is the catchment area algorithm. We will use the algorithm named *Catchment area* (*Paralell*). We will use the DEM layer again as input, and none of the ouputs it produces are final, so here is how you have to fill the corresponding dialog.



Now your model should look like this.




The last step is to add the *Topographic wetness index* algorithm, with the following configuration.




In this case, we will not be using the DEM as input, but instead, we will use the slope and catchment area layers that are calculated by the algorithms that we previously added. As you add new algorithms, the outputs they produce become available for other algorithms, and using them you link the algorithms, creating the workflow.

In this case, the output TWI layer is a final layer, so we have to indicate so. In the corresponding textbox, enter

the name that you want to be shown for this output.




Enter a name and a group name in the upper part of the model window, and then save it clicking on the *Save* button.




You can save it anywhere you want and open it later, but if you save it in the models folder (which is the folder that you will see when the save file dialog appears), you model will also be available in the toolbox as well. So stay on that folder and save the model with the filename that you prefer.

Now close the modeler dialog and go to the toolbox. In the Models entry you will find you model.



You can run it just like any normal algorithm, double-clicking on it.



As you can see, the parameters dialog, contain the input that you added to the model, along with the outputs that you set as final when adding the corresponding algorithms.

Run it using the DEM as input and you will get the TWI layer in just one single step.


# 18.18 More complex models

Muista: In this lesson we will work with a more complex model in the graphical modeler.

The first model that we created in the previous chapter was a very simple one, with just one input and 3 algorithms. More complex models can be created, with different types of inputs and containing more step. For this chapter we will work with a model that creates a vector layer with watersheds, based on a DEM and a threshold value. That will be very useful for calculating several vector layers corresponding to different thresholds, without having to repeat each single step each time.


This lesson does not contain instructions about how to create you model. You already know the necessary steps (we saw them in a previous lesson) and you have already seen the basic ideas about the modeler, so you should try it yourself. Spend a few minutes trying to create your model, and don't worry about making mistakes. Remember: first add the inputs and then add the algorithms that use them to create the workflow.

In case you could not create the full model yourself and you need some extra help, the data folder corresponding to this lesson contains an 'almost' finished version of it. Open the modeler and then open the model file that you will find in the data folder. You should see something like this.




This model contains all the steps needed to complete the calculation, but it just has one input: the DEM. That means that the threshold for channel definition use a fixed value, which makes the model not as useful as it could be. That is not a problem, since we can edit the model, and that is exactly what we will do.


First, let's add a numerical input. That will ask the user for a numerical input that we can use when such a value is needed in any of the algorithms included in our model. Click on the *Number* entry in the inputs tree, and you will see the corresponding dialog. Fill it with the values shown next.



Now your model should look like this.




The input that we have just added is not used, so the model hasn't actually changed. We have to link that input to the algorithm that uses it, in this case the *Channel network* one. To edit an algorithm that already exists in the modeler, just click on the pen icon on the corresponding box in the canvas. If you click on the *Channel network* algorithm, you will see something like this.




The dialog is filled with the current values used by the algorithm. You can see that the threshold parameter has a fixed value of 1,000,000 (this is also the default value of the algorithm, but any other value could be put in there). However, you might notice that the parameter is not entered in a common text box, but in an option menu. If you

unfold it, you will see something like this.





The input that we added is there and we can select it. Whenever an algorithm in a model requires a numerical value, you can hardcode it and directly type it, or you can use any of the available inputs and values (remember that some algorithms generate single numerical values. We will see more about this soon). In the case of a string parameter, you will also see string inputs and you will be able to select one of them or type the desired fixed value.

Select the *Threshold* input in the *Threshold* parameter and click on *OK* to apply the changes to your model. Now the design of the model should look like this.



The model is now complete. Try to run it using the DEM that we have used in previous lessons, and with different threshold values. Here you have a sample of the result obtained for different values. You can compare with the result for the default value, which is the one we obtained in the hydrological analysis lesson.





Threshold = 1,0000,000

### 18.19 Numeric calculations in the modeler


Varoitus: Beware, this chapter is not well tested, please report any issue; images are missing

**Muista:** In this lesson we will see how to use numeric outputs in the modeler

For this lesson, we are going to modify the hydrological model that we created in the last chapter (open it in the modeler before starting), so we can automate the calculation of a valid threshold value and we do not have to ask the user to enter it. Since that value refers to the variable in the threshold raster layer, we will extract it from that layer, based on some simple statistical analysis.


Starting with the aforementioned model, let's do the following modifications:

First, calculate statistics of the flow accumulation layer using the Raster layer statistics algorithm.



This will generate a set of statistical values that will now be available for all numeric fields in other algorithms.


If you edit the *Channel network* algorithm, as we did in the last lesson, you will see now that you have other options apart from the numeric input that you added.




However, none of this values is suitable for being used as a valid threshold, since they will result in channel networks that will not be very realistic. We can, instead, derive some new parameter based on them, to get a better result. For instance, we can use the mean plus 2 times the standard deviation.

To add that arithmetical operation, we can use the calculator that you will find in the *Geoalgorithms/modeler/modeler-tools* group. This group contains algorithms that are not very useful outside of the modeler, but that provide some useful functionality when creating a model.

The parameters dialog of the calculator algorithm looks like this:




As you can see, the dialog is different to the other ones we have seen, but you have in there the same variables that were available in the *Threshold* field in the *Channel network* algorithm. Enter the above formula and click on *OK* to add the algorithm.




If you expand the outputs entry, as shown above, you will see that the model is connected to two of the values, namely the mean and the standard deviation, which are the ones that we have used in the formula.

Adding this new algorithm will add a new numeric value. If you go again to the *Channel network* algorithm, you can now select that value in the *Threshold* parameter.



Click on OK and your model should look like this.



We are not using the numeric input that we added to the model, so it can be removed. Right-click on it and select

#### Remove

Varoitus: todo: Add image

Our new model is now finished.

#### 18.20 A model within a model

Varoitus: Beware, this chapter is not well tested, please report any issue; images are missing

**Muista:** In this lesson we will see how to use a model within a bigger model.

We have already created a few models, and in this lesson we are going to see how we can combine them on a single bigger one. A model behaves like any other algorithm, which means that you can add a model that you have already created as part of another one that you create after that.

In this case, we are going to expand our hydrological model, by adding the mean TWI value in each of the basins that it generates as result. To do that, we need to calculate the TWI, and to compute the statistics. Since we have already created a model to calculate TWI from a DEM, it is a good idea to reuse that model instead of adding the algorithms it contains individually.

Let's start with the model we used as starting point for the last lesson.

Varoitus: todo: Add image

First, we will add the TWI model. For it to be available, it should have been saved on the models folder, since otherwise it will not be shown in the toolbox or the algorithms list in the modeler. Make sure you have it available.

Add it to the current model and use the input DEM as its input. The output is a temporary one, since we just want the TWI layer to compute the statistics. The only output of this model we are creating will still be the vector layer with the watersheds.

Here is the corresponding parameters dialog:

Varoitus: todo: Add image

Now we have a TWI layer that we can use along with the watersheds vector layer, to generate a new one which contains the values of the TWI corresponding to each watershed.

This calculation is done using the *Grid statistics in polygons* algorithm. Use the layers mentioned above as input, to create the final result.

Varoitus: todo: Add image

The output of the *Vectorize grid classes* algorithm was originally our final output, but now we just want it as an intermediate result. To change that, we have to edit the algorithm. Just double–click on it to see its parameters dialog, and delete the name of the output. That will make it a temporary output, as it is by default.

Varoitus: todo: Add image

This is how the final model should look like:

Varoitus: todo: Add image

As you see, using a model in another model is nothing special, and you can add it just like you add another algorithm, as long as the model is saved in the models folder and is available in the toolbox.


## 18.21 Using modeler-only tools for creating a model

**Muista:** This lesson shows how to use some algorithms that are only available in the modeler, to provide additional functionality to models.

The goal of this lesson is to use the modeler to create an interpolation algorithm that takes into account the current selection, not just to use only selected features, but to use the extent of that selection to create the interpolated raster layer.


The interpolation process involves two steps, as it has been already explained in previous lessons: rasterizing the points layer and fill the no-data values that appear in the rasterized layer. In case the points layer has a selection, only selected points will be used, but if the output extent is set to be automatically adjusted, the full extent of the layer will be used. That is, the extent of the layer is always considered to be the full extent of all features, not the one computed from just the selected ones. We will try to fix that by using some additional tools into our model.

Open the modeler and start the model by adding the required inputs. In this case we need a vector layer (restricted to points) and an attribute from it, with the values that we will use for rasterizing.




The next step is to compute the extent of the selected features. That's where we can use the model-only tool called *Vector layer bounds*. First, we will have to create a layer that has the extent of those selected features. Then, we can use this tool on that layer.

An easy way of creating a layer with the extent of the selected features is to compute a convex hull of the input points layer. It will use only the selected point, so the convex hull will have the same bounding box as the selection. Then we can add the *Vector layer bounds* algorithm, and use the convex hull layer as input. It should look this in the modeler canvas:





The result from the *Vector layer bounds* is a set of four numeric values and a extent object. We will use both the numeric outputs and the extent for this exercise.




We can now add the algorithm that rasterizes the vector layer, using the extent from the *Vector layer bounds* algorithm as input.

Fill the parameters of the algorithm as shown next:






Finally, fill the no-data values of the raster layer using the *Close gaps* algorithm.




The algorithm is now ready to be saved and added to the toolbox. You can run it and it will generate a raster layer from interpolating the selected points in the input layer, and the layer will have the same extent as the selection.

Here's an improvement to the algorithm. We have used a harcoded value for the cellsize when rasterizing. This value is fine for our test input layer, but might not be for other cases. We could add a new parameter, so the user enters the desired value, but a much better approach would be to have that value automatically computed.

We can use the modeler-only calculator, and compute that value from the extent coordinates. For instance, to create a layer with a fixed width of 100 pixels, we can use the following formula in the calculator.



Now we have to edit the rasterize algorithm, so it uses the output of the calculator instead of the hardcoded value.



# 18.22 Interpolation

Muista: This chapter shows how to interpolate point data, and will show you another real example of performing

#### spatial analysis

In this lesson, we are going to interpolate points data to obtain a raster layer. Before doing it, we will have to do some data preparation, and after interpolating we will add some extra processing to modify the resulting layer, so we will have a complete analysis routine.


Open the example data for this lesson, which should look like this.




The data correspond to crop yield data, as produced by a modern harvester, and we will use it to get a raster layer of crop yield. We do not plan to do any further analysis with that layer, but just to use it as a background layer for easily identifying the most productive areas and also those where productivity can be improved.

The first thing to do is to clean—up the layer, since it contains redundant points. These are caused by the movement of the harvester, in places where it has to do a turn or it changes its speed for some reason. The *Points filter* algorithm will be useful for this. We will use it twice, to remove points that can be considered outliers both in the upper and lower part of the distribution.

For the first execution, use the following parameter values.




Now for the next one, use the configuration shown below.



Notice that we are not using the original layer as input, but the output of the previous run instead.


The final filter layer, with a reduced set of points, should look similar to the original one, but it contains a smaller number of points. You can check that by comparing their attribute tables.

Now let's rasterize the layer using the Rasterize algorithm.




The *Filtered points* layer refers to the resulting one of the second filter. It has the same name as the one produced by the first filter, since the name is assigned by the algorithm, but you should not use the first one. Since we will not be using it for anything else, you can safely remove it from your project to avoid confusion, and leave just the last filtered layer.


The resulting raster layer looks like this.




It is already a raster layer, but it is missing data in some of its cells. It only contain valid values in those cells that contained a point from the vector layer that we have just rasterized, and a no–data value in all the other ones. To fill the missing values, we can use the *Close gaps* algorithm.




The layer without no-data values looks like this.




To restrict the area covered by the data to just the region where crop yield was measured, we can clip the raster layer with the provided limits layer.



And for a smoother result (less accurate but better for rendering in the background as a support layer), we can apply a *Gaussian filter* to the layer.





With the above parameters you will get the following result


# 18.23 More interpolation

Muista: This chapter shows another practical case where interpolation algorithms are used.


Interpolation is a common technique, and it can be used to demonstrate several techniques that can be applied using the QGIS processing framework. This lesson uses some interpolation algorithms that were already introduced, but has a different approach.

The data for this lesson contains also a points layer, in this case with elevation data. We are going to interpolate it much in the same way as we did in the previous lesson, but this time we will save part of the original data to use it for assessing the quality of the interpolation process.

First, we have to rasterize the points layer and fill the resulting no—data cells, but using just a fraction of the points in the layer. We will save 10% of the points for a later check, so we need to have 90% of the points ready for the interpolation. To do so, we could use the *Split shapes layer randomly* algorithm, which we have already used in a previous lesson, but there is a better way to do that, without having to create any new intermediate layer. Instead of that, we can just select the points we want to use for the interpolation (the 90% fraction), and then run the algorithm. As we have already seen, the rasterizing algorithm will use only those selected points and ignore the rest. The selection can be done using the *Random selection* algorithm. Run it with the following parameters.




That will select 90% of the points in the layer to rasterize



The selection is random, so your selection might differ from the selection shown in the above image.


Now run the Rasterize algorithm to get the first raster layer, and then run the Close gaps algorithm to fill the

no-data cells [Cell resolution: 100 m].




To check the quality of the interpolation, we can now use the points that are not selected. At this point, we know the real elevation (the value in the points layer) and the interpolated elevation (the value in the interpolated raster layer). We can compare the two by computing the differences between those values.

Since we are going to use the points that are not selected, first, let's invert the selection.




The points contain the original values, but not the interpolated ones. To add them in a new field, we can use the

Add raster values to points algorithm




The raster layer to select (the algorithm supports multiple raster, but we just need one) is the resulting one from the interpolation. We have renamed it to *interpolate* and that layer name is the one that will be used for the name of the field to add.

Now we have a vector layer that contains both values, with points that were not used for the interpolation.




Now, we will use the fields calculator for this task. Open the *Field calculator* algorithm and run it with the following parameters.




If your field with the values from the raster layer has a different name, you should modify the above formula accordingly. Running this algorithm, you will get a new layer with just the points that we haven't used for the interpolation, each of them containing the difference between the two elevation values.

Representing that layer according to that value will give us a first idea of where the largest discrepancies are found.



Interpolating that layer will get you a raster layer with the estimated error in all points of the interpolated area.



You can also get the same information (difference between original point values and interpolated ones) directly with  $GRASS \rightarrow v.sample$ .


Your results might differ from these ones, since there is a random component introduced when running the random selection, at the beginning of this lesson.

# 18.24 Iterative execution of algorithms

**Muista:** This lesson shows a different way of executing algorithms that use vector layers, by running them repeatedly, iterating over the features in an input vector layer

We already know the graphical modeler, which is one way of automating processing tasks. However, in some situations, the modeler might not be what we need to automate a given task. Let's see one of those situations and how to easily solve it using a different functionality: the iterative execution of algorithms.


Open the data corresponding to this chapter. It should look like this.



You will recognize our well-known DEM from previous chapters and a set of watersheds extracted from it. Imagine that you need to cut the DEM into several smaller layers, each of them containing just the elevation data corresponding to a single watershed. That will be useful if you later want to calculate some parameters related to each watershed, such as its mean elevation or it hypsographic curve.

This can be a lengthy and tedious task, especially if the number of watersheds is large. However, it is a task that can be easily automated, as we will see.

The algorithm to use for clipping a raster layer with a polygon layer is called *Clip raster with polygons*, and has the following parameters dialog.




You can run it using the watersheds layer and the DEM as input, and you will get the following result.




As you can see, the area covered by all the watershed polygons is used.

You can have the DEM clipped with just a single watershed by selecting the desired watershed and then running

the algorithm as we did before.




Since only selected features are used, only the selected polygon will be used to crop the raster layer.



Doing this for all the watersheds will produce the result we are looking for, but it doesn't look like a very practical way of doing it. Instead, let's see how to automate that *select and crop* routine.


First of all, remove the previous selection, so all polygons will be used again. Now open the *Clip raster with polygon* algorithm and select the same inputs as before, but this time click on the button that you will find in the



right-hand side of the vector layer input where you have selected the watersheds layer.

This button will cause the selected input layer to be split into as many layer as feature are found in it, each of them containing a single polygon. With that, the algorithm will be called repeatedly, one for each one of those single-polygon layers. The result, instead of just one raster layer in the case of this algorithm, will be a set of raster layers, each one of them corresponding to one of the executions of the algorithm.

Here's the result that you will get if you run the clipping algorithm as explained.



For each layer, the black and white color palette, (or whatever palette you are using), is adjusted differently, from its minimum to its maximum values. That's the reason why you can see the different pieces and the colors do not seem to match in the border between layers. Values, however, do match.

If you enter an output filename, resulting files will be named using that filename and a number corresponding to each iteration as suffix.

# 18.25 More iterative execution of algorithms

Muista: This lesson shows how to combine the iterative execution of algorithms with the modeler to get more automation.


The iterative execution of algorithms is available not just for built-in algorithms, but also for the algorithms that you can create yourself, such as models. We are going to see how to combine a model and the iterative execution of algorithms, so we can obtain more complex results with ease.

The data the we are going to use for this lesson is the same one that we already used for the last one. In this case, instead of just clipping the DEM with each watershed polygon, we will add some extra steps and calculate a hypsometric curve for each of them, to study how elevation is distributed within the watershed.


Since we have a workflow that involves several steps (clipping + computing the hypsometric curve), we should go to the modeler and create the corresponding model for that workflow.

You can find the model already created in the data folder for this lesson, but it would be good if you first try to create it yourself. The clipped layer is not a final result in this case, since we are just interested in the curves, so this model will not generated any layers, but just a table with the curve data.

The model should look like this:




Add the model to you models folder, so it is available in the toolbox, and now execute it.




Select the DEM and watersheds basins, and do not forget to toggle the button that indicates that the algorithm has to be run iteratively.

The algorithm will be run several times, and the corresponding tables will be created and open in your QGIS project.



We can make this example more complex by extending the model and computing some slope statistics. Add the *Slope*, *aspect*, *curvature* algorithm to the model, and then the *Raster statistics* algorithm, which should use the slope output as its only input.



If you now run the model, apart from the tables you will get a set of pages with statistics. These pages will be available in the results dialog.


# 18.26 The batch processing interface

**Muista:** This lesson introduces the batch processing interface, which allows to execute a single algorithm with a set of different input values.


Sometimes a given algorithm has to be executed repeteadly with different inputs. This is, for instance, the case when a set of input files have to be converted from one format to another, or when several layers in a given

projection must be converted into another projection.

In that case, calling the algorithm repeatedly on the toolbox is not the best option. Instead, the batch processing interface should be used, which greatly simplifies performing a multiple execution of a given algorithm. To run an algorithm as a batch process, find it in the toolbox, and instead of double–clicking on it, right–click on it and select *Run as batch process*.



For this example, we will use the *Reproject algorithm*, so find it and do as described above. You will get to the following dialog.




If you have a look at the data for this lesson, you will see that it contains a set of three shapefiles, but no QGIS project file. This is because, when an algorithm is run as a batch process, layer inputs can be selected either from the current QGIS project or from files. That makes it easier to process large amounts of layers, such as, for instance, all the layers in a given folder.

Each row in the table of the batch processing dialog represents a single execution of the algorithm. Cells in a row correspond to the parameter needed by the algorithm, which are not arranged one above the other, as in the normal single–execution dialog, but horizontally in that row.


Defining the batch process to run is one by filling the table with the corresponding values, and the dialog itself contains several tools to make this task easier.

Let's start filling the fields one by one. The first column to fill is the *Input layer* one. Instead of entering the names of each one of the layers we want to process, you can select all of them and let the dialog put one in each row. Click on the button in the upper-left cell, and in the file selection dialog that will popup, select the three files to reproject. Since only one of them is needed for each row, the remaining ones will be used to fill the rows underneath.




The default number of rows is 3, which is exactly the number of layers we have to convert, but if you select more layers, new rows will be added automatically. If you want to fill the entries manually, you can add more rows using the *Add row* button.

We are going to convert all those layers to the EPSG:23029 CRS, so we have to select that CRS in the second field. We want the same on for all rows, but we do not have to do it for every single row. Instead, set that CRS for the first row (the one at the top) using the button in the corresponding cell, and then double click on the column header. That causes all the cells in the column to be filled using the value of the top cell.




Finally, we have to select an output file for each execution, which will contain the corresponding reprojected layer. Once again, let's do it just for the first row. Click on the button in the upper cell and, in a folder where you want to put your output files, enter a filename (for instance, reprojected.shp).

Now, when you click *OK* on the file selection dialog, the file does not automatically gets written to the cell, but an input box like the following one is shown instead.



If you select the first option, only the current cell will be filled. If you select any of the other ones, all the rows below will be filled with a given pattern. In this case, we are going to select the *Fill with parameter value* option, and then the *Input Layer* value in the drop down menu below. That will cause the value in the *Input Layer* (that is, the layer name) to be added to the filename we have added, making each output filename different. The batch processing table should now look like this.



The last column sets whether or not to add the resulting layers to the current QGIS project. Leave the default *Yes* option, so you can see your results in this case.

Click on *OK* and the batch process will be run. If everything went fine, all your layers will have been processed, and 3 new layers would have been created.

# 18.27 Models in the batch processing interface

Varoitus: Beware, this chapter is not well tested, please report any issue; images are missing

**Muista:** This lesson shows another example of the batch processing interface, but this time using a model instead of a built-in algorithm

Models are just like any other algorithm, and they can be used in the batch processing interface. To demonstrate that, here is a brief example that we can do using our already well-known hydrological model.

Make sure you have the model added to your toolbox, and then run it in batch mode. This is what the batch processing dialog should look like.

```
Varoitus: todo: Add image
```

Add rows up to a total of 5. Select the DEM file corresponding to this lesson as the input for all of them. Then enter 5 different threshold values as shown next.

```
Varoitus: todo: Add image
```

As you see the batch processing interface can be run not just to run the same process on different datasets but also on the same dataset with different parameters.

Click on OK and you should get 5 new layers with watersheds corresponding to the specified 5 threshold values.

# 18.28 Pre- and post-execution script hooks

**Muista:** This lesson shows how to use pre- and post-execution hooks, which allow to perform additional operations before and after actual processing.

Pre- and post-execution hooks are Processing scripts that run before and after actual data processing is performed. This can be used to automate tasks that should be performed whenever an algorithm is executed.

The syntax of the hooks is identical to the syntax of Processing scripts, see the corresponding chapter in the QGIS User Guide for more details.

In addition to all scripts features, in hooks you can use a special global variable named alg, which represents the algorithm that has just been (or is about to be) executed.

Here is an example post-execution script. By default, Processing stores analysis results in temporary files. This script will copy outputs to a specific directory, so they won't be deleted after closing QGIS.

```
import os
import shutil
from processing.core.outputs import OutputVector, OutputRaster, OutputFile
MY_DIRECTORY = '/home/alex/outputs'

for output in alg.outputs:
    if isinstance(output, (OutputVector, OutputRaster, OutputFile)):
        dirname = os.path.split(output.value)[0]
        shutil.copytree(dirname, MY_DIRECTORY)
```

In the first two lines we import the required Python packages: os — for path manipulations, e.g. extracting file name, and shutil — for various filesystem operations like copying files. In the third line we import Processing outputs. This will be explained in more detail later in this lesson.

Then we define a MY\_DIRECTORY constant, which is the path to the directory where we want to copy analysis results.

At the end of the script, we have the main hook code. In the loop we iterate over all algorithm outputs and check if this output is a file-based output and can be copied. If so, we determine top-level directory in which output files are located and then copy all files to our directory.

To activate this hook we need to open the Processing options, find the entry named *Post-execution script file* in the *General* group, and specify the filename of the hook script there. the specified hook will be executed after each Processing algorithm.

In a similar way, we can implement pre-execution hooks. For example, let's create a hook to check input vectors for geometry errors.

```
from qgis.core import QgsGeometry, QgsFeatureRequest
from processing.core.parameters import ParameterVector

for param in alg.parameters:
    if isinstance(param, ParameterVector):
        layer = processing.getObject(param.value)
        for f in layer.getFeatures(QgsFeatureRequest().setSubsetOfAttributes([])):
        errors = f.geometry().validateGeometry()
        if len(errors) > 0:
            progress.setInfo('One of the input vectors contains invalid geometries!')
```

As in the previous example, first we import required QGIS and Processing packages.

Then we iterate over all the algorithm parameters and if a ParameterVector parameter is found, we get the corresponding vector layer object from it. We loop over all the features of the layer and check them for geometry errors. If at least one feature contains an invalid geometry, we print a warning message.

To activate this hook we need enter its filename in the *Pre-execution script file* option in the Processing configuration dialog. The hook will be executed before running any Processing algorithm.

# 18.29 Other programs

Module contributed by Paolo Cavallini - Faunalia

**Muista:** This chapter shows how to use additional programs from inside Processing. To complete it, you must have installed, with the tools of your operating system, the relevant packages.

### 18.29.1 GRASS

GRASS is a free and open source GIS software suite for geospatial data management and analysis, image processing, graphics and maps production, spatial modeling, and visualization.

It is installed by default on Windows through the OSGeo4W standalone installer (32 and 64 bit), and it is packaged for all major Linux distributions.

#### 18.29.2 R

R is a free and open source software environment for statistical computing and graphics.

It has to be installed separately, together with a few necessary libraries (LIST).

The beauty of Processing implementation is that you can add your own scripts, simple or complex ones, and they may then be used as any other module, piped into more complex workflows, etc.

Test some of the preinstalled examples, if you have R already installed (remember to activate R modules from the General configuration of Processing).

### 18.29.3 OTB

OTB (also known as Orfeo ToolBox) is a free and open source library of image processing algorithms. It is installed by deafult on Windows through the OSGeo4W standalone installer (**NB: 32 bit only**). Paths should be configured in Processing.

In a standard OSgeo4W Windows installation, the paths will be:

```
OTB application folder C:\OSGeo4W\apps\orfeotoolbox\applications OTB command line tools folder C:\OSGeo4W\bin
```

On Debian and derivatives, it will be /usr/bin

### 18.29.4 Others

TauDEM is a suite of Digital Elevation Model (DEM) tools for the extraction and analysis of hydrologic information. Availability in various operating system varies.

LASTools is a set of mixed, free and proprietary commands to process and analyze LiDAR data. Availability in various operating system varies.

More tools are available through additional plugins, e.g.:

- LecoS: a suite for land cover statistics and landscape ecology
- lwgeom: formerly part of PostGIS, this library brings a few useful tools for geometry cleanup
- Animove: tools to analyse the home range of animals.

More will come.

## 18.29.5 Comparison among backends

#### **Buffers and distances**

Let's load points. shp and type buf in the filter of the Toolbox, then double click on:

- Fixed distance buffer: Distance 10000
- Variable distance buffer: Distance field SIZE
- v.buffer.distance: distance 10000
- v.buffer.column: bufcolumn SIZE
- Shapes Buffer: fixed value 10000 (dissolve and not), attribute field (with scaling)

See how speed is quite different, and different options are available.

Exercise for the reader: find the differences in geometry output between different methods.

Now, raster buffers and distances:

- first, load and rasterize the vector rivers.shp with *GRASS*  $\rightarrow$  *v.to.rast.value*; **beware:** cell size must be set to 100 m, otherwise the computation time will be enormous; resulting map will have 1 and NULLs
- same, with  $SAGA \rightarrow Shapes \ to \ Grid \rightarrow COUNT$  (resulting map: 6 to 60)
- then, *proximity* (value= 1 for GRASS, a list of rivers ID for SAGA), *r.buffer* with parameters 1000,2000,3000, *r.grow.distance* (the first of the two maps; the second will show the areas pertaining to each river, if done on the SAGA raster).

#### **Dissolve**

Dissolve features based on a common attribute:

- $GRASS \rightarrow v.dissolve$  municipalities.shp on PROVINCIA
- $QGIS \rightarrow Dissolve$  municipalities.shp on PROVINCIA
- OGR o Dissolve municipalities.shp on PROVINCIA
- $SAGA \rightarrow Polygon\ Dissolve\$ municipalities.shp on PROVINCIA (NB: Keep inner boundaries must be unselected)

**Muista:** The last one is broken in SAGA <=2.10

Exercise for the reader: find the differences (geometry and attributes) between different methods.

# 18.30 Interpolation and contouring

Module contributed by Paolo Cavallini - Faunalia

Muista: This chapter shows how to use different backends to calculate different interpolations.

### 18.30.1 Interpolation

The project shows a gradient in rainfall, from south to north. Let's use different methods for interpolation, all based on vector points.shp, parameter RAIN:

Varoitus: Set cell size to 500 for all analyses.

- $GRASS \rightarrow v.surf.rst$
- $SAGA \rightarrow Multilevel B$ -Spline Interpolation
- *SAGA* → *Inverse Distance Weighted* [Inverse distance to a power; Power: 4; Search radius: Global; Search range: all points]
- *GDAL* → *Grid* (*Inverse Distance to a power*) [Power:4]
- *GDAL* → *Grid* (*Moving average*) [Radius1&2: 50000]

Then measure variation among methods and correlate it with distance to points:

- *GRASS* → *r.series* [Unselect Propagate NULLs, Aggregate operation: stddev]
- $GRASS \rightarrow v.to.rast.value$  on points.shp
- $GDAL \rightarrow Proximity$
- $GRASS \rightarrow r.covar$  to show the correlation matrix; check the significance of the correlation e.g. with http://vassarstats.net/rsig.html.

Thus, areas far from points will have less accurate interpolation.

#### 18.30.2 Contour

Various methods to draw contour lines [always step= 10] on the stddev raster:

- $GRASS \rightarrow r.contour.step$
- $GDAL \rightarrow Contour$
- $SAGA \rightarrow Contour\ lines\ from\ grid\ [NB:\ in\ some\ older\ SAGA\ versions,\ output\ shp\ is\ not\ valid,\ known\ bug]$

# 18.31 Vector simplification and smoothing

Module contributed by Paolo Cavallini - Faunalia

Muista: This chapter shows how simplify vectors, and smooth out sharp corners.

Sometimes we need a simplified version of a vector, to have a smaller file size and get rid of unnecessary details. Many tools do this in a very rough way, and miss the adjacency and sometimes the topological correctness of polygons. GRASS is the ideal tool for this: being a topological GIS, adjacency and correctness are preserved even at very high simplification levels. In our case, we have a vector resulting from a raster, thus showing a "saw" pattern at borders. Applying a simplification results in straight lines:

• GRASS → v.generalize [Maximal tolerance value: 30 m]

We can also do the reverse, and make a layer more complex, smoothing out sharp corners:

•  $GRASS \rightarrow v.generalize$  [method: chaiken]

Try to apply this second command both to original vector and to the one from the first analysis, and see the difference. Note that adjacency is not lost.

This second option can be applied e.g. to contour lines resulting from a coarse raster, to GPS tracks with sparse vertices, etc.

# 18.32 Planning a solar farm

Module contributed by Paolo Cavallini - Faunalia

**Muista:** This chapter shows how to use several criteria to locate the areas suitable for installing a photovoltaic power station

First of all, create an aspect map from DTM:

•  $GRASS \rightarrow r.aspect$  [Data type: int; cell size:100]

In GRASS, aspect is calculated in degrees, counterclockwise starting from East. To extract only South facing slopes (270 degrees +- 45), we can reclassify it:

• GRASS → r.reclass

with the following rules:

```
225 thru 315 = 1 south * = NULL
```

You can use the text file reclass\_south.txt provided. Note that with these simple text files we can create also very complex reclassifications.

We want to build a large farm, so we select only large (> 100 ha) contiguous areas:

•  $GRASS \rightarrow r.reclass.greater$ 

Finally, we convert to a vector:

• *GRASS* → *r.to.vect* [Feature type: area; Smooth corners: yes]

Exercise for the reader: repeat the analysis, replacing GRASS commands with analogous from other programs.

# 18.33 Use R scripts in Processing

Module contributed by Matteo Ghetta - funded by Scuola Superiore Sant' Anna


Processing allows to write and run R scripts inside QGIS.

**Varoitus:** R has to be installed on your computer and the PATH has to correctly set up. Moreover Processing just calls the external R packages, it is not able to install them. So be sure to install external packages directly in R. See the related *chapter* in the user manual.

**Muista:** If you have some *packages* problem, maybe it is related to missing *mandatory* packages required by Processing, like sp, rgdal and raster.


## 18.33.1 Adding scripts

Adding a script is very simple. Open the Processing toolbox and just click on the  $R \to Tools \to Create\ new\ R$  script.



**Muista:** If you cannot see R in Processing, you have to activate it in  $Processing \rightarrow Options \rightarrow Providers$ 

It opens a script editor window in which you have to specify some parameters before you can add the script body.



## 18.33.2 Creating plots

In this tutorial we are going to create a **boxplot** of a vector layer field.

Open the r\_intro.qgs QGIS project under the exercise\_data/processing/r\_intro/ folder.

### **Script parameters**

Open the editor and start writing at the beginning of it.

You **must** specify some parameters **before** the script body:

1. the name of the group in which you want to put your script:

```
##plots=group
```

so you will find your script in the **plots** group in the Processing toolbox.

2. you have to tell Processing that you want to display a plot (just in this example):

```
##showplots
```

this way in the **Result Viewer** of Processing you'll see the plot.

3. You need also to tell Processing with which kind of data you are working with. In this example we want to create a plot from a field of a vector layer:

```
##Layer=vector
```

Processing knows now that the input is a vector. The name *Layer* is not important, what matters is the **vector** parameter.

4. Finally, you have to specify the input field of the vector layer you want to plot:

```
##X=Field Layer
```

So Processing knows that you have called **X** the **Field Layer**.

### **Script body**

Now that you have set up the *heading* of the script you can add the function:


boxplot(Layer[[X]])

Notice that **boxplot** is the name of the R function itself that calls **Layer** as dataset and **X** as the field of the dataset.

**Varoitus:** The parameter **X** is within a double square bracket [[]]

### The final script looks like this:


```
##Vector processing=group
##showplots
##Layer=vector
##X=Field Layer
boxplot(Layer[[X]])
```




Save the script in the default path suggested by Processing. The name you choose will be the same as the name of the script you'll find in the Processing toolbox.

**Muista:** You can save the script in other paths, but Processing isn't able to upload them automatically and you have to upload all the scripts manually

Now just run it using the button on the top of the editor window:




Otherwise, once the editor window has been closed, use the text box of Processing to find your script:



You are now able to fill the parameters required in the Processing algorithm window:


- as Layer choose the sample points one
- fill the  $\boldsymbol{X}$  field with the **value** parameter

Click on Run.



The **Result window** should be automatically opened, if not, just click on  $Processing \rightarrow Result\ Viewer...$ 

This is the final result you'll see:



Muista: You can open, copy and save the image by right clicking on the plot

### 18.33.3 Create a vector

With an R script you can also create a vector and automatically load it in QGIS.

The following example has been taken from the Random sampling grid script that you can download from the online collection  $R \to Tools \to Download\ R$  scripts from the on-line collection.

The aim of this exercise is to create a random point vector in a layer extent using the spsample function of the sp package.

### **Script parameters**

As before we have to set some parameters before the script body:

1. specify the name of the group in which you want to put your script, for example Point pattern analysis:

```
##Point pattern analysis=group
```

2. set the layer that will contain the random points:

```
##Layer=vector
```

3. set the number of points that are going to be created:

##Size=number 10

**Muista:** 10 is going to be the default value. You can change this number or you can leave the parameter without a default number

4. specify that the output is a vector layer:

```
##Output= output vector
```

### **Script body**

Now you can add the body of the function:

1. run the spsample function:

```
pts=spsample(Layer, Size, type="random")
```


this way the function takes the extent of the *Layer*, the number of points is taken from the *Size* parameter and the point generation is *random* 

2. Write the line that contains the parameters of the output:

```
Output=SpatialPointsDataFrame(pts, as.data.frame(pts))
```


### The final script looks like this:

```
##Point pattern analysis=group
##Layer=vector
##Size=number 10
##Output= output vector
pts=spsample(Layer,Size,type="random")
Output=SpatialPointsDataFrame(pts, as.data.frame(pts))
```




Save it and run it, clicking on the running button.

In the new window type in the right parameters:



and click on run.

Resulting points will be displayed in the map canvas



#### 18.33.4 R - Processing syntax

Beware that Processing uses some special syntax to get the results out of R:

- > before your command, as in >lillie.test (Layer[[Field]]) means the result should be sent to R output (Result viewer)
- + after a plot to call overlay plots. For example plot(Layer[[X]], Layer[[Y]]) + abline(h=mean(Layer[[X]]))

## 18.34 R Syntax in Processing scripts

Module contributed by Matteo Ghetta - funded by Scuola Superiore Sant' Anna

Writing R scripts in Processing could be quite tricky because of the syntax that has to be adopted.

Each script starts with the **Input** and **Output** preceded with ##.

#### 18.34.1 Inputs

Before you specify teh inputs you can also set the algorithm group in which your script will be put. If the group already exists, the algorithm will be added to the other, else a new group will be automatically created:

```
1. group creation, ##My Group=group
```

7. boolean, ##Bol = boolean

Then you have to specify all the input types and eventually the additional parameters. You can have different inputs:

```
    vector, ##Layer = vector
    vector Field, ##F = Field Layer (where Layer is the name of the input Layer)
    raster, ##r = raster
    table, ##t = table
    number, ##Num = number
    string, ##Str = string
```

you can also have a dropdown menu with all the parameters you want; the items must be separated with semicolons ;:

```
8. ##type=selection point; lines; point+lines
```

#### 18.34.2 Outputs

As for the inputs, each output has to be defined at the beginning of the script:

```
    vector, ##output= output vector
    raster, ##output= output raster
    table, ##output= output table
    plots, ##showplots
```

5. R output in the Result Viewer, just put inside the script > before the output you want to display

#### 18.34.3 Script body

The script body follows an R style syntax and the **Log** panel can help you if something went wrong with your script.

Remember that in the script you have to load all the additional libraries:

```
library(sp)
```

#### **Example with vector output**

Let's take an algorithm from the online collection that creates random points from the extent of an input layer:

```
##Point pattern analysis=group
##Layer=vector
##Size=number 10
##Output= output vector
library(sp)
pts=spsample(Layer,Size,type="random")
Output=SpatialPointsDataFrame(pts, as.data.frame(pts))
```

#### and get through the lines:

- 1. Point pattern analysis is the group of the algorithm
- 2. Layer is the input vector layer
- 3. Size is the **numerical** parameter with a default value of 10
- 4. Output is the vector layer that will be created by the algorithm
- 5. library (sp) loads the **sp** library (that should be already installed in your computer and that installation has to be made **in R**)
- 6. call the spsample function of the sp library and pass it to all the input defined above
- 7. create the output vector with the <code>SpatialPointsDataFrame</code> function

That's it! Just run the algorithm with a vector layer you have in the QGIS Legend, choose a number of the random point and you will get them in the QGIS Map Canvas.

#### **Example with raster output**

The following script will perform a basic ordinary kriging and will create a raster map of the interpolated values:

```
##Basic statistics=group
##Layer=vector
##Field=Field Layer
##Output=output raster
require("automap")
require("sp")
require("raster")
table=as.data.frame(Layer)
coordinates(table)= ~coords.x1+coords.x2
c = Layer[[Field]]
kriging_result = autoKrige(c~1, table)
prediction = raster(kriging_result$krige_output)
Output<-prediction</pre>
```

from a vector and its field in input the algorithm will use the  $\mathtt{autoKrige}$  function of the  $\mathtt{automap}$  R package and it will first calculate the kriging model and then create a raster.

The raster is created with the raster function of the raster R package.

#### **Example with table output**

Let's edit the Summary Statistics algorithm so that the output is a table file (csv).

The script body is the following:

```
##Basic statistics=group
##Layer=vector
##Field=Field Layer
##Stat=Output table
Summary_statistics<-data.frame(rbind(
sum(Layer[[Field]]),
length(Layer[[Field]]),
length(unique(Layer[[Field]])),
min(Layer[[Field]]),
max(Layer[[Field]]),
max(Layer[[Field]])-min(Layer[[Field]]),
mean(Layer[[Field]]),
median(Layer[[Field]]),
sd(Layer[[Field]])),row.names=c("Sum:","Count:","Unique values:","Minimum value:","Maximum value:
colnames (Summary_statistics) <-c (Field)</pre>
Stat<-Summary_statistics
```

The third line specifies the **Vector Field** in input and the fourth line tells the algorithm that the output should be a table.

The last line will take the Stat object created in the script and convert it into a csv table.

#### **Example with console output**

We can take the previous example and instead of creating a table, print the result in the **Result Viewer**:

```
##Basic statistics=group
##Layer=vector
##Field=Field Layer
Summary_statistics<-data.frame(rbind(
sum(Layer[[Field]]),
length(Layer[[Field]]),
length(unique(Layer[[Field]])),
min(Layer[[Field]]),
max(Layer[[Field]]),
max(Layer[[Field]]),
max(Layer[[Field]]),
mean(Layer[[Field]]),
sd(Layer[[Field]]),
sd(Layer[[Field]])),row.names=c("Sum:","Count:","Unique values:","Minimum value:","Maximum value:
colnames(Summary_statistics)<-c(Field)
>Summary_statistics
```

The script is exactly the same of above with just 2 edits:

- 1. no more output specified (the fourth line has been removed)
- 2. the last line begins with > that tells Processing to print the object in the result viewer

#### **Example with plot**

Creating plots is very simple. You have to use the ##showplots parameter as the following script shows:

```
##Basic statistics=group
##Layer=vector
##Field=Field Layer
##showplots
```

```
qqnorm(Layer[[Field]])
qqline(Layer[[Field]])
```

the script takes a field of the vector layer in input and creates a QQ Plot to test the normality of the distribution.

The plot is automatically added to the Result Viewer of Processing.

## 18.35 R Syntax Summary table for Processing

Module contributed by Matteo Ghetta - funded by Scuola Superiore Sant' Anna

Processing allows a lot of different input and output parameter that can be used in the script body. Here a summary table:

### 18.35.1 Input parameters

| Parameter    | Syntax example          | Returning objects   |
|--------------|-------------------------|---|
| vector       | Layer = vector          | SpatialDataFrame object, default object of rgdal package        |
| vector point | Layer = vector point    | SpatialPointDataFrame object, default object of rgdal           |
|              |                         | package   |
| vector line  | Layer = vector line     | SpatialLineDataFrame object, default object of rgdal package    |
| vector       | Layer = vector polygon  | SpatialPolygonsDataFrame object, default object of rgdal        |
| polygon      |                         | package   |
| multiple     | Layer = multiple vector | SpatialDataFrame objects, default object of rgdal package       |
| vector       |                         |   |
| table        | Layer = table           | dataframe conversion from csv, default object of read.csv       |
|              |                         | function  |
| field        | Field = Field Layer     | name of the Field selected, e.g. "Area"                         |
| raster       | Layer = raster          | RasterBrick object, default object of raster package            |
| multiple     | Layer = multiple raster | RasterBrick objects, default object of raster package           |
| raster       |                         |   |
| number       | N = number              | integer or floating number chosen                               |
| string       | S = string              | string added in the box   |
| longstring   | LS = longstring         | string added in the box, could be longer then the normal string |
| selection    | S = selection           | string of the selected item chosen in the dropdown menu         |
|              | first;second;third      |   |
| crs          | C = crs                 | string of the resulting CRS chosen, in the format:              |
|              |                         | "EPGS:4326"   |
| extent       | E = extent              | Extent object of the raster package, you can extract values as  |
|              |                         | E@xmin  |
| point        | P = point               | when clicked on the map, you have the coordinates of the point  |
| file         | F = file                | path of the file chosen, e.g. "/home/matteo/file.txt"           |
| folder       | F = folder              | path of the folder chosen, e.g. "/home/matteo/Downloads"        |

Any of the input could be also **OPTIONAL**, that means that you have a handy way to tell the script to ignore this parameter.

In order to set an input as optional, you just have to add the string optional before the input, e.g.

```
##Layer = vector
##Field1 = Field Layer
##Field2 = optional Field Layer
```

#### 18.35.2 Output parameters

Output parameters take the Input names you gave at the beginning of the script and write the object you want.

| Parameter | Syntax example         |  |
|-----------|------------------------|--|
| vector    | Output = output vector |  |
| raster    | Output = output raster |  |
| table     | Output = output table  |  |
| file      | Output = output file   |  |

**Muista:** for the plot input type, you can save the plot as png directly from the *Processing Result Viewer* or you can choose to save the plot directly from the algorithm interface.

#### **18.35.3 Examples**

In order to better understand all the input and output parameters, please have a look at the R Syntax chapter.

## 18.36 Predicting landslides

Module contributed by Paolo Cavallini - Faunalia

Muista: This chapter shows how to create an oversimplified model to predict the probability of landslides.

First, we calculate slope (choose among various backends; the interested reader can calculate the difference between the outputs):

- $GRASS \rightarrow r.slope$
- $SAGA \rightarrow Slope$ , Aspect, Curvature
- GDAL Slope

Then we create a model of predicted rainfall, based on the interpolation of rainfall values at meteo stations:

•  $GRASS \rightarrow v.surf.rst$  (resolution: 500 m)

The probability of a landslide will be very roughly related to both rainfall and slope (of course a real model will use more layers, and appropriate parameters), let's say (rainfall \* slope )/100:

- $SAGA \rightarrow Raster\ calculator\ rain,\ slope:\ (a*b)/100\ (or:\ GRASS \rightarrow r.mapcalc)$
- then let's calculate what are the municipalities with the greatest predicted risk of rainfall: SAGA → Raster statistics with polygons (the parameters of interest are Maximum and Mean)

## Module: Using Spatial Databases in QGIS

In this module you will learn about how to use Spatial Databases with QGIS to manage, display and manipulate data in the database as well as performing analysis by querying. We will primarily use PostgreSQL and Post-GIS (which were covered in previous sections), but the same concepts are applicable to other spatial database implementations including spatialite.

### 19.1 Lesson: Working with Databases in the QGIS Browser


In the previous 2 modules we looked at the basic concepts, features and functions of relational databases as well as extensions that let us store, manage, query and manipulate spatial data in a relational database. This section will dive deeper into how to effectively use spatial databases in QGIS.

The goal for this lesson: To learn how to interact with spatial databases using the QGIS Browser interface.


## 19.1.1 Follow Along: Adding Database Tables to QGIS using the Browser

We have already briefly looked at how to add tables from a database as QGIS layers, now lets look at this in a bit more detail and look at the different ways this can be done in QGIS. Lets start by looking at the new Browser interface.

- Start a new empty map in QGIS.
- Open the Browser by clicking the Browser tab at the bottom of the Layer Panel
- Open the PostGIS portion of the tree and you should find your previously configured connection available (you may need to click the Refresh button at the top of the browser window).



- Double clicking on any of the table/layers listed here will add it to the Map Canvas.
- Right Clicking on a table/layer in this view will give you a few options. Click on the *Properties* item to look at the properties of the layer.




**Muista:** Of course you can also use this interface to connect to PostGIS databases hosted on a server external to your workstation. Right clicking on the PostGIS entry in the tree will allow you to specify connection paramaters for a new connection.

## 19.1.2

## Follow Along: Adding a filtered set of records as a Layer

Now that we have seen how to add an entire table as a QGIS layer it might be nice to learn how to add a filtered set of records from a table as a layer by using queries that we learned about in previous sections.

- Start a new empty map with no layers
- Click the *Add PostGIS Layers* button or select  $Layer \rightarrow Add PostGIS Layers$  from the menu.
- In the Add PostGIS Table(s) dialog that comes up, connect to the postgis\_demo connection.
- Expand the public schema and you should find the three tables we were working with previously.
- Click the lines layer to select it, but instead of adding it, click the *Set Filter* button to bring up the *Query Builder* dialog.
- Construct the following expression using the buttons or by entering it directly:
  - "roadtype" = 'major'



• Click *OK* to complete editing the filter and click *Add* to add the filtered layer to your map.

• Rename the lines layer in the tree to roads\_primary.

You will notice that only the Primary Roads have been added to your map rather than the entire layer.

#### 19.1.3 In Conclusion

You have seen how to interact with spatial databases using the QGIS Browser and how to add layers to your map based on a query filter.

#### 19.1.4 What's Next?

Next you'll see how to work with the DB Manager interface in QGIS for a more complete set of database management tasks.

# 19.2 Lesson: Using DB Manager to work with Spatial Databases in QGIS

We have already seen how to perform many database operations with QGIS as well as with other tools, but now it's time to look at the DB Manager tool which provides much of this same functionality as well as more management oriented tools.

The goal for this lesson: To learn how to interact with spatial databases using the QGIS DB Manager.


## 19.2.1 Follow Along: Managing PostGIS Databases with DB Manager

You should first open the DB Manager interface by selecting *Database -> DB Manager -> DB Manager* on the menu or by selecting the DB Manager icon on the toolbar.



You should already see the previous connections we have configured and be able to expand the myPG section and its public schema to see the tables we have worked with in previous sections.


The first thing you may notice is that you can now see some metadata about the Schemas contained in your database.



Schemas are a way of grouping data tables and other objects in a PostgreSQL database and a container for permissions and other constraints. Managing PostgreSQL schemas is beyond the scope of this manual, but you can find more information about them in the PostgreSQL documentation on Schemas. You can use the DB Manager to create new Schemas, but will need to use a tool like pgAdmin III or the command line interface to manage them effectively.


DB Manager can also be used to manage the tables within your database. We have already looked at various ways to create and manage tables on the command line, but now lets look at how to do this in DB Manager.

First, its useful to just look at a table's metadata by clicking on its name in tree and looking in the Info tab.




In this panel you can see the *General Info* about the table as well the information that the PostGIS extension maintains about the geometry and spatial reference system.

If you scroll down in the *Info* tab, you can see more information about the *Fields*, *Constraints* and *Indexes* for the table you are viewing.



Its also very useful to use DB Manager to simply look at the records in the database in much the same way you might do this by viewing the attribute table of a layer in the Layer Tree. You can browse the data by selecting the *Table* tab.




There is also a *Preview* tab which will show you the layer data in a map preview.

Right-clicking on a layer in the tree and clicking Add to Canvas will add this layer to your map.


So far we have only been viewing the database its schemas and tables and their metadata, but what if we wanted to alter the table to add an additional column perhaps? DB Manager allows you to do this directly.

- Select the table you want to edit in the tree
- Select  $Table \rightarrow Edit\ Table$  from the menu to open the  $Table\ Properties\ dialog$ .




You can use this dialog to Add Columns, Add geometry columns, edit existing columns or to remove a column completely.

Using the *Constraints* tab, you can manage which fields are used as the primary key or to drop existing constraints.




The *Indexes* tab can be used to add and delete both spatial and normal indexes.



## 19.2.2 Follow Along: Creating a New Table

Now that we have gone through the process of working with existing tables in our database, let's use DB Manager to create a new table.

- If it is not already open, open the DB Manager window, and expand the tree until you see the list of tables already in your databse.
- From the menu select *Table* -> *Create Table* to bring up the Create Table dialog.
- Use the default Public schema and name the table places.
- Add the id, place\_name, and elevation fields as shown below
- Make sure the id field is set as the primary key.
- Click the checkbox to *Create geometry column* and make sure it is set to a POINT type and leave it named geom and specify 4326 as the *SRID*.
- Click the checkbox to *Create spatial index* and click *Create* to create the table.



• Dismiss the dialog letting you know that the table was created and click *Close* to close the Create Table Dialog.

You can now inspect your table in the DB Manager and you will of course find that there is no data in it. From here you can *Toggle Editing* on the layer menu and begin to add places to your table.

## 19.2.3 Follow Along: Basic Database Administration

The DB Manager will also let you do some basic Database Administration tasks. It is certainly not a substitute for a more complete Database Administration tool, but it does provide some functionality that you can use to maintain your database.

Database tables can often become quite large and tables which are being modified frequently can end up leaving around remnants of records that are no longer needed by PostgreSQL. The *VACUUM* command takes care of doing a kind of garbage collection to compact and optional analyze your tables for better performance.

Lets take a look at how we can perform a VACUUM ANALYZE command from within DB Manager.

- Select one of your tables in the DB Manager Tree.
- Select  $Table \rightarrow Run\ Vacuum\ Analyze$  from the menu.

Thats it! PostgreSQL will perform the operation. Depending on how big your table is, this may take some time to complete.

You can find more information about the VACUUM ANALYZE process in the PostgreSQL Documentation on VACUUM ANALYZE



## Follow Along: Executing SQL Queries with DB Manager

DB Manager also provides a way for you to write queries against your database tables and to view the results. We have already seen this type of functionality in the *Browser* panel, but lets look at it again here with DB Manager.


- Select the lines table in the tree.
- Select the SQL window button in the DB Manager toolbar.




• Compose the following SQL query in the space provided:

```
select * from lines where roadtype = 'major';
```

- Click the *Execute (F5)* button to run the query.
- You should now see the records that match in the *Result* panel.



- Click the checkbox for *Load as new layer* to add the results to your map.
- Select the id column as the *Column with unique integer values* and the geom column as the *Geometry column*.
- Enter roads\_primary as the Layer name (prefix).
- Click Load now! to load the results as a new layer into your map.



The layers that matched your query are now displayed on your map. You can of course use this query tool to execute any arbitrary SQL command including many of the ones we looked at in previous modules and sections.


#### 19.2.5 Importing Data into a Database with DB Manager

We have already looked at how to import data into a spatial database using command line tools, so now let's learn how to use DB Manager to do imports.

• Click the Import layer/file button on the toolbar in the DB Manager dialog.




- Select the urban\_33S.shp file from exercise\_data/projected\_data as the input dataset.
- Click the *Update Options* button to pre-fill some of the form values.
- Make sure that the Create new table option is selected
- Specify the *Source SRID* as 32722 and the *Target SRID* as 4326.
- Enable the checkbox to Create Spatial Index
- Click *OK* to perform the import.



- Dismiss the dialog letting you know that the import was successful
- Click the *Refresh* button on the DB Manager Toolbar.

You can now inspect the table in your database by clicking on it in the Tree. Verify that the data has been reprojected by checking that the *Spatial ref*: is listed as WGS 84 (4326)




Right clicking on the table in the Tree and a selecting Add to Canvas will add the table as a layer in your map.

#### 19.2.6 Exporting Data from a Database with DB Manager


Of course DB Manager can also be used to export data from your spatial databases, so lets take a look at how that is done.

- Select the lines layer in the Tree and click the *Export to File* button on the toolbar to open the *Export to vector file* dialog.
- Click the ... button to select the *Output file* and save the data to your exercise\_data directory as urban\_4326.
- Set the *Target SRID* as 4326.
- Click *OK* to initialize the export.



• Dismiss the dialog letting you know the export was successful and close the DB Manager.

You can now inspect the shapefile you created with the Browser panel.



#### 19.2.7 In Conclusion

You have now seen how to use the DB Manager interface in QGIS to Manage your spatial databases, to execute sql queries against your data and how to import and export data.

#### 19.2.8 What's Next?

Next, we will look at how to use many of these same techniques with *spatialite* databases.

### 19.3 Lesson: Working with spatialite databases in QGIS

While PostGIS is generally used on a server to provide spatial database capabilities to multiple users at the same time, QGIS also supports the use of a file format called *spatialite* that is a lightweight, portable way to store an entire spatial database in a single file. Obviously, these 2 types of spatial databases should be used for different purposes, but the same basic principles and techniques apply to both. Let's create a new spatialite database and explore the functionality provided to work with these databases in QGIS.

The goal for this lesson: To learn how to interact with spatialite databases using the QGIS Browser interface.



Using the Browser panel, we can create a new spatialite database and get it setup for use in QGIS.


- Right click on the *Spatialite* entry in the Browser tree and select *Create Database*.
- Specify where on your filesystem you want to store the file and name it qqis-sl.db.
- Again right click on the *Spatialite* entry in the Browser tree and now select the *New Connection* item. Find the file you created in the last step and open it.

Now that you have configured your new database you will find that the entry in Browser tree has nothing underneath it and the only thing you can do at this point is to delete the connection. This is of course because we haven't added any tables to this database. Let's go ahead and do that.


• Find the button to create a new layer and use the dropdown to create a new new Spatialite layer, or select Layer → New → New Spatialite Layer.



- Select the database we created in the previous steps in the drop down.
- Give the layer the name places.
- Tick the checkbox next to Create an auto-incrementing primary key.
- Add 2 attributes as shown in below
- Click *OK* to create the table.



• Click the refresh button at the top of the Browser and you should now see your places table listed.



You can right click on the table and view its properties as we did in the previous exercise.

From here you can start an editing session and start adding data to your new database directly.

We also learned about how to import data into a database using the DB Manager and you can use this same technique to import data into your new spatialite DB.

#### 19.3.2 In Conclusion

You have seen how to create spatialite databases and add tables to them and to use these tables as layers in QGIS.

## **Appendix: Contributing To This Manual**

To add materials to this course, you must follow the guidelines in this Appendix. You are not to alter the conditions in this Appendix except for clarification. This is to ensure that the quality and consistency of this manual can be maintained.

## 20.1 Downloading Resources

The source of this document is available at GitHub. Consult GitHub.com for instructions on how to use the git version control system.

#### 20.2 Manual Format

This manual is written using Sphinx, a Python document generator using the reStructuredText markup language. Instructions on how to use these tools are available on their respective sites.

## 20.3 Adding a Module

- To add a new module, first create a new directory (directly under the top-level of the qgis-training-manual directory) with the name of the new module.
- Under this new directory, create a file called index.rst. Leave this file blank for now.
- Open the index.rst file under the top-level directory. Its first lines are:

```
.. toctree::
    :maxdepth: 2

foreword/index
    introduction/index
```

You will note that this is a list of directory names, followed by the name index. This directs the top-level index file to the index files in each directory. The order in which they are listed determines the order they will have in the document.

- Add the name of your new module (i.e., the name you gave the new directory), followed by /index, to this list, wherever you want your module to appear.
- Remember to keep the order of the modules logical, such that later modules build on the knowledge presented in earlier modules.
- Open your new module's own index file ([module name]/index.rst).
- Along the top of the page, write a line of 80 asterisks (\*). This represents a module heading.

- Follow this with a line containing the markup phrase | MOD | (which stands for "module"), followed by the name of your module.
- End this off with another line of 80 asterisks.
- Leave a line open beneath this.
- Write a short paragraph explaining the purpose and content of the module.
- Leave one line open, then add the following text:

```
.. toctree::
   :maxdepth: 2

lesson1
lesson2
```

... where lesson1, lesson2, etc., are the names of your planned lessons.

The module-level index file will look like this:

## 20.4 Adding a Lesson

To add a lesson to a new or existing module:

- Open the module directory.
- Open the index.rst file (created above in the case of new modules).
- Ensure that the name of the planned lesson is listed underneath the toctree directive, as shown above.
- Create a new file under the module directory.
- Name this file exactly the same as the name you provided in the module's index.rst file, and add the
  extension .rst.

**Muista:** For editing purposes, a .rst file works exactly like a normal text file (.txt).

- To begin writing the lesson, write the markup phrase |LS|, followed by the lesson name.
- In the next line, write a line of 80 equal signs (=).
- Leave a line open after this.
- Write a short description of the lesson's intended purpose.
- Include a general introduction to the subject matter. See the existing lessons in this manual for examples.
- Beneath this, start a new paragraph, beginning with this phrase:

```
**The goal for this lesson:**
```

• Briefly explain the intended outcome of completing this lesson.

• If you can't describe the goal of the lesson in one or two sentences, consider breaking the subject matter up into multiple lessons.

Each lesson will be subdivided into multiple sections, which will be addressed next.

### 20.5 Adding a Section

There are two types of sections: "follow along" and "try yourself".

- A "follow along" section is a detailed set of directions intended to teach the reader how to use a given aspect
  of QGIS. This is typically done by giving click-by-click directions as clearly as possible, interspersed with
  screenshots.
- A "try yourself" section gives the reader a short assignment to try by themselves. It is usually associated with an entry in the answer sheet at the end of the documentation, which will show or explain how to complete the assignment, and will show the expected outcome if possible.

Every section comes with a difficulty level. An easy section is denoted by |basic|, moderate by |moderate|, and advanced by |hard|.

#### 20.5.1 Adding a "follow along" section

- To start this section, write the markup phrase of the intended difficulty level (as shown above).
- Leave a space and then write |FA| (for "follow along").
- Leave another space and write the name of the section (use only an initial capital letter, as well as capitals for proper nouns).
- In the next line, write a line of 80 minuses/dashes (–). Ensure that your text editor does not replace the default minus/dash character with a long dash or other character.
- Write a short introduction to the section, explaining its purpose. Then give detailed (click-by-click) instructions on the procedure to be demonstrated.
- In each section, include internal links, external links and screenshots as needed.
- Try to end each section with a short paragraph that concludes it and leads naturally to the next section, if possible.

#### 20.5.2 Adding a "try yourself" section

- To start this section, write the markup phrase of the intended difficulty level (as shown above).
- Leave a space and then write | TY | (for "try yourself").
- In the next line, write a line of 80 minuses/dashes (–). Ensure that your text editor does not replace the default minus/dash character with a long dash or other character.
- Explain the exercise that you want the reader to complete. Refer to previous sections, lessons or modules if necessary.
- Include screenshots to clarify the requirements if a plain textual description is not clear.

In most cases, you will want to provide an answer regarding how to complete the assignment given in this section. To do so, you will need to add an entry in the answer sheet.

- First, decide on a unique name for the answer. Ideally, this name will include the name of the lesson and an incrementing number.
- Create a link for this answer:

```
:ref:'Check your results <answer-name>'
```

- Open the answer sheet (answers/answers.rst).
- Create a link to the "try yourself" section by writing this line:

```
.. _answer-name:
```

- · Write the instructions on how to complete the assignment, using links and images where needed.
- To end it off, include a link back to the "try yourself" section by writing this line:

```
:ref: 'Back to text <backlink-answer-name>'
```

• To make this link work, add the following line above the heading to the "try yourself" section:

```
.. _backlink-answer-name:
```

Remember that each of these lines shown above must have a blank line above and below it, otherwise it could cause errors while creating the document.

#### 20.6 Add a Conclusion

• To end a lesson, write the phrase | IC | for "in conclusion", followed by a new line of 80 minuses/dashes (-). Write a conclusion for the lesson, explaining which concepts have been covered in the lesson.

### 20.7 Add a Further Reading Section

- This section is optional.
- Write the phrase FR for "further reading", followed by a new line of 80 minuses/dashes (-).
- Include links to appropriate external websites.

#### 20.8 Add a What's Next Section

- Write the phrase | WN | for "what's next", followed by a new line of 80 minuses/dashes (-).
- Explain how this lesson has prepared students for the next lesson or module.
- Remember to change the "what's next" section of the previous lesson if necessary, so that it refers to your new lesson. This will be necessary if you have inserted a new lesson among existing lessons, or after an existing lesson.

## 20.9 Using Markup

To adhere to the standards of this document, you will need to add standard markup to your text.

#### 20.9.1 New concepts

• If you are explaining a new concept, you will need to write the new concept's name in italics by enclosing it in asterisks (\*).

```
This sample text shows how to introduce a *new concept*.
```

#### 20.9.2 Emphasis

- To emphasize a crucial term which is not a new concept, write the term in bold by enclosing it in double asterisks (\*\*).
- Use this sparingly! If used too much, it can seem to the reader that you are shouting or being condescending.

```
This sample text shows how to use **emphasis** in a sentence. Include the punctuation mark if it is followed by a **comma,** or at the **end of the sentence.**
```

#### **20.9.3 Images**

- When adding an image, save it to the folder \_static/lesson\_name/.
- Include it in the document like this:

```
.. image:: /static/training_manual/lesson_name/image_file.extension
:align: center
```

• Remember to leave a line open above and below the image markup.

#### 20.9.4 Internal links

• To create an anchor for a link, write the following line above the place where you want the link to point to:

```
.. _link-name:
```

• To create a link, add this line:

```
:ref: 'Descriptive link text <link-name>'
```

• Remember to leave a line open above and below this line.

#### 20.9.5 External links

• To create an external link, write it out like this:

```
'Descriptive link text <link-url>'_
```

• Remember to leave a line open above and below this line.

#### 20.9.6 Using monospaced text

• When you are writing text that the user needs to enter, a path name, or the name of a database element such as a table or column name, you must write it in monospaced text. For example:

```
Enter the following path in the text box: :kbd:'path/to/file'.
```

#### 20.9.7 Labeling GUI items

• If you are referring to a GUI item, such as a button, you must write its name in *the GUI label format*. For example:

```
To access this tool, click on the :guilabel: 'Tool Name' button.
```

• This also applies if you are mentioning the name of a tool without requiring the user to click a button.

20.9. Using Markup

#### 20.9.8 Menu selections

• If you are guiding a user through menus, you must use the menu  $\rightarrow$  selection  $\rightarrow$  format. For example:

```
To use the :guilabel: 'Tool Name' tool, go to :menuselection: 'Plugins --> Tool Type --> Tool Name'.
```

#### 20.9.9 Adding notes

• You might need to a note in the text, which explains extra details that can't easily be made part of the flow of the lesson. This is the markup:

```
[Normal paragraph.]
.. note:: Note text.
   New line within note.

New paragraph within note.

[Unindented text resumes normal paragraph.]
```

#### 20.9.10 Adding a sponsorship/authorship note

If you are writing a new module, lesson or section on behalf of a sponsor, you must include a short sponsor message of their choice. This must notify the reader of the name of the sponsor and must appear below the heading of the module, lesson or section that they sponsored. However, it may not be an advertisement for their company.

If you have volunteered to write a module, lesson or section in your own capacity, and not on behalf of a sponsor, you may include an authorship note below the heading of the module, lesson or section that you authored. This must take the form This [module/lesson/section] contributed by [author name]. Do not add further text, contact details, etc. Such details are to be added in the "Contributors" section of the Foreword, along with the name(s) of the part(s) you added. If you only made enhancements, corrections and/or additions, list yourself as an editor.

#### 20.10 Thank You!

Thank you for contributing to this project! By so doing, you are making QGIS more accessible to users and adding value to the QGIS project as a whole.

### **Answer Sheet**

## 21.1 Results For Adding Your First Layer

# 21.1.1 Preparation

You should see a lot of lines, symbolizing roads. All these lines are in the vector layer that you just loaded to create a basic map.

Back to text

### 21.2 Results For An Overview of the Interface

# 21.2.1 *Overview* (Part 1)

Refer back to the image showing the interface layout and check that you remember the names and functions of the screen elements.

Back to text



- 1. Save as
- 2. Zoom to layer
- 3. Help
- 4. Rendering on/off
- 5. Measure line

Back to text

## 21.3 Results For Working with Vector Data



There should be five layers on your map:

- places
- water
- buildings
- · rivers and
- roads.

Back to text




All the vector layers should be loaded into the map. It probably won't look nice yet though (we'll fix the ugly colors later).

Back to text

## 21.4 Results For Symbology



- Verify that the colors are changing as you expect them to change.
- It is enough to change only the *water* layer for now. An example is below, but may look different depending on the color you chose.




**Muista:** If you want to work on only one layer at a time and don't want the other layers to distract you, you can hide a layer by clicking in the check box next to its name in the Layers list. If the box is blank, then the layer is hidden.

Back to text

# 21.4.2 Symbol Structure

Your map should now look like this:



If you are a Beginner-level user, you may stop here.


- Use the method above to change the colors and styles for all the remaining layers.
- Try using natural colors for the objects. For example, a road should not be red or blue, but can be gray or black.
- Also feel free to experiment with different Fill Style and Border Style settings for the polygons.

Back to text

# 21.4.3 Symbol Layers

• Customize your *buildings* layer as you like, but remember that it has to be easy to tell different layers apart on the map.


Here's an example:



Back to text




To make the required symbol, you need two symbol layers:




The lowest symbol layer is a broad, solid yellow line. On top of it there is a slightly thinner solid gray line.

• If your symbol layers resemble the above but you're not getting the result you want, check that your symbol levels look something like this:




• Now your map should look like this:



## 21.4.5 Symbol Levels

• Adjust your symbol levels to these values:



- Experiment with different values to get different results.
- Open your original map again before continuing with the next exercise.

Back to text

### 21.5 Results For Attribute Data




The *NAME* field is the most useful to show as labels. This is because all its values are unique for every object and are very unlikely to contain *NULL* values. If your data contains some *NULL* values, do not worry as long as most of your places have names.

### 21.6 Results For The Label Tool

# 21.6.1 Label Customization (Part 1)


Your map should now show the marker points and the labels should be offset by  $2.0\,$  mm: The style of the markers and labels should allow both to be clearly visible on the map:



Back to text


## 21.6.2 Label Customization (Part 2)

One possible solution has this final product:



#### To arrive at this result:

- Use a font size of 10, a Label distance of 1, 5 mm, Symbol width and Symbol size of 3.0 mm.
- In addition, this example uses the *Wrap label on character* option:




• Enter a space in this field and click *Apply* to achieve the same effect. In our case, some of the place names are very long, resulting in names with multiple lines which is not very user friendly. You might find this setting to be more appropriate for your map.


Back to text

### 21.6.3 Using Data Defined Settings

- Still in edit mode, set the FONT\_SIZE values to whatever you prefer. The example uses 16 for towns, 14 for suburbs, 12 for localities and 10 for hamlets.
- Remember to save changes and exit edit mode.
- Return to the *Text* formatting options for the *places* layer and select FONT\_SIZE in the *Attribute field* of the font size data override dropdown:



Your results, if using the above values, should be this:




Back to text


### 21.7 Results For Classification

## 21.7.1 Refine the Classification

• Use the same method as in the first exercise of the lesson to get rid of the borders:




The settings you used might not be the same, but with the values *Classes* = 6 and *Mode* = *Natural Breaks (Jenks)* (and using the same colors, of course), the map will look like this:



### 21.8 Results For Creating a New Vector Dataset




The symbology doesn't matter, but the results should look more or less like this:



Back to text

## 21.8.2 Topology: Add Ring Tool

The exact shape doesn't matter, but you should be getting a hole in the middle of your feature, like this one:




• Undo your edit before continuing with the exercise for the next tool.


Back to text

## 21.8.3 Topology: Add Part Tool

• First select the Bontebok National Park:



• Now add your new part:



• Undo your edit before continuing with the exercise for the next tool.


Back to text



- Use the Merge Selected Features tool, making sure to first select both of the polygons you wish to merge.
- Use the feature with the *OGC\_FID* of 1 as the source of your attributes (click on its entry in the dialog, then click the *Take attributes from selected feature* button):

#### Muista:

If you're using a different dataset, it is highly likely that your original polygon's OGC\_FID will not be 1. Just choose the feature which has an OGC\_FID.




**Muista:** Using the *Merge Attributes of Selected Features* tool will keep the geometries distinct, but give them the same attributes.

Back to text




For the *TYPE*, there is obviously a limited amount of types that a road can be, and if you check the attribute table for this layer, you'll see that they are predefined.

- Set the widget to Value Map and click Load Data from Layer.
- Select roads in the Label dropdown and highway for both the Value and Description options:



• Click Ok three times.

• If you use the *Identify* tool on a street now while edit mode is active, the dialog you get should look like this:




Back to text

### 21.9 Results For Vector Analysis


## 21.9.1 Extract Your Layers from OSM Data


For the purpose of this exercise, the OSM layers which we are interested in are multipolygons and lines. The multipolygons layer contains the data we need in order to produce the houses, schools and restaurants layers. The lines layer contains the roads dataset.


The Query Builder is found in the layer properties:



Using the *Query Builder* against the multipolygons layer, create the following queries for the houses, schools, restaurants and residential layers:








Once you have entered each query, click *OK*. You'll see that the map updates to show only the data you have selected. Since you need to use again the multipolygons data from the OSM dataset, at this point, you can use one of the following methods:


- Rename the filtered OSM layer and re-import the layer from osm\_data.osm, OR
- Duplicate the filtered layer, rename the copy, clear the query and create your new query in the Query Builder.

**Muista:** Although OSM's building field has a house value, the coverage in your area - as in ours - may not be complete. In our test region, it is therefore more accurate to *exclude* all buildings which are defined as anything other than house. You may decide to simply include buildings which are defined as house and all other values that have not a clear meaning like yes.

To create the roads layer, build this query against OSM's lines layer:




You should end up with a map which looks similar to the following:



Back to text

## 

• Your buffer dialog should look like this:



The *Buffer distance* is 1000 meters (i.e., 1 kilometer).

• The *Segments to approximate* value is set to 20. This is optional, but it's recommended, because it makes the output buffers look smoother. Compare this:




The first image shows the buffer with the *Segments to approximate* value set to 5 and the second shows the value set to 20. In our example, the difference is subtle, but you can see that the buffer's edges are smoother with the higher value.


Back to text

## 21.9.3 Distance from Restaurants


To create the new houses\_restaurants\_500m layer, we go through a two step process:

• First, create a buffer of 500m around the restaurants and add the layer to the map:







• Next, select buildings within that buffer area:



• Now save that selection to our new <code>houses\_restaurants\_500m</code> layer:




Your map should now show only those buildings which are within 50m of a road, 1km of a school and 500m of a restaurant:




### 21.10 Results For Raster Analysis




• Set your *DEM (Terrain analysis)* dialog up like this:




### Your result:



Back to text




• Set your *Raster calculator* dialog up like this:



• For the 5 degree version, replace the 2 in the expression and file name with 5.

#### Your results:

• 2 degrees:



• 5 degrees:




### 21.11 Results For Completing the Analysis



- Open the Query Builder by right-clicking on the all\_terrain layer in the Layers list, select the General tab.
- Then build the query "suitable" = 1.
- Click *OK* to filter out all the polygons where this condition isn't met.

When viewed over the original raster, the areas should overlap perfectly:



• You can save this layer by right-clicking on the *all\_terrain* layer in the *Layers list* and choosing *Save As...*, then continue as per the instructions.

Back to text


# 21.11.2 Inspecting the Results

You may notice that some of the buildings in your new\_solution layer have been "sliced" by the *Intersect* tool. This shows that only part of the building - and therefore only part of the property - lies on suitable terrain. We can therefore sensibly eliminate those buildings from our dataset


Back to text




At the moment, your analysis should look something like this:



Consider a circular area, continuous for 100 meters in all directions.




If it is greater than 100 meters in radius, then subtracting 100 meters from its size (from all directions) will result in a part of it being left in the middle.



Therefore, you can run an *interior buffer* of 100 meters on your existing *suitable\_terrain* vector layer. In the output of the buffer function, whatever remains of the original layer will represent areas where there is suitable terrain for 100 meters beyond.


#### To demonstrate:

- Go to  $Vector \rightarrow Geoprocessing\ Tools \rightarrow Buffer(s)$  to open the Buffer(s) dialog.
- Set it up like this:




- Use the *suitable\_terrain* layer with 10 segments and a buffer distance of -100. (The distance is automatically in meters because your map is using a projected CRS.)
- Save the output in exercise\_data/residential\_development/ as suitable\_terrain\_continuous100m.shp.
- If necessary, move the new layer above your original suitable\_terrain layer.

Your results will look like something like this:




- Now use the *Select by Location* tool (*Vector*  $\rightarrow$  *Research Tools*  $\rightarrow$  *Select by location*).
- Set up like this:



• Select features in *new\_solution* that intersect features in *suitable\_terrain\_continuous100m.shp*.

#### This is the result:



The yellow buildings are selected. Although some of the buildings fall partly outside the new suitable\_terrain\_continuous100m layer, they lie well within the original suitable\_terrain layer and therefore meet all of our requirements.


• Save the selection under exercise\_data/residential\_development/ as final\_answer.shp.

Back to text

### 21.12 Results For WMS


## 21.12.1 Adding Another WMS Layer


Your map should look like this (you may need to re-order the layers):




# 21.12.2 Adding a New WMS Server

• Use the same approach as before to add the new server and the appropriate layer as hosted on that server:





• If you zoom into the Swellendam area, you'll notice that this dataset has a low resolution:



Therefore, it's better not to use this data for the current map. The Blue Marble data is more suitable at global or national scales.

Back to text



You may notice that many WMS servers are not always available. Sometimes this is temporary, sometimes it is permanent. An example of a WMS server that worked at the time of writing is the *World Mineral Deposits* WMS

at http://appsl.gdr.nrcan.gc.ca/cgi-bin/worldmin\_en-ca\_ows. It does not require fees or have access constraints, and it is global. Therefore, it does satisfy the requirements. Keep in mind, however, that this is merely an example. There are many other WMS servers to choose from.

Back to text

### 21.13 Results For Database Concepts

# 21.13.1 Address Table Properties

For our theoretical address table, we might want to store the following properties:

House Number Street Name Suburb Name City Name Postcode Country

When creating the table to represent an address object, we would create columns to represent each of these properties and we would name them with SQL-compliant and possibly shortened names:

house\_number street\_name suburb city postcode country

Back to text

## 21.13.2 Normalising the People Table

The major problem with the *people* table is that there is a single address field which contains a person's entire address. Thinking about our theoretical *address* table earlier in this lesson, we know that an address is made up of many different properties. By storing all these properties in one field, we make it much harder to update and query our data. We therefore need to split the address field into the various properties. This would give us a table which has the following structure:

|   |            |  | _ |  | street_name                     |   | 4          |   |             |  |
|---|------------|--|---|--|---------------------------------|---|------------|---|-------------|--|
| 1 | Tim Sutton |  | 3 |  | Buirski Plein<br>Avenue du Roix | İ | Swellendam | İ | 071 123 123 |  |

**Muista:** In the next section, you will learn about Foreign Key relationships which could be used in this example to further improve our database's structure.

Back to text




Our people table currently looks like this:

The street\_id column represents a 'one to many' relationship between the *people* object and the related *street* object, which is in the *streets* table.

One way to further normalise the table is to split the name field into *first\_name* and *last\_name*:

We can also create separate tables for the town or city name and country, linking them to our *people* table via 'one to many' relationships:

An ER Diagram to represent this would look like this:



Back to text



The SQL required to create the correct people table is:

The schema for the table (enter  $\d$  people) looks like this:

Table "public.people"

| Column    | Type                    | Modifiers  |  |  |  |  |
|-----------|-------------------------|--|--|--|--|--|
| id        | integer                 | not null default<br>  nextval('people_id_seq'::regclass) |  |  |  |  |
| name      | character varying(50)   |  |  |  |  |  |
| house_no  | integer                 | not null   |  |  |  |  |
| street_id | integer                 | not null   |  |  |  |  |
| phone_no  | character varying       |  |  |  |  |  |
| Indexes:  |                         |  |  |  |  |  |
| "people_p | key" PRIMARY KEY, btree | (id)   |  |  |  |  |

**Muista:** For illustration purposes, we have purposely omitted the fkey constraint.

Back to text



The reason the DROP command would not work in this case is because the *people* table has a Foreign Key constraint to the *streets* table. This means that dropping (or deleting) the *streets* table would leave the *people* table with references to non-existent *streets* data.

**Muista:** It is possible to 'force' the *streets* table to be deleted by using the *CASCADE* command, but this would also delete the *people* and any other table which had a relationship to the *streets* table. Use with caution!

Back to text



The SQL command you should use looks like this (you can replace the street name with a name of your choice):

```
insert into streets (name) values ('Low Road');
```

Back to text

## 21.13.7 Add a New Person With Foreign Key Relationship

Here is the correct SQL statement:

```
insert into streets (name) values('Main Road');
insert into people (name, house_no, street_id, phone_no)
  values ('Joe Smith', 55, 2, '072 882 33 21');
```

If you look at the streets table again (using a select statement as before), you'll see that the id for the Main Road entry is 2.

That's why we could merely enter the number 2 above. Even though we're not seeing Main Road written out fully in the entry above, the database will be able to associate that with the street\_id value of 2.

Muista: If you have already added a new street object, you might find that the new Main Road has an ID of 3 not 2.

Back to text



Here is the correct SQL statement you should use:

```
select count(people.name), streets.name
from people, streets
where people.street_id=streets.id
group by streets.name;
```

#### Result:

**Muista:** You will notice that we have prefixed field names with table names (e.g. people.name and streets.name). This needs to be done whenever the field name is ambiguous (i.e. not unique across all tables in the database).

Back to text

### 21.14 Results For Spatial Queries

## 21.14.1 The Units Used in Spatial Queries

The units being used by the example query are degrees, because the CRS that the layer is using is WGS 84. This is a Geographic CRS, which means that its units are in degrees. A Projected CRS, like the UTM projections, is in meters.

Remember that when you write a query, you need to know which units the layer's CRS is in. This will allow you to write a query that will return the results that you expect.

Back to text



```
CREATE INDEX cities_geo_idx
  ON cities
  USING gist (the_geom);
```

Back to text

### 21.15 Results For Geometry Construction



```
insert into geometry_columns values ('','public','streets','the_geom',2,4326,
    'LINESTRING');
create index streets_geo_idx
    on streets
    using gist
    (the_geom);
```

# 21.15.2 Linking Tables

```
delete from people;
alter table people add column city_id int not null references cities(id);
(capture cities in QGIS)
insert into people (name, house_no, street_id, phone_no, city_id, the_geom)
   values ('Faulty Towers',
           34,
           3,
           '072 812 31 28',
           'SRID=4326; POINT (33 33)');
insert into people (name, house_no, street_id, phone_no, city_id, the_geom)
   values ('IP Knightly',
           32,
           1,
           '071 812 31 28',
           'SRID=4326; POINT (32 -34)');
insert into people (name, house_no, street_id, phone_no, city_id, the_geom)
   values ('Rusty Bedsprings',
           39,
           1,
           '071 822 31 28',
           1,
           'SRID=4326; POINT (34 -34)');
```

#### If you're getting the following error message:

then it means that while experimenting with creating polygons for the cities table, you must have deleted some of them and started over. Just check the entries in your cities table and use any id which exists.

Back to text

### 21.16 Results For Simple Feature Model



```
create table cities (id serial not null primary key, name varchar(50),
```

```
the_geom geometry not null);
alter table cities
add constraint cities_geom_point_chk
check (st_geometrytype(the_geom) = 'ST_Polygon'::text );
```



### Populate the Geometry\_Columns Table

```
insert into geometry_columns values
    ('','public','cities','the_geom',2,4326,'POLYGON');
```

Back to text



### Adding Geometry

#### Result:

| name         |     | street_name |     | geometry      |  |  |
|--------------|-----|-------------|-----|---------------|--|--|
|              | -+- |             | -+- |               |  |  |
| Roger Jones  |     | High street |     |               |  |  |
| Sally Norman |     | High street |     |               |  |  |
| Jane Smith   |     | Main Road   |     |               |  |  |
| Joe Bloggs   |     | Low Street  |     |               |  |  |
| Fault Towers |     | Main Road   |     | POINT(33 -33) |  |  |
| (5 rows)     |     |             |     |               |  |  |

As you can see, our constraint allows nulls to be added into the database.

Back to text

### CHAPTER 22

### Indeksit ja taulut

- genindex
- modindex
- search